REFER TO DRAWING 892.29.02B

TREES: 3 Quercus robur

70 Acer campestre
90 Corylus avellana
90 Crataegus monogyna
45 Ilex aquifolium
70 Prunus spinosa
45 Rhamnus cathartica
70 Viburnum opulus

PB1/02

TREES: 3 Prunus padus

SUPPLEMENTARY PLANTING
WITHIN VEGETATED AREA (PB1/01)

Pit plant transplants by carefully removing grasses and any ruderal species in a 600mm Ø space per plant. Prepare 300 x 300mm x 300mm deep pit and backfill with topsoil. Surround each transplant with 600mm Ø of bark mulch.
Density: 1 plant per m²

55 Alnus glutinosa
40 Betula pubescens
55 Ilex aquifolium
70 Rhamnus cathartica
40 Sorbus aria
70 Viburnum lantana

TREES: 2 Acer campestre (PB1/01)

TREES: 2 Acer campestre (PB1/01)

TREES: 2 Prunus avium "Plena"

SUB STATION

PB1/01

HEDGE: 22 Prunus "Rotundifolia"

G3

G2

G1

G5

DITCH

DITCH

SOLENT ROAD



1:1250 scale
SITE LAYOUT

TPO GROUP TREE

EXISTING TREE

TREE TO BE REMOVED WITHIN APPLICATION AREA

TREE TO BE REMOVED WITHIN HIGHWAY LAND

PROPOSED TREE

PLANT BED

GRASS AREA

EXISTING VEGETATION TO BE RETAINED

EXISTING VEGETATION TO BE SUPPLEMENTED

WP WATERPOINT

NORTH

0 5 10 15 20
metres

REFER TO LANDSCAPE LAYOUT: 892.10.02B
FOR PLANT SCHEDULES AND SPECIFICATIONS

A 31-07-23 Include field hedgerow.
B 04-08-23 Increase field hedgerow and include supplementary planting on the South boundary.

SOLENT ROAD, HAVANT

PLANTING LAYOUT - SOUTH
Sheet 1 of 3

Scale	Date
1:200 @ A1	JULY 2023
Drawing	**Revision**
892.19.02	B

TALA TERRY ANDERSON LANDSCAPE ARCHITECTS
54 Kenilworth Avenue . Wimbledon . London SW19 7LW Tel: 020-8947 6859
info@terryanderson.co.uk