

PROPOSED RESIDENTIAL DEVELOPMENT  
LAND WEST OF OLD MANOR FARM, SOUTH OF LOWER  
ROAD  
BEDHAMPTON  
HAMPSHIRE

## FLOOD RISK ASSESSMENT & DEVELOPMENT DRAINAGE STRATEGY

BARGATE HOMES LTD

JANUARY 2025

REF: SS/21/0433/6430



## DOCUMENT CONTROL RECORD

### Document Issue:

| Rev | Date     | Issue Status                                     | Prepared by | Checked by |
|-----|----------|--------------------------------------------------|-------------|------------|
| -   | 24.09.21 | First Issue for comment                          | S. Smith    | C. Pendle  |
| A   | 25.07.24 | Updated to new layout                            | S. Smith    | C. Pendle  |
| B   | 30.07.24 | Updated to client's comments                     | S. Smith    | C. Pendle  |
| C   | 31.07.24 | Updated paragraph 3.12                           | S. Smith    | C. Pendle  |
| D   | 13.11.24 | Updated drawings in appendices to current layout | S. Smith    | C. Pendle  |
| E   | 13.11.24 | Updated to correct drainage strategy             | S. Smith    | C. Pendle  |
| F   | 17.01.25 | Added paragraph 4.33 - GIS Floodplain Analysis   | S. Smith    | C. Pendle  |
| G   | 17.01.25 | Updated paragraph 4.33 - GIS Floodplain Analysis | S. Smith    | C. Pendle  |



## Contents

|                                                    |    |
|----------------------------------------------------|----|
| 1. Executive Summary.....                          | 1  |
| 2. Introduction.....                               | 2  |
| 3. The Development Site.....                       | 3  |
| 4. Flood Risk Assessment.....                      | 6  |
| 5. Existing and Proposed Surface Water Runoff..... | 13 |
| 6. Surface Water Drainage Strategy.....            | 15 |
| 7. Water Quality and Pollution Prevention.....     | 17 |
| 8. Foul Water Drainage Strategy.....               | 20 |

## Appendices

Appendix A – Site Layout

Appendix B – Topographical Survey

Appendix C – Foul and Surface Water Drainage Strategy

Appendix D – Pre / Post Development Runoff and Storage Calculations

Appendix E – Public Sewer Records

Appendix F – SUDS Compatibility Matrix

Appendix G – SUDS Management and Maintenance Plan

## References

Environment Agency Flood Map Information © and database right [www.environment\\_agency.gov.uk](http://www.environment_agency.gov.uk)

Contains British Geological Survey materials © NERC (2018)

National Planning Policy Framework (Department for Communities and Local Government, March 2012)

PPG Flood risk and coastal change (Department for Communities and Local Government, March 2014)

Havant Borough Council Strategic Flood Risk Assessment, 2018 (SFRA) (HBC, November 2018)

Havant Borough Council Partnership for South Hampshire Level 1 Strategic Flood Risk Assessment, 2024 (SFRA) (AECOM, February 2024)

Hampshire County Council Preliminary Flood Risk Assessment (PFRA) (HCC, April 2011)



## 1 Executive Summary

|                  |                                  |                                                                                                         |
|------------------|----------------------------------|---------------------------------------------------------------------------------------------------------|
| SITE INFORMATION | CLIENT                           | Bargate Homes Ltd                                                                                       |
|                  | SITE NAME                        | Phase 2 Manor Farm                                                                                      |
|                  | SITE LOCATION                    | SU 69849 05991<br>Bedhampton<br>Havant<br>Hampshire                                                     |
|                  | SITE AREA                        | 3.67 ha                                                                                                 |
|                  | CURRENT LAND USE                 | Greenfield – Arable / Agricultural grassland                                                            |
|                  | PROPOSED LAND USE                | No.43 Residential Dwellings (Class C3A)                                                                 |
|                  | SITE GEOLOGY – Superficial       | River Terrace Deposit – Sand, Silt, Clay                                                                |
|                  | SITE GEOLOGY - Bedrock           | Lewis Nodular Chalk, Seaford Chalk, Newhaven Chalk, Culver Chalk and Portsdown Chalk Formations – Chalk |
|                  | SOIL INFILTRATION RATE           | Superficial: Insufficient. Underlying Chalk: $1 \times 10^{-4}$ m/s                                     |
|                  | GROUNDWATER LEVELS               | ~3.8m Below Ground Level                                                                                |
|                  | GROUNDWATER SPZ / AQUIFER        | SPZ 1 close by/ Principle (Bedrock), Superficial (Secondary A) Vulnerable                               |
|                  | GROUND CONTAMINATION             | TBC – None anticipated                                                                                  |
|                  |                                  |                                                                                                         |
| FLOOD RISK       | ENVIRONMENT AGENCY FLOOD ZONE    | Flood Zone 1 - Lowest Risk < 0.1% (<1:1000)                                                             |
|                  | FLUVIAL (RIVERS & WATERCOURSES)  | Not a risk                                                                                              |
|                  | PLUVIAL (SURFACE WATER)          | Not a risk                                                                                              |
|                  | GROUNDWATER                      | Not a risk                                                                                              |
|                  | EXISTING/PROPOSED SEWERS & MAINS | Not a risk                                                                                              |
|                  | ARTIFICIAL                       | Not a risk                                                                                              |
|                  | TIDAL                            | Not a risk                                                                                              |
|                  |                                  |                                                                                                         |
| FOUL & SURFACE   | PROPOSED SURFACE WATER STRATEGY  | Gravity to ditch                                                                                        |
|                  | PROPOSED SUDS TYPE               | Swales, Filter Trenches, Reed Bed, Attenuation Basin                                                    |
|                  | EXISTING SW PEAK FLOW RATE       | Greenfield QBar: 3.3 l/s                                                                                |
|                  | PROPOSED SW PEAK FLOW RATE       | 3.3 l/s                                                                                                 |
|                  | FOUL WATER STRATEGY              | Pumped to Phase 1 Foul Sewer                                                                            |
|                  | EXISTING FW PEAK FLOW RATE       | N/A                                                                                                     |
|                  | PROPOSED FW PEAK FLOW RATE       | 2.0 l/s (SFA 4000 l/unit/d) for 43 Units                                                                |
|                  |                                  |                                                                                                         |
| MISC             | FURTHER INVESTIGATIONS           | N/A                                                                                                     |

---

## 2 Introduction

### 2.1 Scope

Bargate Homes is seeking outline planning permission for the construction of up to No.43 residential dwellings, associated landscaping, open space and allotments with access from Lower Road. The 36,709m<sup>2</sup> (3.67ha) site is located at land adjacent to Lower Road, Bedhampton. Refer to Appendix A for site layout.

### 2.2

MJA Consulting has been appointed to provide a Flood Risk Assessment & Drainage Strategy suitable to submit as part of the planning application for the disposal of foul and surface water from the proposed development.

### 2.3 Report Structure

The National Planning Policy Framework (NPPF) and the Flood Risk and Coastal Planning Practice Guidance (PPG) is the current guidance on development and flood risk in England and Wales. The Flood Risk technical guidance for the National Planning Policy Framework requires a Flood Risk Assessment (FRA) to be carried out on sites over 1ha to consider all potential forms of flooding including that from river, sea, estuarial, land drainage, groundwater, overland flow, surface water run-off, sewer systems, and artificial water bodies (lakes, reservoirs, canals etc.) to both the development site and to offsite parties and land.

### 2.4

This report will take the structure of a 'Flood Risk Assessment' in accordance with the National Planning Policy Framework, the Flood Risk and Coastal Planning Practice Guidance, Environment Agency's Flood Risk Assessment Guidance and CIRIA Report 624 'Development and Flood Risk.

### 2.5

The objectives of this report are:

- To confirm whether the proposed development site is affected by current or anticipated future flooding from all sources for the lifetime of the site.
- To confirm that this development will not increase the risk of flooding to any offsite properties and land or increase the population within a floodplain.
- To undertake calculations to establish the foul and surface water runoff rates from the existing site and to assess the potential foul and surface water runoff from the proposed development.
- To detail a suitable strategy for the management of foul and surface water generated from the proposed development allowing for future climate change.
- To satisfy the approving planning authority that the most sustainable foul and surface water drainage solutions have been considered, in line with Environment Agency guidance, The Building Regulations (Document H 2002) and government legislation such as the Flood and Water Management Act 2010 (Defra) and The National Planning Policy Framework (NPPF & PPG).

### 3 The Development Site

Figure 1: Site location




Image courtesy of: Bing Maps, 2021 Microsoft Corporation Image courtesy of Ordnance Survey

Figure 2: Development boundary



Image courtesy of: Google Maps, 2021 Microsoft Corporation

---

### 3.1 Site Location and Description

The application site is located at land south west of Bedhampton in Hampshire and directly south west of Phase 1 of the development. The site is centred on National Grid Reference SU 69849 05991 and is bound by Lower Road to the north and the railway line to the south. The A27/A3(M) lies to the west and arable land to the east of the site. The 36,709m<sup>2</sup> (3.67ha) parcel of land comprises an arable field.

### 3.2 Topography

A topographical survey of the site was undertaken by Encompass Surveys in March 2021 which indicates the site falls to the south at 1 in 55 with levels ranging from 8.19mAOD to 3.73mAOD (metres above Ordnance Datum). Refer to Appendix B for a Topographical Survey of the existing site.

### 3.3 Geology

Information published by the British Geological Society (BGS) indicates the underlying geology at the site as Lewis Nodular Chalk, Seaford Chalk, Newhaven Chalk, Culver Chalk and Portsdown Chalk Formations – Chalk, with superficial deposits of River Terrace Deposits – Sand, Silt and Clay.

3.4 Ground investigations were carried out in September 2017 for the adjacent phase 1 site and confirmed that site is underlain by sandy, silty clay over chalk substrata. The Clay is circa 1-3m thick. The clay is at its thinnest in the south west corner. It is assumed that the geology underlaying this phase 2 land is of similar nature.

### 3.5 Soil Permeability

Soil infiltration testing in accordance BRE 365 methodology was carried out in eight trial pits On the adjacent phase 1 site. The tests failed to achieve 75% drain and therefore failed to comply with BRE 365 “soakaway design”. Additional testing in the chalk just below the clay layer also showed low insufficient infiltration rates. Falling head tests in boreholes circa 14-15m below ground level showed higher soakage rates of  $1.4 \times 10^{-4}$  m/s, likely due to fissures in the chalk. It is also assumed that the infiltration rates will be similar on the phase 2 land.

### 3.6 Groundwater

Groundwater levels were taken during the intrusive investigation on the phase 1 parcel. These tests were carried out in 2017, 2018 and 2019 during and after the winter recharge periods when groundwater levels are typically at their maximum.

3.7 Groundwater was encountered at various depths across the site but on average was 3.8m BGL, with a maximum level recorded at 3.52m BGL. Due to the topographical differences between the parcels, it is assumed that groundwater at phase 2 will be at least 2m below ground level.

3.8 Historic BGS borehole records in the *vicinity* of the site are available and show the highest water level as circa 1.2m BGL.

---

### 3.9 Hydrogeology

The Environment Agency's mapping website (<http://magic.defra.gov.uk/MagicMap.aspx>) has classified the site as not within a Source Protection Zone but it is located 250m south (downstream) of a Zone 1 Source Protection Zone. The flow of water from the site is away from the abstraction point, towards the coast.

3.10 The bedrock Chalk formations are classified as 'Principle' aquifers. These are layers of rock that provide a high level of water storage. They may support water supply and/or river base flow on a strategic scale.

3.11 The superficial deposits are classified as a 'Secondary A' aquifer. These are permeable layers of rock that can support water supplies on a local rather than strategic scale. They may be an important source for base flows to rivers.

### 3.12 Hydrology and existing site drainage characteristics

The existing site is undeveloped grassland, as such rainfall that lands on the site firstly infiltrates directly at source and into the underlying soils. It is likely the site has relatively poor surface water drainage with some overland flow.

3.13 The closest watercourse is located approximately 85m east of the site and the site is located approximately 730m north of Langstone Harbour.

### 3.14 Ground Contamination

The available environment data does not indicate the presence of any significant sources of contamination risk on site and no visual or olfactory evidence of soil contamination was identified during a site walkover.

---

## 4 Flood Risk

4.1 The assessment of flood risk to the site requires that all potential forms of flooding are considered. In accordance with the Environment Agency's Flood Risk Assessment Guidance, NPPF, PPG and CIRIA Report 624. The sources of flooding to be assessed include tidal, fluvial (rivers, streams and watercourses), pluvial (overland rainfall runoff), groundwater, artificial sources (canals and reservoirs) and existing / proposed sewerage and water mains infrastructure.

### 4.2 History of Flooding

During the data collection process it is important to consider the information which already exists for the site location with respect to flood risk. The main sources of data for flood risk and recorded incidents of flooding for this site has been the *Havant Borough Council Strategic Flood Risk Assessment (SFRA) (AECOM, February 2024)* and the *Hampshire County Council Preliminary Flood Risk Assessment (PFRA) (HCC, April 2011)*. Additional information has been obtained from The Environment Agency, British Society Chronology of Extreme Hydrological Events, local news and media outlets.

4.3 Within the SFRA/PRFA studies, consultation was carried out with all appropriate authorities and organisations including the Environment Agency, Southern Water, Havant Borough Council and local community stakeholders to identify known or perceived problem areas with respect to flooding.

4.4 With reference to the above, and in the context of the proposed development, there are no historic issues of flooding from the following potential sources including:


- Fluvial (Rivers)
- Tidal.
- Groundwater.
- Pluvial (Surface water runoff).
- Existing foul, storm and combined sewers or potable water main infrastructure.
- Artificial infrastructure.

### 4.5 Fluvial

The closest stream, also a main river classification, to the site runs north to south ~340m to the east and flows into Langstone Channel and the Solent. The Environment Agency confirms that no incidents of flooding from main rivers or ordinary watercourses have been recorded within the site boundary.

4.6 The Environment Agency (EA) is the principal flood risk management operating authority in England. The EA have carried out a national flood risk assessment (NaFRA) which assesses the probability of flooding to land from all main rivers in England. The results of this modelling are combined and calibrated against data from recorded flood events to produce the Environment Agency's Flood Zone Map (Figure 3).

**Figure 3: Extract from Environment Agency River and Sea Water Flood Map (2025)**



Contains Environment Agency information © Environment Agency 2025

**Key:**

 Main Rivers

**Dark Blue** : (Flood Zone 3)

Shows the area that could be affected by flooding, either from rivers or the sea, if there were no flood defences. This area could be flooded: from the sea by a flood that has a 0.5% (1 in 200) or greater chance of happening each year, or from a river by a flood that has a 1% (1 in 100) or greater chance of happening each year.

**Light Blue** : (Flood Zone 2)

Shows the additional extent of an extreme flood from rivers or the sea.

These outlying areas are likely to be affected by a major flood, with up to a 0.1% (1 in 1000) chance of occurring each year.

These two colours show the extent of the natural floodplain if there were no flood defences or certain other manmade structures and channel improvements.

**Clear** : (Flood Zone 1)

Shows the area where flooding from rivers and the sea is very unlikely.

There is less than a 0.1% (1 in 1000) chance of flooding occurring each year.

- 4.7 The latest Environment Agency 'Flood Zone Map' (March 2019) indicates the site is located within the lowest risk category - Flood Zone 1. 'Flood Zone 1' is land assessed as having a less than 1 in 1000 (<0.1%) annual probability of flooding from a main river in each year and is not within an area of recorded river flooding.
- 4.8 Hampshire County Council as the Lead Local Flood Authority (LLFA) are responsible for assessing the flood risk from all other ordinary watercourses (non-main rivers) in the Bedhampton area, with this information detailed in the Havant SFRA. This study has concluded that the site is not at risk of flooding from all ordinary watercourses within the locality of the development.

- 4.9 It is demonstrated that safe and dry access and egress at the site is achievable to a publicly accessible location outside the 1:100 year (plus climate change) flood event extent, in accordance with DEFRA Report FD2320/TR2 - 'Flood Risk Assessment Guidance for New Developments'.
- 4.10 **Tidal**  
Lying 1km from the coast, parts of Bedhampton and its local river networks encounter a risk from tidal flooding. However, the site itself is not at risk of tidal flooding as confirmed by the SFRA, PFRA and the Environment Agency.
- 4.11 **Surface Water**  
The 'FMfSWF' (Flood Map for Surface Water Flooding) presented within the SFRA confirms that no incidents of flooding from surface water runoff have been recorded within the site boundary. Since the SFRA/PFRA reports were produced, no further evidence of surface water flooding at the site has been identified.
- 4.12 The Environment Agency's 'uFMfSW' (updated Flood Map for Surface Water) (Figure 4) is a theoretical assessment of potential overland flow paths, ground levels and drainage systems using information from Hampshire County Council as the LLFA to indicate areas that may be susceptible to surface water flooding.

**Figure 4: Extract from Environment Agency Surface Water Flood Map (2025)**



Contains Environment Agency information © Environment Agency 2025

**Key:**

-  High (Greater than 1:30(3.3%) chance of flooding)
-  Medium (Between 1:100(1%) and 1:30(3.3%) chance of flooding)
-  Low (Between 1:1000 (0.1%) and 1:100 (1%) chance of flooding)
-  Very Low (Less than 1:1000 (0.1%) chance of flooding)

- 
- 4.13 This map indicates that the majority of the existing site has a 'very low' (less than a 1:1000 or 0.1%) risk of flooding from surface water runoff. There is a small section of southwest of the site that has a 'low' to 'medium' (1:1000 to 1:30) risk of flooding from surface water runoff. This is correlated with the low point on the site.
- 4.14 The implementation of a sensible layout and robust SuDS scheme to collect, attenuate and convey the surface water runoff from the proposed development will mitigate any residual risk of surface water flooding to the site in its developed state.
- 4.15 **Groundwater**  
The PFRA, SFRA and the Environment Agency confirm that no recorded events of groundwater flooding have been identified at or within the vicinity of the site.
- 4.16 **Artificial Sources**  
With reference to the SFRA/PRFA there have been no recorded incidents of flooding to the site or surrounding areas from artificial sources.
- 4.17 There are no additional artificial sources of flooding, such as that from canals, reservoirs and sewage treatment works within a 1 km radius of the site.
- 4.18 **Overland Flood Flow / Exceedance**  
The occurrence of overland flooding at the site due to an extreme rainfall event exceeding the design capacity of the drainage system and SuDS, or a failure of the associated flow controls have been considered both during the construction and operational phase of the development.
- 4.19 If SuDS or the piped drainage system becomes overwhelmed by exceptional rainfall then exceedance routes are proposed to protect people and property by providing unobstructed overland flow routes across the development.
- 4.20 The design levels of hard paved and landscaped areas will aim to contain and convey flood flows through areas of the site to cause minimum flood risk to properties and residents such as parking areas and low-lying open space.
- 4.21 All proposed attenuation features within the development are designed to manage the 1 in 100 year return storm (1% chance of occurrence each year) plus an extra allowance of 40% for the potential increase in peak rainfall predicted up to 2115.
- 4.22 Any residual risk of overland flooding to properties is to be mitigated by the provision of raised property slab levels a minimum of 150mm above surrounding ground level.
- 4.23 The described protection measures ensure that properties both within the proposed development and any offsite parties and land will not be affected by overland runoff in the event of a reasonably extreme rainfall event exceeding the design storm or a failure or a blockage of the SuDS structures within the system.

---

#### 4.24 Existing Sewers & Water Mains

The SFRA confirms that for the area in which the site lies, there have been no incidents of flooding from sewers in the last 10 years.

4.25 With reference to the Southern Water flood register; there have been no recorded incidents of flooding from the existing foul and surface water sewers or potable water mains within the vicinity of the development.

4.26 With reference to Southern Water records and engineering drawings for the surrounding development there is a 225mm foul water sewer that runs along Lower Road to the north of the site.

4.27 Southern Water will be consulted to confirm that there is adequate capacity for the proposed development flows. The proposed development will have a 'no detriment' impact on the local foul sewer system and does not create an increase in flood risk.

#### 4.28 Proposed Site Drainage

A Flood Risk Assessment requires that an evaluation of all proposed artificial drainage systems and infrastructure within, or in close proximity to the site is carried out. In the context of this development, the following systems are to be installed which need to be assessed in terms of potential flooding through the capacity of the systems being exceeded or the structural, hydraulic, mechanical or operational failure of the system occurring during the lifetime of the development:

- Piped foul water sewers, manholes and potable water mains.
- SuDS for the temporary conveyance and attenuation of surface water.
- Foul water pumping station and associated rising main.

4.29 All adoptable foul and surface water drains, sewers and manholes will be designed and constructed to the Sewers for Adoption 7<sup>th</sup> edition with all private drainage constructed in accordance with *The Building Regulations Part H, BS EN 752 or BS EN 12056-2* as appropriate, ensuring adequate design capacity and robust structural integrity for the

lifetime of the development. This will not only prevent the risk of flooding to both the development and offsite parties, but will avoid the potential contamination of groundwater by preventing the ingress of groundwater into the pipework and egress of sewage into the underlying soils.

4.30 All SuDS within the drainage system will be sized to manage the runoff from the exceptionally rare 1 in 100 storm event (1% AEP), plus an additional 40% allowance for predicted future climate change effects (in accordance with EA recommendations up to the year 2115).

4.31 The new development as a whole must not create or exacerbate existing flood risk elsewhere and in particular to properties, land and highways downstream of the site. During the design of the proposed development careful consideration has been given to the most sustainable method of surface water disposal and strict controls have been imposed to limit the peak rate and volume of runoff generated from the developed site.


- 4.32 All surface water runoff from impermeable areas on the proposed development will be and safely disposed at a controlled rate to mimic the existing natural runoff regime for the undeveloped greenfield site. This will ensure that the risk of flooding to properties and land downstream of the site will not increase as a result of this proposed development.

4.33 **GIS Floodplain Analysis**

The Partnership for South Hampshire Level 1 Strategic Flood Risk Assessment (2024) undertakes floodplain analysis to consider how the extent of flood zone 3 may be impacted by climate change. Additional water depths of 300mm and 600mm were added to this water surface to provide an indication of those areas of floodplain that could become flooded if the water level were to increase. This mapping does not show the expected impacts of specific climate change predictions, rather it highlights areas which could be sensitive to an increase in flood level.

- 4.34 This analysis identified ‘areas that may be sensitive to change in water level’ which are outlined in the Figure 11 maps within the SFRA. The mapping shows the site is sensitive to a change in water level by circa. 300mm. Figure 5 shows the site boundary in relation to the sensitivity zones and the fluvial flood risk (SFRA, 2024).

**Figure 5: Extract from sensitivity mapping Figure 11C (SFRA, 2024)**



Contains Environment Agency information © Environment Agency 2024

- 4.35 From the topographic survey and Ordinance Survey data it is evident that general area falls from north to south, with the lowest level in the southern corner of the site at 3.70 mAOD. The fluvial flood risk areas, as shown in figure 5, lie circa 300m to the east of the site. Based on Ordinance Survey data these flood zones and their associated watercourses generally lie at a lower level than the site itself. In the absence of detailed levels of the flood zones, a worst-case scenario of 3.70 mAOD for the extent of flood zone 2 and 3 is assumed.

- 
- 4.36 An additional 300mm of sensitivity would create a level of 4.00 mAOD. The lowest proposed finish floor level onsite is 5.50 mAOD. It can be assumed that the site lies at least 1.5m above the sensitivity level of any fluvial flood risk. Therefore, it can be concluded that the developable area of the site is not at risk of flooding.
- 4.37 **Sequential Test**  
The flood risk technical guidance to the National Planning Policy Framework (NPPF) categorises residential developments as 'More Vulnerable' within the risk classification. 'More vulnerable' developments located within Flood Zone 1 are considered appropriate under the NPPF.
- 4.38 The NPPF guidance states that planning authorities should complete a risk based 'Sequential Test' at all stages of the planning process, to steer new development to areas with the lowest probability of flooding. Under the requirements of the 'Sequential Test' and as the proposed development is already located within Flood Zone 1 (lowest risk), there are no more suitable, developable and deliverable alternative sites, better located from a flood risk perspective which could accommodate the proposed development.

## 5 Existing and Proposed Site Runoff

- 5.1 This section aims to calculate the estimated peak rate and volume of surface water runoff from the existing site. These discharge figures are then used to establish the post-development constraints to inform the preliminary design of the site surface water drainage strategy.

### 5.2 Catchment Areas

The existing and proposed permeable and impermeable areas are listed in the table below.

| Site Catchment     | Impermeable         | Permeable             | Total                 |
|--------------------|---------------------|-----------------------|-----------------------|
| Existing Site Area | 0 m <sup>2</sup>    | 36,709 m <sup>2</sup> | 36,709 m <sup>2</sup> |
| Proposed Site Area | 9238 m <sup>2</sup> | 27,471 m <sup>2</sup> | 36,709 m <sup>2</sup> |

- 5.3 This development represents an overall approximate increase of 9238 m<sup>2</sup> in impermeable area post development.

### 5.4 Existing Surface Water Runoff Peak Runoff Rate & Volume (Greenfield)

An assessment of the estimated current greenfield runoff rate has been carried out using the Institute of Hydrology Report 124 (QBar) methodology.

#### Catchment: 0.92ha (FSR)

|                 |                      |
|-----------------|----------------------|
| 1 in 1 year     | 2.8 l/s              |
| QBAR            | 3.3 l/s              |
| 1 in 30 year    | 7.4 l/s              |
| 1 in 100 year   | 10.5 l/s             |
| Volume 100y 6hr | 291.4 m <sup>3</sup> |

- 5.5 Refer to Appendix D for calculations. A 10% allowance for urban creep has been included in the calculations.

### 5.6 Post Development Surface Water Runoff Peak Runoff Rate & Volume

The procedure for surface water management in accordance within 'Rainfall runoff management for developments' (DEFRA/EA Report – SC030219 E, 2013) states; *"For the range of annual flow rate probabilities up to and including the 1% (1 in 100 year) annual exceedance probability event including an appropriate allowance for climate change, the post-developed rate of run-off into a watercourse, sewer, or other receiving water body, should be no greater than the existing pre-developed rate of run-off for the same event"*.

- 5.7 The National Planning Policy Framework requires that consideration is given to the effect of climate change on the surface water flows generated by any new development. Table 2 of the NPPF - Flood Risk Assessments: Climate Change Allowances – Detailed Guidance (Feb 2016), specifies that an assessment of a 40% increase in rainfall intensity allowance is made when calculating post development runoff rates for residential developments.

- 
- 5.8 The additional volume of runoff generated from a site should also be limited to the greenfield runoff volume where possible. Where infiltration cannot be utilised to dispose of the additional volume; *“The limiting discharge for any return period up to the 1% AEP (1 in 100 year) event including climate change, shall not be greater than the mean annual peak rate of runoff for the greenfield site – QBar or 2 l/s/ha, whichever is the greatest”*.
- 5.9 As a result of this development and the increase in impermeable areas, the peak rate and volume of surface water that could potentially runoff the proposed site if not effectively managed, could be greater than in its current undeveloped state.
- 5.10 To mitigate this potential increase, it is proposed that all surface water runoff from impermeable areas on the proposed residential development will be attenuated on site and discharged via infiltration.
- 5.11 Where possible permeable paving will be utilised on driveways and shared parking areas. This will function as under-drained, sealed-tank systems and discharge to the positive drainage network. Swales, reed beds and attenuation basins will also serve as additional attenuation and water quality treatment components.

---

## 6 Surface Water Drainage Strategy

- 6.1 The National Planning Policy Framework (NPPF) requires that developments do not exacerbate flood risks both to the development site and to offsite parties and land, which means there is a need to control surface water drainage and overland runoff to ensure there are no increases in peak rates and volumes of runoff as a result of the development.
- 6.2 Environment Agency guidance and government legislation such as the Flood and Water Management Act (Defra 2010) requires surface water drainage strategies for new developments to be in accordance with the ideals of ‘sustainable development’ via the provision of Sustainable Drainage Systems (SuDS).
- 6.3 SuDS are more sustainable than conventional drainage methods because they can mitigate many of the adverse effects of urban stormwater runoff on the environment. This can be achieved through reducing peak runoff rates and volumes to sewer networks and watercourses, reducing the risk of downstream flooding.
- 6.4 The Building Regulations Document H (2015) details the appropriate hierarchy of potential methods for disposing surface water from a development:
1. A soakaway or some other adequate infiltration system, or where that is not practicable;
  2. A watercourse, or where that is not possible;
  3. A sewer.
- 6.5 Soil permeability rates for the superficial clay are insufficient to use conventional infiltration methods to disposing the surface water runoff generated from the proposed development.
- 6.6 There is a watercourse to the south-west of the development site suitable to discharge to.
- 6.7 This site lies with Southern Water’s service region. With reference to sewer records, there are dedicated surface water sewers along the northern boundary of the site but would require pumping to reach them.
- 6.8 Therefore, it is proposed to utilise a dry detention basin with a discharge to the watercourse to dispose of surface water runoff from the proposed development’s hard standing areas including roofs, driveways and roads.
- 6.9 The surface water network will include swales; a reed bed and an attenuation basin, which will all serve as conveyance, storage, and water quality treatment.
- 6.10 Drainage from house and garage roofs, driveways and parking courts, carriageways and footways will drain to swales which convey water to reed beds in the southern landscaped area of the site.
- 6.11 The attenuation basin which will be dry when not receiving storm water and will attenuate large return period storms via restricted outflow. Infiltration to ground will also occur gradually within the swales and base of the attenuation basin. Although no infiltration will be modelled in the surface water calculations.

- 
- 6.12 Any exceedance overflow will overtop the basin and flow to the southwest at a rate far lower than the predevelopment greenfield run off for a large return period storm.
- 6.13 A 10% allowance for urban creep has been included in the calculations.
- 6.14 The total storage requirement provided by the attenuation basins is 955m<sup>3</sup>. This will provide storage onsite to manage the 1:100year (1% AEP) storm event, plus an extra allowance of 40% for the predicted potential increase in peak rainfall up to 2115.
- 6.15 Following the drainage hierarchy, infiltration would be the first method of disposal for the runoff. However, infiltration tests proved insufficient to utilise soakaway features at shallow depths. Deep borehole soakaways are also discouraged. There is a watercourse that lies to the south-west corner of the site, but not within the site boundary, which is culverted under the railway line. This watercourse runs north to south. The site naturally drains to this ditch via overland flow and field drains. Discharging the sites' runoff to this ditch would mimic greenfield conditions.
- 6.16 The ditch is adjacent to the site boundary with various field drains from site outfalling along its length. These perforated plastic drainpipes are 50mm and 75mm diameter which are too small and unsuitable to utilise as part of the onsite drainage system. Therefore, it is proposed to utilise overland flow across a short distance from the site boundary into the ditch, mimicking greenfield conditions. The control chamber following the basin will discharge into a 110m swale leading down to the south-west corner of the site. The downstream end of the swale contains a small basin with a permanently wet depth, as well as weir in the form of a 1m wide and 0.4m cut into the bank. This weir allows the maximum discharge of 3.3l/s to spill out and into the ditch.
- 6.17 All drains and manholes/inspection chambers will be designed and constructed in accordance with the Building Regulations Part H and BS EN 752, ensuring adequate capacity and robust structural integrity for the lifetime of the development. This will ensure that no polluted discharge from the drainage system to ground will take place.

## 7 Water Quality and Pollution Prevention

- 7.1 The proposed SuDS scheme has been designed to mitigate against the contamination of the receiving watercourse. The CIRIA SuDS Manual 2015 details an approach for establishing the hazard posed by the intended land use activities and the extent to which the proposed SuDS components can reduce and mitigate the contamination risk to the receiving waterbody.
- 7.2 Referring to Table 26.2 – ‘Pollution hazard indices for different land use classifications’ the proposed development and land use results in a low pollution hazard, therefore a ‘Simple Index’ method can be used to make a qualitative assessment of the proposed SuDS management.

**Table 1: Table 26.2 – ‘Pollution hazard indices for different land use classifications’ CIRIA C753, 2015**

| <b>TABLE 26.2 Pollution hazard indices for different land use classifications</b>                                                                                                                                                        |                               |                                     |                                                                            |                     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------|-------------------------------------|----------------------------------------------------------------------------|---------------------|
| <b>Land use</b>                                                                                                                                                                                                                          | <b>Pollution hazard level</b> | <b>Total suspended solids (TSS)</b> | <b>Metals</b>                                                              | <b>Hydrocarbons</b> |
| Residential roofs                                                                                                                                                                                                                        | Very low                      | 0.2                                 | 0.2                                                                        | 0.05                |
| Other roofs (typically commercial/ industrial roofs)                                                                                                                                                                                     | Low                           | 0.3                                 | 0.2 (up to 0.8 where there is potential for metals to leach from the roof) | 0.05                |
| Individual property driveways, residential car parks, low traffic roads (eg cul de sacs, homezones and general access roads) and non-residential car parking with infrequent change (eg schools, offices) ie < 300 traffic movements/day | Low                           | 0.5                                 | 0.4                                                                        | 0.4                 |

### Roof Runoff:

*Total SuDS mitigation index  $\geq$  pollution hazard index (for each contaminant type)*

*For the development site: TSS = 0.2, Metals = 0.2, Hydrocarbons = 0.05*

### Driveway / Parking / Road Runoff:

*Total SuDS mitigation index  $\geq$  pollution hazard index (for each contaminant type)*

*For the development site: TSS = 0.5, Metals = 0.4, Hydrocarbons = 0.4*

**Table 2 - Table 26.3 – ‘Indicative SuDS mitigation indices for discharge to surface waters’ CIRIA C753, 2015**

| <b>TABLE 26.3 Indicative SuDS mitigation indices for discharges to surface waters</b> |                                                                                                                                                                                                                                                    |               |                     |  |
|---------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|---------------------|--|
| <b>Type of SuDS component</b>                                                         | <b>Mitigation indices<sup>1</sup></b>                                                                                                                                                                                                              |               |                     |  |
|                                                                                       | <b>TSS</b>                                                                                                                                                                                                                                         | <b>Metals</b> | <b>Hydrocarbons</b> |  |
| Filter strip                                                                          | 0.4                                                                                                                                                                                                                                                | 0.4           | 0.5                 |  |
| Filter drain                                                                          | 0.4 <sup>2</sup>                                                                                                                                                                                                                                   | 0.4           | 0.4                 |  |
| Swale                                                                                 | 0.5                                                                                                                                                                                                                                                | 0.6           | 0.6                 |  |
| Bioretention system                                                                   | 0.8                                                                                                                                                                                                                                                | 0.8           | 0.8                 |  |
| Permeable pavement                                                                    | 0.7                                                                                                                                                                                                                                                | 0.6           | 0.7                 |  |
| Detention basin                                                                       | 0.5                                                                                                                                                                                                                                                | 0.5           | 0.6                 |  |
| Pond <sup>4</sup>                                                                     | 0.7 <sup>3</sup>                                                                                                                                                                                                                                   | 0.7           | 0.5                 |  |
| Wetland                                                                               | 0.8 <sup>3</sup>                                                                                                                                                                                                                                   | 0.8           | 0.8                 |  |
| Proprietary treatment systems <sup>5,6</sup>                                          | These must demonstrate that they can address each of the contaminant types to acceptable levels for frequent events up to approximately the 1 in 1 year return period event, for inflow concentrations relevant to the contributing drainage area. |               |                     |  |

**Table 3 - Table 26.4 – ‘Indicative SuDS mitigation indices for discharge to groundwater’ CIRIA C753, 2015**

| <b>TABLE 26.4 Indicative SuDS mitigation indices for discharges to groundwater</b>                                                                                                                                                                                                                                                          |  |                                                                                                                                                                       |               |                     |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|---------------------|
| <b>Characteristics of the material overlying the proposed infiltration surface, through which the runoff percolates<sup>1</sup></b>                                                                                                                                                                                                         |  | <b>TSS</b>                                                                                                                                                            | <b>Metals</b> | <b>Hydrocarbons</b> |
| A layer of dense vegetation underlain by a soil with good contaminant attenuation potential <sup>2</sup> of at least 300 mm in depth <sup>3</sup>                                                                                                                                                                                           |  | 0.6 <sup>4</sup>                                                                                                                                                      | 0.5           | 0.6                 |
| A soil with good contaminant attenuation potential <sup>2</sup> of at least 300 mm in depth <sup>3</sup>                                                                                                                                                                                                                                    |  | 0.4 <sup>4</sup>                                                                                                                                                      | 0.3           | 0.3                 |
| Infiltration trench (where a suitable depth of filtration material is included that provides treatment, ie graded gravel with sufficient smaller particles but not single size coarse aggregate such as 20 mm gravel) underlain by a soil with good contaminant attenuation potential <sup>2</sup> of at least 300 mm in depth <sup>3</sup> |  | 0.4 <sup>4</sup>                                                                                                                                                      | 0.4           | 0.4                 |
| Constructed permeable pavement (where a suitable filtration layer is included that provides treatment, and including a geotextile at the base separating the foundation from the subgrade) underlain by a soil with good contaminant attenuation potential <sup>2</sup> of at least 300 mm in depth <sup>3</sup>                            |  | 0.7                                                                                                                                                                   | 0.6           | 0.7                 |
| Bioretention underlain by a soil with good contaminant attenuation potential <sup>2</sup> of at least 300 mm in depth <sup>3</sup>                                                                                                                                                                                                          |  | 0.8 <sup>4</sup>                                                                                                                                                      | 0.8           | 0.8                 |
| Proprietary treatment systems <sup>5,6</sup>                                                                                                                                                                                                                                                                                                |  | These must demonstrate that they can address each of the contaminant types to acceptable levels for inflow concentrations relevant to the contributing drainage area. |               |                     |

7.3 To deliver adequate treatment, the selected SuDS components should have a total pollution mitigation index (for each contaminant type) that equals or exceeds the pollution hazard index (for each contaminant type). Where the mitigation index of an individual component is insufficient, two or more components in a series is required, where:

$$\text{Total SuDS mitigation index} = \text{mitigation index}_1 + 0.5 (\text{mitigation index}_2)$$

- 7.4 The proposed development surface water drainage system consists of the following SuDS component:

**Roof Runoff:**

***Primary Treatment – Swale***

Using table 26.3/26.4 – Mitigation Indices

***TSS = 0.5 which is > 0.2 therefore ok.***

***Metals = 0.6 which is > 0.2 therefore ok.***

***Hydrocarbons = 0.6 which is > 0.05 therefore ok.***

***+ Secondary Treatment – Detention Basin***

Using table 26.3/26.4 – Mitigation Indices

***TSS =  $0.5 + (0.5 * 0.5) = 0.75$  which is > 0.2 therefore ok.***

***Metals =  $0.6 + (0.5 * 0.5) = 0.15$  which is > 0.2 therefore ok.***

***Hydrocarbons =  $0.6 + (0.6 * 0.5) = 0.18$  which is > 0.05 therefore ok.***

**Driveway / Parking / Road Runoff:**

***Primary Treatment – Detention Basin***

Using table 26.3/26.4 – Mitigation Indices:

***TSS = 0.5 which is  $\geq 0.5$  therefore ok.***

***Metals = 0.6 which is > 0.4 therefore ok.***

***Hydrocarbons = 0.6 which is > 0.4 therefore ok.***

- 7.5 The runoff will also pass through filter trenches and a pond with a reed bed which will add to the mitigation indices. The total combination of SuDS will meet the high water quality and silt removal requirements to discharge via deep borehole soakaways.
- 7.6 The total mitigation level exceeds the development pollution risk and would be suitable for both medium and high-risk developments. The proposed drainage strategy incorporates measures to far exceed the water quality target requirements within the SuDS Manual and therefore complies with the Water Framework Directives for discharge of runoff into controlled waters.

---

## 8 Foul Water Drainage Strategy

- 8.1 All foul water flows generated from the development will discharge via pumping station and rising main into the Phase 1 foul system located beyond the north-eastern boundary of the site.
- 8.2 A package pumping station will be required.
- 8.3 The predicted peak foul sewer discharge from the 43 units based on the Sewers for Adoption guidance of 4000 l/dwelling/day will be 2.0 l/s.
- 8.4 Southern Water will be consulted to confirm that there is adequate capacity for the proposed development flows. The proposed development will have a 'no detriment' impact on the local foul sewer system and does not create an increase in flood risk.



---

## **APPENDIX A**


### **SITE LAYOUT**



**SITE LEGEND:**

- Application Boundary Line
- Affordable Rent
- Shared Ownership
- Brick Boundary Wall - 1.8m height
- Close Board Fence - 1.8m height
- Post and Rail Fence - 1.2m height
- Estate Railing - 1.2m height
- Parking Bay
- EV Charging Point
- Timber Shed - 1.2x1.8m
- Proposed Tree
- Illustrative Swale

Refer to drawings 2255-TFC-00-00-DR-L-1001 to for detailed landscape proposals.



Romsey Portishead  
T:01794 367703 T:01275 407000  
F:01794 367276 F:01794 367276

www.thrivearchitects.co.uk

This drawing is the copyright of Thrive Architects Ltd ©. All rights reserved. Ordnance Survey Data © Crown Copyright. All rights reserved. Licence No. 100007359. Permission is granted to scale from this drawing for the purposes of **Local Authority Planning Approval only**. For all other purposes DO NOT scale from this drawing. Contractors, sub-contractors and suppliers are to check all relevant dimensions and levels of the site and building before commencing any shop drawings or building work. Any discrepancies should be recorded to the Architect. Where applicable this drawing is to be read in conjunction with the Consultants' drawings.

| Rev | Description                                                  | Date     | Au  | Ch |
|-----|--------------------------------------------------------------|----------|-----|----|
| A   | Planning Issue.                                              | 19.07.24 | MS  | -  |
| B   | Amended inline with with house type and engineering updates. | 28.10.24 | CMi | -  |

|             |                                 |          |             |
|-------------|---------------------------------|----------|-------------|
| Project     | Manor Farm, Bedhampton. Phase 2 |          |             |
| Drawing     | Site Layout Phase 2             |          |             |
| Client      | Bargate Homes                   |          |             |
| Job no.     | BARG230421                      | Date     | 22.10.23    |
| Dwg no.     | SL01                            | Revision | B           |
| Author      | CMi                             | Checker  |             |
| Status      | PLANNING                        | Scale    | 1:500 at A1 |
| Client ref. |                                 | Office   | Romsey      |






---


## **APPENDIX B**

### **TOPOGRAPHICAL SURVEY**





NOTES:  
Drainage:  
Inspection Covers are fitted where possible and all drainage invert information has been obtained through visual inspection only, with no entry into manholes. Therefore the complete accuracy cannot be guaranteed. Where drainage is of critical importance we suggest the services of a specialist drainage expert be used.  
Trees:  
Every effort has been made to identify and detail all trees on site but where trees are of critical importance we suggest the use of a specialist such as an arborist. Tree spread and heights are indicative.  
GPS:  
GPS detail is relative to the time and date of survey. GPS levels and grids are obtained using industry standard guidelines and can vary according to the quality of the GPS network at the time of survey. Unless stated otherwise, surveys are Scale Factor 1 and Horizontal and Vertical Datums are established from a central site fix and baseline orientation station utilizing GNSS correction data.  
Survey notes:  
Survey specification is linked to the original purpose of the survey commissioned at source and is to be used for this purpose only.  
Survey is accurate within limitations of site conditions at the time of survey. In areas difficult to survey due to restricted access, lines of sight or dense vegetation, critical dimensions and positions should be verified following suitable clearance.  
Survey detail obtained and shown is relative to the plotting scale.  
Copyright:  
This survey information is Copyright Encompass Surveys Ltd (2009). All rights reserved.



LEGEND

TREE SPECIES INFORMATION

|           |     |                 |      |
|-----------|-----|-----------------|------|
| ALDER     | ALD | LOCUST          | LOC  |
| ASH       | ASH | LONGOON PLANE   | LON  |
| ASPEN     | ASP | PRINCIPAL       | PRN  |
| BEECH     | BCH | MAPLE           | MPL  |
| BIRCH     | BIR | DOG             | DNG  |
| CHERRY    | CHY | PINE            | PNE  |
| CYPRESS   | CYP | POPLAR          | POP  |
| ELM       | ELM | PRUNUS          | PRN  |
| FIR       | FIR | RHODODENDRON    | RSD  |
| FILLET    | FIL | ROSEMARY        | ROSM |
| HAWTHORN  | HAW | SILVER BIRCH    | SBR  |
| HOLM      | HOL | SORBUS          | SOR  |
| HOLLY     | HOL | SWEET CHESTNUT  | SCN  |
| HORNBEAM  | HBN | SYCAMORE        | SYC  |
| LARICINUS | LAR | WALNUT          | WNT  |
| LARCH     | LAR | WILLOW          | WILW |
| LIME      | LIM | YEW             | YEW  |
|           |     | SPECIES UNKNOWN | SPU  |
|           |     | CONIFER         | COP  |

TREE ANNOTATIONS: Tree Species / Tree Not Size / No of Beds  
Tree Height / Tree Canopy Spread

FENCE INFORMATION

|                       |     |                   |     |
|-----------------------|-----|-------------------|-----|
| BARBED WIRE FENCE     | BWF | BASINMENT LEVEL   | RTL |
| CORRUGATED IRON FENCE | CIF | BELLY LEVEL       | BL  |
| CLOSE BOARD FENCE     | CBF | COVER LEVEL       | CL  |
| CHAIN LINK FENCE      | CLF | CHAMP ROSE COURSE | CRS |
| CHESTNUT PALING       | CPF | FLOOR LEVEL       | FL  |
| CHASH BARBERS         | CBF | INSET LEVEL       | IL  |
| KNOWALE               | KOL | OUTFALL LEVEL     | OL  |
| IRON RAILINGS         | IRF | THRESHOLD LEVEL   | THL |
| LARCH LAF FENCE       | LLF | FOLD WATER        | FW  |
| WELLS LAMENED FENCE   | WLF | SURFACE WATER     | SW  |
| PAULSAGE FENCE        | PSF | UNABLE TO LIFT    | UTL |
| POCKET FENCE          | POF | WATER LEVEL       | WL  |
| POST AND CHAIN FENCE  | PCF |                   |     |
| POST AND MAIL FENCE   | PMF |                   |     |
| POST AND WIRE FENCE   | PWF |                   |     |
| STOCK WIRE FENCE      | SWF |                   |     |
| TRILLUS FENCING       | TUF | CONCRETE          | CNC |

SURFACE INFORMATION

|                 |     |
|-----------------|-----|
| CONCRETE        | CNC |
| BRICK PAVING    | BP  |
| FLYING PAVING   | FP  |
| PAVING SLABS    | PS  |
| REINFORCED WALL | RW  |
| TACTILE PAVING  | TAC |

FEATURE INFORMATION

|                         |     |                      |     |
|-------------------------|-----|----------------------|-----|
| BOLLARD                 | BO  | NOTICE BOARD         | NB  |
| BRITISH TELESCOPE BOX   | BTB | POST                 | P   |
| BUS STOP                | BS  | RAIN WATER PIPE      | RWP |
| CABLE TELESCOPE BOX     | CTB | RAISED FLOWERS       | RFB |
| CABLE TELEVISION BOX    | CTV | ROAD SIGN            | RS  |
| CASTING BOX             | CB  | ROCKING EVER         | RE  |
| ELECTRICITY CABLE PIT   | ECP | SERVICE MANHOLE POST | SMP |
| ELECTRICITY CONTROL BOX | ECB | SOIL VENT PIPE       | SV  |
| ELECTRICITY POLE        | EP  | STOP SIGN            | SC  |
| FREE HIGHWAY            | FH  | STOP VALVE           | SV  |
| INSPECTION COVER        | IC  | TELEPHONE CALL BOX   | TCB |
| LAMP POST               | LP  | TRAFFIC SIGNAL       | TS  |
| LITTER BOX              | LB  | TRAFFIC SIGNALS SC   | TSC |
| LITTER BIN              | LB  | WATER METER          | WM  |
| MANHOLE OUTLET          | MO  | WATER TAP            | WT  |
| NAME PLATE              | NP  |                      |     |

Level Datum:  
Levels are related to OSGB15 derived from the GPS network  
Grid:  
Grid is related to OSGB15 derived from the GPS network  
Northpoint:

**ENCOMPASS SURVEYS**

Encompass Surveys Ltd  
Unit 2  
Tollcross Business Centre  
Durcan Road  
Park Gate, Southampton  
Hampshire SO31 7GA  
Tel: 023 8660000 Email: info@encompass-surveys.co.uk  
Fax: 023 8660725 Website: encompass-surveys.co.uk

Client: Bangor Homes  
Survey Location: Southampton P2  
Survey type: Topographical Scale: 1:200@A0  
Drawing ref: ENC/210221/0000170 Date: March 2021  
Drawn/QA: CH/GJ Revision: Plot 2 of 6



**NOTES:**

**Drainage:**  
Inspection Coves are lifted where possible and all drainage invert information has been obtained through visual inspection only, with the exception of the 10% of inspection coves that are completely guaranteed. Where drainage is of critical importance we suggest that a surveyor of a specialist drainage expert be used.

**Trees:**  
Every effort has been made to identify and detail all trees on the site and to provide a list of all trees. The survey was carried out by a specialist such as an arborist. Tree spread and heights are indicative GPS only.


**Survey:**  
Details relate to the time and date of survey. GPS levels and/or are obtained using industry standard guidelines and can vary slightly from actual quality. The survey is carried out using the United States standard surveying system. Scale Factor 1 and Horizontal and Vertical Datums are established from a central site fix and the datum elevation station utilizes GCSG coordinate system.

**Survey notes:**  
Survey specification is linked to the original purpose of the survey and the surveyor's notes are intended for use for this purpose only. Survey is accurate within limitations of the conditions at the time of survey. The survey is not intended to be used for any other purpose, sight or design vegetation, critical dimensions and positions should be verified following suitable clearance.

**Survey description:**  
The description and drawing is relative to the plotting scale.

**Copyright:**  
The copyright in this document is owned by the surveyor.

**All rights reserved. © Copyright: Encapsures Surveyors Ltd (2009).**



LEGEND

### TREE SPECIES INFORMATION

|                |     |                 |     |
|----------------|-----|-----------------|-----|
| ALDER          | ALD | LOCUST          | LOK |
| ASH            | ASH | LONDON PLANE    | LP  |
| ASPEN          | ASP | MAGNOLIA        | MA  |
| BEECH          | BCH | MAPLE           | MP  |
| CEDAR          | CED | OAK             | OK  |
| CHEVY          | CHF | PINE            | PN  |
| CYPRESS        | CYP | POPLAR          | PO  |
| ELM            | ELM | PRUNUS          | PR  |
| FIR            | FR  | RHODODENDRONS   | RD  |
| FRUIT          | FRT | ROSE            | R   |
| HAWTHORN       | HW  | RYAN BERRY      | SW  |
| HAZEL          | HZ  | SORBUS          | SO  |
| HOLLY          | HL  | SWEET CHESTNUT  | SC  |
| HORSE CHESTNUT | HCH | SYCAMORE        | SY  |
| HORNBEAM       | HBM | WALNUT          | W   |
| LABURNUM       | LRM | WILLOW          | WL  |
| LARCH          | LAR | YEW             | Y   |
| LYME           | LYM | SPECIES UNKNOWN | SP  |
|                |     | COMPASS         | CO  |

**TREE ANNOTATIONS:** Tree Species / Tree Boli Size / No of Boli  
Tree Height / Tree Canopy Spread

## FENCE INFORMATION

|                        |     |                   |
|------------------------|-----|-------------------|
| BARRIED WIRE FENCE     | BWF | BASEMENT LEVEL    |
| CONVINGATED IRON FENCE | CIF | BED LEVEL         |
| CLOSE BOARD FENCE      | CBF | COVER LEVEL       |
| CHALK LICK FENCE       | CLF | DAMP PROOF COURSE |
| CHESTNUT PALING        | CPL | FLOOR LEVEL       |
| CRASH BARRIER          | CRA | INVERT LEVEL      |
| HANDRAIL               | HDL | OUTFALL LEVEL     |
| IRON RAILINGS          | IRL | THRESHOLD LEVEL   |
| LAUNCH LAF FENCE       | LLF | FOUL WATER        |
| MISCELLANEOUS FENCE    | MSF | SURFACE WATER     |
| PALESADE FENCE         | PSF | UNABLE TO LIFT    |
| PICKET FENCE           | PF  | WATER LEVEL       |

## SURFACE INFORMATION

|                  |     |                |
|------------------|-----|----------------|
| STOCK WIRE FENCE | SWF | CONCRETE       |
| TRELLIS FENCING  | TLF | BRICK PAVERS   |
|                  |     | FLOWERBED      |
|                  |     | PAVING SLABS   |
|                  |     | RETAINING WALL |
|                  |     | TACTILE PAVING |

### FEATURE INFORMATION

|                         |      |                     |
|-------------------------|------|---------------------|
| BOLLARD                 | BO   | NOTICE BOARD        |
| BROADCAST TELECOM BOX   | BTE  | RAIN WATER PIPE     |
| BROADCAST TELECOM IC    | BTC  | RASSED FLOWERSHED   |
| BUS STOP                | BS   |                     |
| CABLE TELEVISION BOX    | CATB | ROAD SIGN           |
| CABLE TELEVISION IC     | CATV | ROOFTOP EYE         |
| EARTHING ROD            | ER   | SERVICE MARKER POST |
| ELECTRICITY CABLE PIT   | ELCP | SOIL VENT PIPE      |
| ELECTRICITY CONTROL BOX | ECB  | STOP COOK           |
| ELECTRICITY POLE        | EP   | STOP VALVE          |
| FIRE INFRANT            | FI   | TELEGRAPH POLE      |
| INSPECTION COVER        | IC   | TELEPHONE CALL BOX  |
| LAMP POST               | LP   | TRAFFIC SIGNAL      |
| LITTER BOX              | LB   | TRAFFIC SIGNALS     |
| LITTER BOX              | LB   | WATER METERS        |
| KEROSENE OUTLET         | KO   | WATER TAP           |
| NAME PLATE              | NP   |                     |

Level Datum:  
Levels are related to OSG815 derived from the GPS network.

Grid:  
Grid is related to OSGB15 derived from the GPS network

Northpoint



Encompass Surveys Ltd  
Unit 2  
Tollman Business Centre  
Duncan Road  
Park Gate, Southampton  
Hampshire SO31 7GA

Tel: 023 8069202      Email: [info@encompass-surveys.co.uk](mailto:info@encompass-surveys.co.uk)  
Fax: 023 80697125      Website: [encompass-surveys.co.uk](http://encompass-surveys.co.uk)

|         |               |
|---------|---------------|
| Client: | Bargate Homes |
|---------|---------------|

|                  |                                       |
|------------------|---------------------------------------|
| Survey Location: | Bedhampton P2<br>Bedhampton<br>Havant |
|------------------|---------------------------------------|


|              |               |        |            |
|--------------|---------------|--------|------------|
| Survey type: | Topographical | Scale: | 1:200 (A0) |
|--------------|---------------|--------|------------|

|              |                    |       |            |
|--------------|--------------------|-------|------------|
| Drawing ref: | ENC/210221/6NN3/To | Date: | March 2021 |
|--------------|--------------------|-------|------------|

|                 |                       |
|-----------------|-----------------------|
| Drawn/QA: CH/GL | Revision: Plot 4 of 6 |
|-----------------|-----------------------|

|  |  |
|--|--|
|  |  |
|  |  |





**NOTES:**

Drainage:  
Inspection Covers are fitted where possible and all drainage invert information has been obtained through visual inspection only, with no entry into manholes. Therefore the complete accuracy cannot be guaranteed. Where drainage is of critical importance we suggest the services of a specialist drainage expert be used.

Trees:  
Every effort has been made to identify and detail all trees on site but where trees are of critical importance we suggest the use of a specialist such as an arborist. Tree spread and heights are indicative.

GPS:  
GPS detail is relative to the time and date of survey. GPS levels and grids are obtained using industry standard guidelines and can vary according to the quality of the GPS network at the time of survey. Unless stated otherwise, surveys are Scale factor 1 and Horizontal and Vertical Datums are established from a central site fix and baseline orientation station utilizing GNSS correction data.

Survey notes:  
Survey specification is linked to the original purpose of the survey commissioned at source and is to be used for this purpose only. Survey is accurate within limitations of site conditions at the time of survey. In areas difficult to survey due to restricted access, lines of sight or dense vegetation, critical dimensions and positions should be verified following suitable clearance.

Survey detail obtained and shown is relative to the plotting scale.

Copyright:  
This survey information is Copyright Encompass Surveys Ltd (2009). All rights reserved.

**LEGEND**

**TREE SPECIES INFORMATION**

|          |     |                 |      |
|----------|-----|-----------------|------|
| ALDER    | ALD | LOCUST          | LOC  |
| ASH      | ASH | LONDON PLANE    | LTP  |
| ASPEN    | ASP | PRUNELLA        | PRU  |
| BEECH    | BCH | MAPLE           | MPL  |
| BIRCH    | BIR | DOG             | DOG  |
| CHERRY   | CHY | YEW             | YEW  |
| CYPRESS  | CYP | POPLAR          | POP  |
| ELM      | ELM | PRUNUS          | PRU  |
| FIR      | FIR | RHODODENDRON    | RSD  |
| GUM      | GUM | ROSE            | ROSE |
| HAWTHORN | HAW | SILVER BIRCH    | SBR  |
| HOLM     | HOL | SPRING          | SPR  |
| HOLLY    | HOL | SWEET CHESTNUT  | SCN  |
| HORNBEAM | HBN | SYCAMORE        | SYC  |
| LARIX    | LAR | WALNUT          | WNT  |
| LARCH    | LAR | WILLOW          | WIL  |
| LIME     | LIM | YEW             | YEW  |
|          |     | SPECIES UNKNOWN | SPU  |
|          |     | COMPACT         | COP  |

**TREE ANNOTATIONS:** Tree Species / Tree Height / No of Beds / Tree Height / Tree Canopy Spread

**FENCE INFORMATION**

|                       |     |                     |     |
|-----------------------|-----|---------------------|-----|
| BARBED WIRE FENCE     | BWF | BASINMENT LEVEL     | RTL |
| CORRUGATED IRON FENCE | CIF | BED LEVEL           | BL  |
| CLOSE BOARD FENCE     | CBF | COVER LEVEL         | CL  |
| CHAIN LINK FENCE      | CLF | DEEP POSE COURSE    | DPC |
| CHESTNUT PALING       | CPF | FLOOR LEVEL         | FL  |
| CHINA WOODS           | CWF | INSET LEVEL         | IL  |
| IRON RAILING          | IRF | OUTFALL LEVEL       | OL  |
| LARCH LAP FENCE       | LLF | THATCHED ROOF LEVEL | TRL |
| WELSH RAILING         | WRF | FOAL WATER          | FW  |
| PAULSAGE FENCE        | PSF | SHOCK WATER         | SW  |
| POCKET FENCE          | POF | UNABLE TO LIFT      | UTL |
| POST AND RAIL FENCE   | PRF | WATER UTILITY       | WU  |
| POST AND WIRE FENCE   | PWF |                     |     |
| STOCK WIRE FENCE      | SWF |                     |     |
| WELLS FENCING         | WLF |                     |     |

**SURFACE INFORMATION**

|                 |     |
|-----------------|-----|
| CONCRETE        | CNC |
| BRICK PAVING    | BP  |
| FLYING          | FB  |
| PAVING SLABS    | PS  |
| REINFORCED WALL | RWF |
| TACTILE PAVING  | TAC |

**FEATURE INFORMATION**

|                         |     |                      |     |
|-------------------------|-----|----------------------|-----|
| BOLLARD                 | BO  | NOTICE BOARD         | NB  |
| BRITISH TELECOM BOX     | BTB | POST                 | P   |
| BUS STOP                | BS  | RAIN WATER PIPE      | RWP |
| CABLE TELEVISION BOX    | CTB | RANDED FLOWERS       | RFB |
| CABLE TELEVISION IC     | CTV | RANDY SIGN           | RS  |
| CASTING BOX             | CB  | ROCKING CHAIR        | RC  |
| ELECTRICITY CABLE PIT   | ECP | SERVICE MANHOLE POST | SMP |
| ELECTRICITY CONTROL BOX | ECB | SOIL VENT PIPE       | SV  |
| ELECTRICITY POLE        | EP  | STOP SIGN            | SP  |
| FREE HUBBARD            | FH  | TELEPHONE POLE       | TP  |
| INSPECTION COVER        | IC  | TELEPHONE CALL BOX   | TCB |
| LAMP POST               | LP  | TRAMP SIGN           | TS  |
| LITTER BOX              | LB  | TRAMP SIGNALS SC     | TSC |
| LITTER BIN              | LB  | WATER METER          | WM  |
| MAN OUTLET              | MO  | WATER TAP            | WT  |
| NAME PLATE              | NP  |                      |     |

Level Datum:  
Levels are related to OSGB15 derived from the GPS network

Grid:  
Grid is related to OSGB15 derived from the GPS network

Northpoint:

**ENCOMPASS SURVEYS**

Encompass Surveys Ltd  
Unit 2  
Tollcross Business Centre  
Dunelm Road  
Park Gate, Southampton  
Hampshire SO31 7GA

Tel: 023 8667202 Email: info@encompass-surveys.co.uk  
Fax: 023 8667225 Website: encompass-surveys.co.uk

Client: Bangor Homes

Survey Location: Badmington P2  
Badmington  
Havant

Survey type: Topographical Scale: 1:200@A0

Drawing ref: ENC/210221/000170 Date: March 2021


Drawn/QA: CHVL Revision: Plot 6 of 6



---

## **APPENDIX C**

### **FOUL AND SURFACE WATER DRAINAGE STRATEGY**



Mast  
(Telecommunication)

| KEY: |                                   |  |                                  |
|------|-----------------------------------|--|----------------------------------|
|      | Swale                             |  | Private foul pumping station     |
|      | Reed lined swale                  |  | Foul pipework links and manholes |
|      | Stone grip                        |  | Foul rising main                 |
|      | Storm pipework links and manholes |  | Indicative private foul drainage |
|      | PCC concrete headwall             |  | Excess flow direction            |
|      | Low flow channel                  |  | Bund                             |
|      | PCC hydrobrake control chamber    |  |                                  |
|      | Indicative private storm drainage |  |                                  |
|      | Highway gully and lateral drain   |  |                                  |

|                                                          |          |                                                                  |     |     |
|----------------------------------------------------------|----------|------------------------------------------------------------------|-----|-----|
| P14                                                      | 11.11.24 | Base planning layout amended                                     | SS  | KTG |
| P13                                                      | 24.10.24 | Bund removed                                                     | SS  | KTG |
| P12                                                      | 24.10.24 | Swale adjusted, bund extended, levels of swale added             | SS  | KTG |
| P11                                                      | 26.09.24 | Earth bund protection to railway added                           | SS  | KTG |
| P10                                                      | 25.07.24 | Basin volume label updated                                       | SS  | KTG |
| P9                                                       | 23.07.24 | Drawing updated                                                  | KTG | KTG |
| P8                                                       | 17.07.24 | Parking spaces opposite plots 22/27 amended following RSA1 Audit | KTG | KTG |
| P7                                                       | 16.07.24 | Updated to client's comments                                     | SS  | KTG |
| P6                                                       | 08.07.24 | Site layout updated                                              | KTG | KTG |
| P5                                                       | 20.05.24 | Road 1 extension to Phase 1 site updated                         | AK  | KTG |
| P4                                                       | 20.05.24 | Service margin position and drainage strategy amended            | AK  | KTG |
| P3                                                       | 16.05.24 | New planning layout added, drainage strategy amended             | KTG | KTG |
| P2                                                       | 21.03.24 | Outfall swale added                                              | SS  | KTG |
| REV. No.                                                 | DATE     | DESCRIPTION                                                      | SS  | KTG |
| Client                                                   |          |                                                                  |     |     |
| BARGATE HOMES                                            |          |                                                                  |     |     |
| Project Phase 2, Bedhampton                              |          |                                                                  |     |     |
| Title Drainage Layout                                    |          |                                                                  |     |     |
| Scale: 1:250 @ A0 Status: PRELIMINARY                    |          |                                                                  |     |     |
| Drawn: Project Engineer MJA Project No: Date: 24/10/2023 |          |                                                                  |     |     |
| Drawing Number: 6430-MJA-SW-XX-DR-C-001 Rec: P14         |          |                                                                  |     |     |



---


## **APPENDIX D**

### **PRE / POST DEVELOPMENT RUNOFF AND STORAGE CALCULATIONS**



|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                |                                                                                     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|-------------------------------------------------------------------------------------|
| MJA Consulting                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                | Page 1                                                                              |
| Monarch House<br>Barton Lane<br>OX14 3NB                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Phase 2 Manor Farm<br>Bedhampton<br>Greenfield |  |
| Date 22/09/2021<br>File POND.SRCX                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Designed by S.Smith<br>Checked by CP           |                                                                                     |
| Innovyze                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                | Source Control 2020.1                                                               |
| <p align="center"><u>ICP SUDS Mean Annual Flood</u></p> <p align="center">Input</p> <p>Return Period (years)    100                      Soil            0.400</p> <p>Area (ha) 0.920                                      Urban            0.000</p> <p>SAAR (mm)    729    Region Number    Region 7</p> <p align="center"><b>Results    1/s</b></p> <p>QBAR Rural    3.3</p> <p>QBAR Urban    3.3</p> <p>Q100 years    10.5</p> <p>Q1 year        2.8</p> <p>Q30 years      7.4</p> <p>Q100 years    10.5</p> |                                                |                                                                                     |
| ©1982-2020 Innovyze                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                |                                                                                     |





Date: 25/07/2024 00:00:00

Designed by: S.Smith

Checked by: S.Smith

File: Phase 2 Bedhampton.iddx

Plot Scale: 1:958

Land west of Manor Farm  
Surface Water Calculations

InfoDrainage 2024.4

©2023 Autodesk, Inc. All rights reserved

|                                                                    |                                    |                        |                          |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |



Basin

Type : Pond

Dimensions

|                      |         |
|----------------------|---------|
| Exceedance Level (m) | 5.250   |
| Depth (m)            | 1.460   |
| Base Level (m)       | 3.790   |
| Freeboard (mm)       | 300     |
| Initial Depth (m)    | 0.000   |
| Porosity (%)         | 100     |
| Average Slope (1:X)  | 4.16    |
| Total Volume (m³)    | 954.778 |

| Depth (m) | Area (m²) | Volume (m³) |
|-----------|-----------|-------------|
| 0.000     | 570.00    | 0.000       |
| 0.100     | 609.00    | 58.939      |
| 0.200     | 650.00    | 121.878     |
| 0.300     | 685.00    | 188.620     |
| 0.400     | 724.00    | 259.061     |
| 0.500     | 764.00    | 333.453     |
| 0.600     | 845.00    | 413.869     |
| 0.700     | 887.00    | 500.460     |
| 0.800     | 929.00    | 591.252     |
| 0.900     | 973.00    | 686.343     |
| 1.000     | 1016.00   | 785.786     |
| 1.100     | 1060.00   | 889.578     |
| 1.200     | 1150.00   | 1000.047    |
| 1.300     | 1196.00   | 1117.340    |
| 1.460     | 1200.00   | 1309.020    |

Inlets

Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | 4.010          |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | 1.014          |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

Inlet (2)

|                    |                     |
|--------------------|---------------------|
| Inlet Type         | Point Inflow        |
| Incoming Item(s)   | Catchment Area (38) |
| Bypass Destination | (None)              |
| Capacity Type      | No Restriction      |

Outlets

Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 1.015          |
| Outlet Type         | Free Discharge |

|                                                                   |                                                                    |                        |                          |                                                                                     |
|-------------------------------------------------------------------|--------------------------------------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                                                |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith                                            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
|                                                                   | Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase |                        |                          |                                                                                     |
| Company Address:<br>MJA Consulting                                |                                                                    |                        |                          |                                                                                     |

Advanced

|                 |             |
|-----------------|-------------|
| Perimeter       | Circular    |
| Length (m)      | 61.890      |
| Friction Scheme | Manning's n |
| n               | 0.03        |

|                                                                    |                                    |                        |                          |                                                                                     |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |  |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |
|                                                                    |                                    |                        |                          |                                                                                     |



Swale

Type : Swale

Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 5.250       |
| Depth (m)              | 0.750       |
| Base Level (m)         | 4.500       |
| Top Width (m)          | 4.660       |
| Side Slope (1:X)       | 3.00        |
| Base Width (m)         | 0.160       |
| Freeboard (mm)         | 300         |
| Length (m)             | 29.000      |
| Long. Slope (1:X)      | 300.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 19.706      |

Inlets

Inlet (1)

|                    |                     |
|--------------------|---------------------|
| Inlet Type         | Point Inflow        |
| Incoming Item(s)   | Catchment Area (32) |
| Bypass Destination | (None)              |
| Inlet Destination  | Ponding Area        |
| Capacity Type      | No Restriction      |

Inlet

|                    |                     |
|--------------------|---------------------|
| Inlet Type         | Point Inflow        |
| Incoming Item(s)   | Catchment Area (33) |
| Bypass Destination | (None)              |
| Inlet Destination  | Ponding Area        |
| Capacity Type      | No Restriction      |

Outlets

Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 5.000          |
| Outlet Type         | Free Discharge |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                    |                                    |                        |                          |                                                                                     |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |  |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |
|                                                                    |                                    |                        |                          |                                                                                     |



Swale (1)

Type : Swale

Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 5.250       |
| Depth (m)              | 1.200       |
| Base Level (m)         | 4.050       |
| Top Width (m)          | 7.360       |
| Side Slope (1:X)       | 3.00        |
| Base Width (m)         | 0.160       |
| Freeboard (mm)         | 300         |
| Length (m)             | 27.727      |
| Long. Slope (1:X)      | 300.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 71.370      |

Inlets

Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | 4.008          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

Outlets

Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 4.009          |
| Outlet Type         | Free Discharge |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                    |                                    |                        |                          |                                                                                     |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |  |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |
|                                                                    |                                    |                        |                          |                                                                                     |



Swale (2)

Type : Swale

Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 5.250       |
| Depth (m)              | 1.200       |
| Base Level (m)         | 4.050       |
| Top Width (m)          | 7.360       |
| Side Slope (1:X)       | 3.00        |
| Base Width (m)         | 0.160       |
| Freeboard (mm)         | 300         |
| Length (m)             | 27.847      |
| Long. Slope (1:X)      | 300.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 71.679      |

Inlets

Outlets

Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 7.000          |
| Outlet Type         | Free Discharge |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                    |                                    |                        |                          |                                                                                     |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |  |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |
|                                                                    |                                    |                        |                          |                                                                                     |



Swale (3)

Type : Swale

Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 3.950       |
| Depth (m)              | 0.600       |
| Base Level (m)         | 3.350       |
| Top Width (m)          | 3.760       |
| Side Slope (1:X)       | 3.00        |
| Base Width (m)         | 0.160       |
| Freeboard (mm)         | 300         |
| Length (m)             | 100.112     |
| Long. Slope (1:X)      | 300.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 31.836      |

Inlets

Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | 1.016          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

Outlets

Outlet

|                          |        |
|--------------------------|--------|
| Outgoing Connection      | (None) |
| Outlet Type              | Weir   |
| Width (m)                | 1.000  |
| Coefficient of Discharge | 0.544  |
| Crest Level (m)          | 3.750  |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                          |                                                                   |                               |                                                                                     |
|--------------------------------------------------------------------------|-------------------------------------------------------------------|-------------------------------|-------------------------------------------------------------------------------------|
| <b>Project:</b><br>Land west of Manor Farm<br>Surface Water Calculations | <b>Date:</b><br>25/07/2024                                        |                               |                                                                                     |
|                                                                          | <b>Designed by:</b><br>S.Smith                                    | <b>Checked by:</b><br>S.Smith | <b>Approved By:</b><br>C.Pendle                                                     |
|                                                                          | <b>Report Details:</b><br>Type: Connections<br>Storm Phase: Phase |                               |                                                                                     |
| <b>Company Address:</b><br>MJA Consulting                                |                                                                   |                               |  |

| Name  | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Upstream Cover Level (m) | Upstream Invert Level (m) |
|-------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|--------------------------|---------------------------|
| 1.000 | 46.436     | Pipe            | 232.181     |             | 0.6                            | 225                        | 7.000                    | 6.000                     |
| 2.000 | 8.466      | Pipe            | 56.439      |             | 0.6                            | 225                        | 7.150                    | 5.950                     |
| 1.001 | 17.462     | Pipe            | 291.034     |             | 0.6                            | 225                        | 7.000                    | 5.800                     |
| 1.002 | 20.458     | Pipe            | 204.578     |             | 0.6                            | 225                        | 7.500                    | 5.740                     |
| 1.003 | 23.852     | Pipe            | 54.209      |             | 0.6                            | 225                        | 7.350                    | 5.640                     |
| 1.004 | 6.736      | Pipe            | 56.135      |             | 0.6                            | 225                        | 6.800                    | 5.200                     |
| 1.005 | 23.967     | Pipe            | 54.471      |             | 0.6                            | 225                        | 6.800                    | 5.080                     |
| 1.006 | 5.401      | Pipe            | 38.577      |             | 0.6                            | 225                        | 6.400                    | 4.640                     |
| 3.000 | 26.559     | Pipe            | 221.325     |             | 0.6                            | 225                        | 6.350                    | 5.000                     |
| 3.001 | 7.906      | Pipe            | 197.645     |             | 0.6                            | 225                        | 6.100                    | 4.880                     |
| 3.002 | 5.155      | Pipe            | 257.772     |             | 0.6                            | 225                        | 6.050                    | 4.840                     |
| 3.003 | 28.958     | Pipe            | 160.876     |             | 0.6                            | 300                        | 5.950                    | 4.820                     |
| 3.004 | 21.695     | Pipe            | 197.230     |             | 0.6                            | 300                        | 6.150                    | 4.680                     |
| 3.005 | 14.953     | Pipe            | 213.611     |             | 0.6                            | 300                        | 6.300                    | 4.570                     |
| 1.007 | 3.338      | Pipe            | 66.762      |             | 0.6                            | 450                        | 6.300                    | 4.350                     |
| 1.008 | 36.432     | Pipe            | 280.247     |             | 0.6                            | 450                        | 5.600                    | 4.300                     |
| 1.009 | 6.857      | Pipe            | 342.860     |             | 0.6                            | 450                        | 5.600                    | 4.170                     |
| 1.010 | 28.777     | Pipe            | 287.768     |             | 0.6                            | 450                        | 5.500                    | 4.150                     |
| 1.011 | 14.815     | Pipe            | 296.296     |             | 0.6                            | 450                        | 5.100                    | 4.050                     |
| 1.012 | 19.808     | Pipe            | 282.967     |             | 0.6                            | 450                        | 5.050                    | 4.000                     |
| 1.013 | 24.532     | Pipe            | 306.645     |             | 0.6                            | 450                        | 5.000                    | 3.930                     |
| 4.000 | 13.912     | Pipe            | 139.118     |             | 0.6                            | 225                        | 6.900                    | 5.520                     |
| 4.001 | 9.887      | Pipe            | 98.872      |             | 0.6                            | 225                        | 6.800                    | 5.420                     |
| 4.002 | 17.658     | Pipe            | 98.099      |             | 0.6                            | 225                        | 6.700                    | 5.320                     |
| 4.003 | 28.317     | Pipe            | 97.644      |             | 0.6                            | 225                        | 6.550                    | 5.140                     |
| 4.004 | 8.032      | Pipe            | 100.403     |             | 0.6                            | 225                        | 6.400                    | 4.850                     |
| 4.005 | 22.705     | Pipe            | 103.202     |             | 0.6                            | 225                        | 6.500                    | 4.770                     |
| 4.006 | 4.039      | Pipe            | 100.975     |             | 0.6                            | 300                        | 6.450                    | 4.550                     |
| 4.007 | 19.064     | Pipe            | 40.562      |             | 0.6                            | 300                        | 6.250                    | 4.510                     |
| 6.000 | 6.131      | Pipe            | -47.160     |             | 0.6                            | 300                        | 6.150                    | 4.040                     |
| 5.000 | 5.616      | Pipe            | 16.045      |             | 0.6                            | 300                        | 5.400                    | 4.500                     |
| 4.008 | 2.912      | Pipe            | 145.595     |             | 0.6                            | 300                        | 5.350                    | 4.150                     |
| 4.009 | 3.866      | Pipe            | 128.864     |             | 0.6                            | 300                        | 5.350                    | 4.050                     |
| 7.000 | 3.274      | Pipe            | 109.128     |             | 0.6                            | 300                        | 5.350                    | 4.050                     |
| 4.010 | 9.862      | Pipe            | 328.734     |             | 0.6                            | 300                        | 5.350                    | 4.020                     |
| 1.015 | 5.355      | Pipe            | 0.000       |             | 0.6                            | 450                        | 5.250                    | 3.790                     |
| 1.016 | 10.279     | Pipe            | 73.424      |             | 0.6                            | 225                        | 5.250                    | 3.790                     |
| 1.014 | 19.925     | Pipe            | 332.088     |             | 0.6                            | 450                        | 5.250                    | 3.850                     |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Connections<br>Storm Phase: Phase        | Company Address:<br>MJA Consulting |                        |                          |



| Name  | Downstream<br>Cover Level<br>(m) | Downstream<br>Invert Level<br>(m) | Lock | Flow<br>Restriction<br>(L/s) |
|-------|----------------------------------|-----------------------------------|------|------------------------------|
| 1.000 | 7.000                            | 5.800                             | All  |                              |
| 2.000 | 7.000                            | 5.800                             | All  |                              |
| 1.001 | 7.500                            | 5.740                             | All  |                              |
| 1.002 | 7.350                            | 5.640                             | All  |                              |
| 1.003 | 6.800                            | 5.200                             | All  |                              |
| 1.004 | 6.800                            | 5.080                             | All  |                              |
| 1.005 | 6.400                            | 4.640                             | All  |                              |
| 1.006 | 6.300                            | 4.500                             | All  |                              |
| 3.000 | 6.100                            | 4.880                             | All  |                              |
| 3.001 | 6.050                            | 4.840                             | All  |                              |
| 3.002 | 5.950                            | 4.820                             | All  |                              |
| 3.003 | 6.150                            | 4.640                             | All  |                              |
| 3.004 | 6.300                            | 4.570                             | All  |                              |
| 3.005 | 6.300                            | 4.500                             | All  |                              |
| 1.007 | 5.600                            | 4.300                             | All  |                              |
| 1.008 | 5.600                            | 4.170                             | All  |                              |
| 1.009 | 5.500                            | 4.150                             | All  |                              |
| 1.010 | 5.100                            | 4.050                             | All  |                              |
| 1.011 | 5.050                            | 4.000                             | All  |                              |
| 1.012 | 5.000                            | 3.930                             | All  |                              |
| 1.013 | 5.250                            | 3.850                             | All  |                              |
| 4.000 | 6.800                            | 5.420                             | All  |                              |
| 4.001 | 6.700                            | 5.320                             | All  |                              |
| 4.002 | 6.550                            | 5.140                             | All  |                              |
| 4.003 | 6.400                            | 4.850                             | All  |                              |
| 4.004 | 6.500                            | 4.770                             | All  |                              |
| 4.005 | 6.450                            | 4.550                             | All  |                              |
| 4.006 | 6.250                            | 4.510                             | All  |                              |
| 4.007 | 5.350                            | 4.040                             | All  |                              |
| 6.000 | 5.350                            | 4.170                             | All  |                              |
| 5.000 | 5.350                            | 4.150                             | All  |                              |
| 4.008 | 5.350                            | 4.130                             | All  |                              |
| 4.009 | 5.350                            | 4.020                             | All  |                              |
| 7.000 | 5.350                            | 4.020                             | All  |                              |
| 4.010 | 3.250                            | 3.990                             | All  |                              |
| 1.015 | 5.250                            | 3.790                             | All  |                              |
| 1.016 | 5.250                            | 3.650                             | All  | 3.6                          |
| 1.014 | 5.250                            | 3.790                             | All  |                              |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Phase     | Company Address:<br>MJA Consulting |                        |                          |



| Inflow Label        | Connected To | Flow (L/s) | Runoff Method         | Area (ha) | Percentage Impervious (%) | Urban Creep (%) | Adjusted Percentage Impervious (%) | Area Analysed (ha) |
|---------------------|--------------|------------|-----------------------|-----------|---------------------------|-----------------|------------------------------------|--------------------|
| Catchment Area      | 1            |            | Time of Concentration | 0.013     | 100                       | 10              | 110                                | 0.014              |
| Catchment Area (1)  | 29           |            | Time of Concentration | 0.018     | 100                       | 0               | 100                                | 0.018              |
| Catchment Area (2)  | 30           |            | Time of Concentration | 0.012     | 100                       | 10              | 110                                | 0.013              |
| Catchment Area (3)  | 30           |            | Time of Concentration | 0.034     | 100                       | 10              | 110                                | 0.037              |
| Catchment Area (4)  | 33           |            | Time of Concentration | 0.022     | 100                       | 0               | 100                                | 0.022              |
| Catchment Area (5)  | 11           |            | Time of Concentration | 0.031     | 100                       | 10              | 110                                | 0.035              |
| Catchment Area (6)  | 12           |            | Time of Concentration | 0.003     | 100                       | 0               | 100                                | 0.003              |
| Catchment Area (7)  | 11           |            | Time of Concentration | 0.033     | 100                       | 10              | 110                                | 0.037              |
| Catchment Area (8)  | 24           |            | Time of Concentration | 0.061     | 100                       | 0               | 100                                | 0.061              |
| Catchment Area (9)  | 3            |            | Time of Concentration | 0.006     | 100                       | 10              | 110                                | 0.007              |
| Catchment Area (10) | 14           |            | Time of Concentration | 0.007     | 100                       | 0               | 100                                | 0.007              |
| Catchment Area (11) | 7            |            | Time of Concentration | 0.006     | 100                       | 10              | 110                                | 0.007              |
| Catchment Area (12) | 16           |            | Time of Concentration | 0.020     | 100                       | 10              | 110                                | 0.022              |
| Catchment Area (13) | 8            |            | Time of Concentration | 0.017     | 100                       | 0               | 100                                | 0.017              |
| Catchment Area (14) | 24           |            | Time of Concentration | 0.038     | 100                       | 10              | 110                                | 0.042              |
| Catchment Area (15) | 14           |            | Time of Concentration | 0.043     | 100                       | 10              | 110                                | 0.048              |
| Catchment Area (16) | 30           |            | Time of Concentration | 0.023     | 100                       | 0               | 100                                | 0.023              |
| Catchment Area (17) | 14           |            | Time of Concentration | 0.035     | 100                       | 0               | 100                                | 0.035              |
| Catchment Area (18) | 15           |            | Time of Concentration | 0.012     | 100                       | 0               | 100                                | 0.012              |
| Catchment Area (19) | 16           |            | Time of Concentration | 0.029     | 100                       | 0               | 100                                | 0.029              |
| Catchment Area (20) | 20           |            | Time of Concentration | 0.009     | 100                       | 0               | 100                                | 0.009              |
| Catchment Area (21) | 18           |            | Time of Concentration | 0.018     | 100                       | 0               | 100                                | 0.018              |
| Catchment Area (22) | 17           |            | Time of Concentration | 0.034     | 100                       | 10              | 110                                | 0.037              |
| Catchment Area (23) | 22           |            | Time of Concentration | 0.011     | 100                       | 0               | 100                                | 0.011              |
| Catchment Area (24) | 22           |            | Time of Concentration | 0.018     | 100                       | 0               | 100                                | 0.018              |
| Catchment Area (25) | 26           |            | Time Area Diagram     | 0.058     | 100                       | 0               | 100                                | 0.058              |
| Catchment Area (26) | 26           |            | Time of Concentration | 0.019     | 100                       | 10              | 110                                | 0.020              |
| Catchment Area (27) | 27           |            | Time of Concentration | 0.023     | 100                       | 0               | 100                                | 0.023              |
| Catchment Area (28) | 3            |            | Time of Concentration | 0.024     | 100                       | 0               | 100                                | 0.024              |
| Catchment Area (29) | 1            |            | Time of Concentration | 0.022     | 100                       | 10              | 110                                | 0.024              |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Phase     | Company Address:<br>MJA Consulting |                        |                          |



|                     |       |            |                       |              |     |    |     |              |
|---------------------|-------|------------|-----------------------|--------------|-----|----|-----|--------------|
| Catchment Area (30) | 2     |            | Time of Concentration | 0.086        | 100 | 10 | 110 | 0.095        |
| Catchment Area (31) | 29    |            | Time of Concentration | 0.021        | 100 | 10 | 110 | 0.023        |
| Catchment Area (32) | Swale |            | Time of Concentration | 0.020        | 100 | 10 | 110 | 0.022        |
| Catchment Area (33) | Swale |            | Time of Concentration | 0.006        | 100 | 0  | 100 | 0.006        |
| Catchment Area (34) | 24    |            | Time of Concentration | 0.031        | 100 | 10 | 110 | 0.034        |
| Catchment Area (35) | 22    |            | Time of Concentration | 0.010        | 100 | 10 | 110 | 0.011        |
| Catchment Area (36) | 22    |            | Time of Concentration | 0.008        | 100 | 0  | 100 | 0.008        |
| Catchment Area (37) | 13    |            | Time of Concentration | 0.025        | 100 | 10 | 110 | 0.027        |
| Catchment Area (38) | Basin |            | Time of Concentration | 0.122        | 100 | 0  | 100 | 0.122        |
| <b>TOTAL</b>        |       | <b>0.0</b> |                       | <b>1.026</b> |     |    |     | <b>1.076</b> |

|                                                                   |                                                                |                        |                          |                                                                                     |
|-------------------------------------------------------------------|----------------------------------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                                            |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith                                        | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
|                                                                   | Report Details:<br>Type: Outfall Details<br>Storm Phase: Phase |                        |                          |                                                                                     |
| Company Address:<br>MJA Consulting                                |                                                                |                        |                          |                                                                                     |

Outfalls

| Outfall   | Outfall Type   | Fixed Surcharged<br>Level (m) | Level Curve |
|-----------|----------------|-------------------------------|-------------|
| Swale (3) | Free Discharge |                               |             |

|                                                                   |                                    |                        |                          |                                                                                     |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Title:<br>Rainfall Analysis Criteria                       | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |

|                                 |                          |
|---------------------------------|--------------------------|
| Runoff Type                     | Dynamic                  |
| Output Interval (mins)          | 5                        |
| Time Step                       | Default                  |
| Urban Creep                     | Use Catchment Values     |
| Junction Flood Risk Margin (mm) | 300                      |
| Prefill Manhole Sumps           | <input type="checkbox"/> |
| Perform No Discharge Analysis   | <input type="checkbox"/> |

|                  |                                     |
|------------------|-------------------------------------|
| Rainfall         |                                     |
| FEH              | Type: FEH                           |
| Site Location    | GB 470300 105900 SU 70300 05900     |
| Rainfall Version | 1999                                |
| C (1km)          | -0.029                              |
| D1 (1km)         | 0.459                               |
| D2 (1km)         | 0.300                               |
| D3 (1km)         | 0.375                               |
| E (1km)          | 0.310                               |
| F (1km)          | 2.225                               |
| Summer           | <input checked="" type="checkbox"/> |
| Winter           | <input checked="" type="checkbox"/> |

Return Period

| Return Period (years) | Increase Rainfall (%) |
|-----------------------|-----------------------|
| 1.0                   | 0.000                 |
| 30.0                  | 0.000                 |
| 100.0                 | 45.000                |

Storm Durations

| Duration (mins) | Run Time (mins) |
|-----------------|-----------------|
| 15              | 30              |
| 30              | 60              |
| 60              | 120             |
| 120             | 240             |
| 180             | 360             |
| 240             | 480             |
| 360             | 720             |
| 480             | 960             |
| 600             | 1200            |
| 720             | 1440            |
| 960             | 1920            |
| 1440            | 2880            |
| 2160            | 4320            |
| 2880            | 5760            |
| 4320            | 8640            |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Phase  | Company Address:<br>MJA Consulting |                        |                          |





FEH: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

| Junction | Storm Event                           | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|---------------------------------------|-----------------|------------------|----------------|----------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|------------|
| 1        | FEH: 1 years: +0 %: 15 mins: Summer   | 7.000           | 6.000            | 6.048          | 0.048          | 3.9               | 0.054                     | 0.000                    | 3.5                | 1.680                       | OK         |
| 2        | FEH: 1 years: +0 %: 15 mins: Summer   | 7.150           | 5.950            | 6.006          | 0.056          | 9.6               | 0.063                     | 0.000                    | 9.5                | 4.172                       | OK         |
| 3        | FEH: 1 years: +0 %: 15 mins: Summer   | 7.000           | 5.800            | 5.914          | 0.114          | 16.0              | 0.129                     | 0.000                    | 14.1               | 7.165                       | OK         |
| 4        | FEH: 1 years: +0 %: 15 mins: Summer   | 7.500           | 5.740            | 5.837          | 0.097          | 14.1              | 0.110                     | 0.000                    | 13.1               | 7.143                       | OK         |
| 5        | FEH: 1 years: +0 %: 15 mins: Summer   | 7.350           | 5.640            | 5.705          | 0.065          | 13.1              | 0.074                     | 0.000                    | 12.3               | 7.126                       | OK         |
| 6        | FEH: 1 years: +0 %: 15 mins: Summer   | 6.800           | 5.200            | 5.268          | 0.068          | 12.3              | 0.077                     | 0.000                    | 11.7               | 7.108                       | OK         |
| 7        | FEH: 1 years: +0 %: 15 mins: Summer   | 6.800           | 5.080            | 5.144          | 0.064          | 12.3              | 0.072                     | 0.000                    | 11.7               | 7.384                       | OK         |
| 8        | FEH: 1 years: +0 %: 30 mins: Summer   | 6.400           | 4.640            | 4.706          | 0.066          | 13.1              | 0.075                     | 0.000                    | 13.1               | 11.314                      | OK         |
| 9        | FEH: 1 years: +0 %: 15 mins: Summer   | 6.300           | 4.350            | 4.465          | 0.115          | 32.5              | 0.130                     | 0.000                    | 31.9               | 19.004                      | OK         |
| 10       | FEH: 1 years: +0 %: 30 mins: Summer   | 5.600           | 4.300            | 4.424          | 0.124          | 30.7              | 0.140                     | 0.000                    | 30.7               | 26.412                      | OK         |
| 11       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.350           | 5.000            | 5.070          | 0.070          | 7.2               | 0.079                     | 0.000                    | 6.8                | 3.135                       | OK         |
| 12       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.100           | 4.880            | 4.951          | 0.071          | 7.1               | 0.080                     | 0.000                    | 6.5                | 3.253                       | OK         |
| 13       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.050           | 4.840            | 4.932          | 0.092          | 9.2               | 0.104                     | 0.000                    | 8.8                | 4.447                       | OK         |
| 14       | FEH: 1 years: +0 %: 15 mins: Summer   | 5.950           | 4.820            | 4.909          | 0.089          | 17.8              | 0.101                     | 0.000                    | 17.0               | 8.362                       | OK         |
| 15       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.150           | 4.640            | 4.778          | 0.138          | 18.1              | 0.156                     | 0.000                    | 16.6               | 8.688                       | OK         |
| 16       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.300           | 4.570            | 4.682          | 0.112          | 21.7              | 0.127                     | 0.000                    | 19.8               | 10.887                      | OK         |
| 17       | FEH: 1 years: +0 %: 30 mins: Summer   | 5.600           | 4.170            | 4.318          | 0.148          | 33.3              | 0.168                     | 0.000                    | 33.3               | 28.627                      | OK         |
| 18       | FEH: 1 years: +0 %: 30 mins: Summer   | 5.500           | 4.150            | 4.287          | 0.137          | 34.5              | 0.154                     | 0.000                    | 34.4               | 29.687                      | OK         |
| 19       | FEH: 1 years: +0 %: 30 mins: Summer   | 5.100           | 4.050            | 4.193          | 0.143          | 34.4              | 0.161                     | 0.000                    | 34.3               | 29.647                      | OK         |
| 20       | FEH: 1 years: +0 %: 15 mins: Summer   | 5.050           | 4.000            | 4.141          | 0.141          | 33.9              | 0.159                     | 0.000                    | 35.8               | 21.434                      | OK         |
| 21       | FEH: 1 years: +0 %: 1440 mins: Summer | 5.000           | 3.930            | 4.106          | 0.176          | 7.3               | 0.199                     | 0.000                    | 7.2                | 161.299                     | OK         |
| 22       | FEH: 1 years: +0 %: 1440 mins: Summer | 5.250           | 3.850            | 4.106          | 0.256          | 7.9               | 0.452                     | 0.000                    | 7.7                | 176.715                     | OK         |
| 23       | FEH: 1 years: +0 %: 1440 mins: Summer | 5.250           | 3.790            | 4.106          | 0.316          | 3.3               | 0.558                     | 0.000                    | 3.3                | 322.752                     | Surcharged |
| 24       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.150           | 4.040            | 4.261          | 0.221          | 13.9              | 0.250                     | 0.000                    | 13.4               | 5.864                       | OK         |
| 25       | FEH: 1 years: +0 %: 30 mins: Summer   | 5.350           | 4.020            | 4.165          | 0.145          | 27.4              | 0.164                     | 0.000                    | 26.6               | 24.629                      | OK         |
| 26       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.900           | 5.520            | 5.582          | 0.062          | 6.9               | 0.070                     | 0.000                    | 6.7                | 3.447                       | OK         |
| 27       | FEH: 1 years: +0 %: 15 mins: Summer   | 6.800           | 5.420            | 5.486          | 0.066          | 9.0               | 0.074                     | 0.000                    | 8.6                | 4.451                       | OK         |

|                                                                   |  |  |  |                                    |  |                        |  |                                                                                     |  |  |  |
|-------------------------------------------------------------------|--|--|--|------------------------------------|--|------------------------|--|-------------------------------------------------------------------------------------|--|--|--|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations |  |  |  | Date:<br>25/07/2024                |  |                        |  |  |  |  |  |
|                                                                   |  |  |  | Designed by:<br>S.Smith            |  | Checked by:<br>S.Smith |  |                                                                                     |  |  |  |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Phase  |  |  |  | Company Address:<br>MJA Consulting |  |                        |  |                                                                                     |  |  |  |

|    |                                        |       |       |       |       |      |       |       |      |        |    |
|----|----------------------------------------|-------|-------|-------|-------|------|-------|-------|------|--------|----|
| 28 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.700 | 5.320 | 5.382 | 0.062 | 8.6  | 0.070 | 0.000 | 8.2  | 4.440  | OK |
| 29 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.550 | 5.140 | 5.212 | 0.072 | 12.4 | 0.082 | 0.000 | 11.6 | 6.226  | OK |
| 30 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.400 | 4.850 | 4.952 | 0.102 | 19.0 | 0.115 | 0.000 | 18.1 | 9.426  | OK |
| 31 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.500 | 4.770 | 4.865 | 0.095 | 18.1 | 0.108 | 0.000 | 17.3 | 9.409  | OK |
| 32 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.450 | 4.550 | 4.635 | 0.085 | 17.3 | 0.096 | 0.000 | 16.6 | 9.386  | OK |
| 33 | FEH: 1 years: +0 %:<br>15 mins: Summer | 6.250 | 4.510 | 4.573 | 0.063 | 18.8 | 0.071 | 0.000 | 18.4 | 10.358 | OK |
| 34 | FEH: 1 years: +0 %:<br>15 mins: Summer | 5.350 | 4.040 | 4.278 | 0.238 | 20.4 | 0.269 | 0.000 | 19.0 | 11.168 | OK |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Phase  | Company Address:<br>MJA Consulting |                        |                          |





FEH: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|------------|
| 1        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 7.000           | 6.000            | 6.111          | 0.111          | 12.7              | 0.126                     | 0.000                    | 7.3                | 5.537                       | OK         |
| 2        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 7.150           | 5.950            | 6.143          | 0.193          | 31.5              | 0.219                     | 0.000                    | 29.5               | 13.650                      | OK         |
| 3        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 7.000           | 5.800            | 6.107          | 0.307          | 47.0              | 0.347                     | 0.000                    | 43.8               | 23.509                      | Surcharged |
| 4        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 7.500           | 5.740            | 5.946          | 0.206          | 43.8              | 0.233                     | 0.000                    | 41.8               | 23.489                      | OK         |
| 5        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 7.350           | 5.640            | 5.770          | 0.130          | 41.8              | 0.147                     | 0.000                    | 40.6               | 23.468                      | OK         |
| 6        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.800           | 5.200            | 5.344          | 0.144          | 40.6              | 0.163                     | 0.000                    | 39.6               | 23.445                      | OK         |
| 7        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.800           | 5.080            | 5.211          | 0.131          | 41.8              | 0.148                     | 0.000                    | 41.0               | 24.380                      | OK         |
| 8        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.400           | 4.640            | 4.782          | 0.142          | 46.8              | 0.161                     | 0.000                    | 45.4               | 26.860                      | OK         |
| 9        | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.300           | 4.350            | 4.612          | 0.262          | 113.6             | 0.296                     | 0.000                    | 112.4              | 62.920                      | OK         |
| 10       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 5.600           | 4.300            | 4.568          | 0.268          | 112.4             | 0.303                     | 0.000                    | 105.7              | 62.855                      | OK         |
| 11       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.350           | 5.000            | 5.139          | 0.139          | 23.6              | 0.157                     | 0.000                    | 22.6               | 10.249                      | OK         |
| 12       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.100           | 4.880            | 5.062          | 0.182          | 23.5              | 0.206                     | 0.000                    | 21.0               | 10.657                      | OK         |
| 13       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.050           | 4.840            | 5.044          | 0.204          | 30.1              | 0.231                     | 0.000                    | 29.0               | 14.570                      | OK         |
| 14       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 5.950           | 4.820            | 5.011          | 0.191          | 58.5              | 0.216                     | 0.000                    | 56.1               | 27.359                      | OK         |
| 15       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.150           | 4.640            | 4.897          | 0.257          | 59.9              | 0.291                     | 0.000                    | 55.7               | 28.826                      | OK         |
| 16       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.300           | 4.570            | 4.814          | 0.244          | 72.5              | 0.276                     | 0.000                    | 68.1               | 36.079                      | OK         |
| 17       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 5.600           | 4.170            | 4.473          | 0.303          | 118.0             | 0.342                     | 0.000                    | 109.6              | 68.080                      | OK         |
| 18       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.500           | 4.150            | 4.462          | 0.312          | 13.4              | 0.352                     | 0.000                    | 13.3               | 303.832                     | OK         |
| 19       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.100           | 4.050            | 4.462          | 0.412          | 13.3              | 0.465                     | 0.000                    | 13.0               | 301.872                     | OK         |
| 20       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.050           | 4.000            | 4.462          | 0.462          | 13.3              | 0.522                     | 0.000                    | 13.0               | 305.345                     | Surcharged |
| 21       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.000           | 3.930            | 4.462          | 0.532          | 13.0              | 0.601                     | 0.000                    | 12.7               | 302.062                     | Surcharged |
| 22       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.250           | 3.850            | 4.462          | 0.612          | 14.0              | 1.081                     | 0.000                    | 13.7               | 327.624                     | Surcharged |
| 23       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.250           | 3.790            | 4.461          | 0.671          | 3.4               | 1.187                     | 0.000                    | 3.3                | 319.668                     | Surcharged |
| 24       | FEH: 30 years: +0 %:<br>960 mins: Winter | 6.150           | 4.040            | 4.462          | 0.422          | 3.7               | 0.477                     | 0.000                    | 3.7                | 84.564                      | Surcharged |
| 25       | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.350           | 4.020            | 4.462          | 0.442          | 10.4              | 0.499                     | 0.000                    | 9.7                | 252.581                     | Surcharged |
| 26       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.900           | 5.520            | 5.646          | 0.126          | 22.6              | 0.142                     | 0.000                    | 22.0               | 11.296                      | OK         |
| 27       | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.800           | 5.420            | 5.555          | 0.135          | 29.6              | 0.152                     | 0.000                    | 28.6               | 14.585                      | OK         |

|                                                                   |  |                                    |                        |                          |                                                                                     |  |  |
|-------------------------------------------------------------------|--|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|--|--|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations |  | Date:<br>25/07/2024                |                        |                          |  |  |  |
|                                                                   |  | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |  |  |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Phase  |  | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |  |  |

|    |                                          |       |       |       |       |      |       |       |      |         |            |
|----|------------------------------------------|-------|-------|-------|-------|------|-------|-------|------|---------|------------|
| 28 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.700 | 5.320 | 5.448 | 0.128 | 28.6 | 0.145 | 0.000 | 27.5 | 14.564  | OK         |
| 29 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.550 | 5.140 | 5.293 | 0.153 | 41.1 | 0.173 | 0.000 | 35.6 | 20.431  | OK         |
| 30 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.400 | 4.850 | 5.170 | 0.320 | 59.9 | 0.362 | 0.000 | 57.6 | 30.927  | Surcharged |
| 31 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.500 | 4.770 | 5.028 | 0.258 | 57.6 | 0.291 | 0.000 | 54.9 | 30.910  | Surcharged |
| 32 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.450 | 4.550 | 4.713 | 0.163 | 54.9 | 0.184 | 0.000 | 53.5 | 30.880  | OK         |
| 33 | FEH: 30 years: +0 %:<br>15 mins: Summer  | 6.250 | 4.510 | 4.629 | 0.119 | 60.8 | 0.135 | 0.000 | 60.0 | 34.048  | OK         |
| 34 | FEH: 30 years: +0 %:<br>960 mins: Winter | 5.350 | 4.040 | 4.462 | 0.422 | 7.2  | 0.477 | 0.000 | 7.2  | 163.132 | Surcharged |

|                                                                   |                                    |                        |                          |
|-------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                |                        |                          |
|                                                                   | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Phase  | Company Address:<br>MJA Consulting |                        |                          |





FEH: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Depth

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|------------|
| 1        | FEH: 100 years: +45 %: 15 mins: Summer   | 7.000           | 6.000            | 7.005          | 1.005          | 28.3              | 5.727                     | 4.596                    | 11.7               | 12.418                      | Flood      |
| 2        | FEH: 100 years: +45 %: 15 mins: Summer   | 7.150           | 5.950            | 7.150          | 1.200          | 69.9              | 1.597                     | 0.240                    | 59.2               | 30.336                      | Flood      |
| 3        | FEH: 100 years: +45 %: 15 mins: Summer   | 7.000           | 5.800            | 7.000          | 1.200          | 90.5              | 1.749                     | 0.392                    | 74.6               | 52.382                      | Flood      |
| 4        | FEH: 100 years: +45 %: 30 mins: Summer   | 7.500           | 5.740            | 6.657          | 0.917          | 67.8              | 1.037                     | 0.000                    | 67.2               | 65.559                      | Surcharged |
| 5        | FEH: 100 years: +45 %: 15 mins: Summer   | 7.350           | 5.640            | 6.320          | 0.680          | 72.0              | 0.770                     | 0.000                    | 67.3               | 52.315                      | Surcharged |
| 6        | FEH: 100 years: +45 %: 15 mins: Summer   | 6.800           | 5.200            | 5.886          | 0.686          | 67.3              | 0.776                     | 0.000                    | 68.0               | 52.339                      | Surcharged |
| 7        | FEH: 100 years: +45 %: 15 mins: Summer   | 6.800           | 5.080            | 5.704          | 0.624          | 69.1              | 0.706                     | 0.000                    | 71.4               | 54.496                      | Surcharged |
| 8        | FEH: 100 years: +45 %: 30 mins: Summer   | 6.400           | 4.640            | 5.212          | 0.572          | 74.9              | 0.647                     | 0.000                    | 74.1               | 75.189                      | Surcharged |
| 9        | FEH: 100 years: +45 %: 15 mins: Summer   | 6.300           | 4.350            | 5.037          | 0.687          | 198.5             | 0.777                     | 0.000                    | 192.6              | 140.543                     | Surcharged |
| 10       | FEH: 100 years: +45 %: 15 mins: Summer   | 5.600           | 4.300            | 4.989          | 0.689          | 192.6             | 0.779                     | 0.000                    | 185.8              | 140.486                     | Surcharged |
| 11       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.350           | 5.000            | 6.171          | 1.171          | 52.5              | 1.324                     | 0.000                    | 42.2               | 22.823                      | Flood Risk |
| 12       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.100           | 4.880            | 5.979          | 1.099          | 44.4              | 1.243                     | 0.000                    | 35.0               | 23.787                      | Flood Risk |
| 13       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.050           | 4.840            | 5.927          | 1.087          | 55.1              | 1.229                     | 0.000                    | 48.2               | 32.538                      | Flood Risk |
| 14       | FEH: 100 years: +45 %: 15 mins: Summer   | 5.950           | 4.820            | 5.858          | 1.038          | 111.2             | 1.174                     | 0.000                    | 102.0              | 60.932                      | Flood Risk |
| 15       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.150           | 4.640            | 5.569          | 0.929          | 110.5             | 1.050                     | 0.000                    | 102.2              | 64.475                      | Surcharged |
| 16       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.300           | 4.570            | 5.335          | 0.765          | 139.5             | 0.865                     | 0.000                    | 132.3              | 80.277                      | Surcharged |
| 17       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.600           | 4.170            | 4.941          | 0.771          | 17.3              | 0.873                     | 0.000                    | 17.0               | 593.170                     | Surcharged |
| 18       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.500           | 4.150            | 4.941          | 0.791          | 17.6              | 0.895                     | 0.000                    | 17.4               | 611.786                     | Surcharged |
| 19       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.100           | 4.050            | 4.941          | 0.891          | 17.4              | 1.008                     | 0.000                    | 17.3               | 607.262                     | Flood Risk |
| 20       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.050           | 4.000            | 4.941          | 0.941          | 17.7              | 1.065                     | 0.000                    | 17.6               | 614.976                     | Flood Risk |
| 21       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.000           | 3.930            | 4.941          | 1.011          | 17.6              | 1.144                     | 0.000                    | 17.5               | 610.260                     | Flood Risk |
| 22       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.250           | 3.850            | 4.941          | 1.091          | 19.3              | 1.928                     | 0.000                    | 19.3               | 665.956                     | Surcharged |
| 23       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.250           | 3.790            | 4.941          | 1.151          | 3.4               | 2.034                     | 0.000                    | 3.3                | 492.213                     | Surcharged |
| 24       | FEH: 100 years: +45 %: 1440 mins: Winter | 6.150           | 4.040            | 4.941          | 0.901          | 5.1               | 1.019                     | 0.000                    | 5.0                | 173.305                     | Surcharged |
| 25       | FEH: 100 years: +45 %: 1440 mins: Winter | 5.350           | 4.020            | 4.941          | 0.921          | 12.4              | 1.042                     | 0.000                    | 10.0               | 483.347                     | Surcharged |
| 26       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.900           | 5.520            | 6.735          | 1.215          | 50.0              | 1.374                     | 0.000                    | 38.7               | 25.131                      | Flood Risk |
| 27       | FEH: 100 years: +45 %: 15 mins: Summer   | 6.800           | 5.420            | 6.734          | 1.314          | 55.6              | 1.486                     | 0.000                    | 44.8               | 32.480                      | Flood Risk |

|                                                                          |  |  |  |                                           |  |                               |  |                                                                                     |  |  |  |
|--------------------------------------------------------------------------|--|--|--|-------------------------------------------|--|-------------------------------|--|-------------------------------------------------------------------------------------|--|--|--|
| <b>Project:</b><br>Land west of Manor Farm<br>Surface Water Calculations |  |  |  | <b>Date:</b><br>25/07/2024                |  |                               |  |  |  |  |  |
|                                                                          |  |  |  | <b>Designed by:</b><br>S.Smith            |  | <b>Checked by:</b><br>S.Smith |  |                                                                                     |  |  |  |
| <b>Report Details:</b><br>Type: Junctions Summary<br>Storm Phase: Phase  |  |  |  | <b>Company Address:</b><br>MJA Consulting |  |                               |  |                                                                                     |  |  |  |

|    |                                             |       |       |       |       |       |       |       |       |         |            |
|----|---------------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|---------|------------|
| 28 | FEH: 100 years: +45<br>%: 15 mins: Summer   | 6.700 | 5.320 | 6.700 | 1.380 | 44.8  | 1.648 | 0.088 | 45.5  | 32.494  | Flood      |
| 29 | FEH: 100 years: +45<br>%: 15 mins: Summer   | 6.550 | 5.140 | 6.551 | 1.411 | 64.6  | 2.093 | 0.498 | 73.5  | 45.612  | Flood      |
| 30 | FEH: 100 years: +45<br>%: 15 mins: Summer   | 6.400 | 4.850 | 6.094 | 1.244 | 108.5 | 1.407 | 0.000 | 100.4 | 68.940  | Surcharged |
| 31 | FEH: 100 years: +45<br>%: 15 mins: Summer   | 6.500 | 4.770 | 5.671 | 0.901 | 100.4 | 1.019 | 0.000 | 94.4  | 68.920  | Surcharged |
| 32 | FEH: 100 years: +45<br>%: 1440 mins: Winter | 6.450 | 4.550 | 4.941 | 0.391 | 8.0   | 0.443 | 0.000 | 8.0   | 271.793 | Surcharged |
| 33 | FEH: 100 years: +45<br>%: 1440 mins: Winter | 6.250 | 4.510 | 4.941 | 0.431 | 8.8   | 0.488 | 0.000 | 8.8   | 298.882 | Surcharged |
| 34 | FEH: 100 years: +45<br>%: 1440 mins: Winter | 5.350 | 4.040 | 4.941 | 0.901 | 9.8   | 1.019 | 0.000 | 9.8   | 329.091 | Surcharged |

|                                                                            |  |                                    |                        |                                                                                     |                          |
|----------------------------------------------------------------------------|--|------------------------------------|------------------------|-------------------------------------------------------------------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations          |  | Date:<br>25/07/2024                |                        |  |                          |
|                                                                            |  | Designed by:<br>S.Smith            | Checked by:<br>S.Smith |                                                                                     | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase |  | Company Address:<br>MJA Consulting |                        |                                                                                     |                          |



FEH: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

| Stormwater Control | Storm Event                           | Max. US Level (m) | Max. DS Level (m) | Max. Avg. Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Avg. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Total Lost Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) |
|--------------------|---------------------------------------|-------------------|-------------------|---------------------|-------------------|-------------------|---------------------|-------------------|---------------------------|--------------------------|------------------------|--------------------|-----------------------------|-----------------------------|
| Swale              | FEH: 1 years: +0 %: 15 mins: Summer   | 4.643             | 4.517             | 4.540               | 0.047             | 0.017             | 0.040               | 2.8               | 0.344                     | 0.000                    | 0.000                  | 2.0                | 1.220                       | 4                           |
| Swale (1)          | FEH: 1 years: +0 %: 30 mins: Summer   | 4.258             | 4.175             | 4.168               | 0.116             | 0.125             | 0.118               | 18.2              | 1.683                     | 0.000                    | 0.000                  | 17.8               | 15.655                      | 2                           |
| Swale (2)          | FEH: 1 years: +0 %: 30 mins: Summer   | 4.165             | 4.165             | 4.118               | 0.022             | 0.115             | 0.068               | 2.1               | 0.792                     | 0.000                    | 0.000                  | 2.0                | 0.809                       |                             |
| Swale (3)          | FEH: 1 years: +0 %: 1440 mins: Summer | 3.767             | 3.765             | 3.599               | 0.083             | 0.415             | 0.249               | 3.3               | 26.770                    | 0.000                    | 0.000                  | 3.3                | 297.957                     | 138                         |
| Basin              | FEH: 1 years: +0 %: 1440 mins: Summer | 4.106             | 4.106             | 4.106               | 0.316             | 0.316             | 0.316               | 15.3              | 199.376                   | 0.000                    | 0.000                  | 3.3                | 322.874                     | 551                         |

|                                                                   |                                                                            |                        |                          |                                                                                     |
|-------------------------------------------------------------------|----------------------------------------------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                                                        |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith                                                    | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
|                                                                   | Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase |                        |                          |                                                                                     |
| Company Address:<br>MJA Consulting                                |                                                                            |                        |                          |                                                                                     |

| Percentage Available (%) | Status     |
|--------------------------|------------|
| 98.253                   | OK         |
| 97.642                   | OK         |
| 98.895                   | OK         |
| 15.913                   | Flood Risk |
| 79.118                   | OK         |

|                                                                            |  |                                    |                        |                                                                                     |                          |
|----------------------------------------------------------------------------|--|------------------------------------|------------------------|-------------------------------------------------------------------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations          |  | Date:<br>25/07/2024                |                        |  |                          |
|                                                                            |  | Designed by:<br>S.Smith            | Checked by:<br>S.Smith |                                                                                     | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase |  | Company Address:<br>MJA Consulting |                        |                                                                                     |                          |



FEH: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

| Stormwater Control | Storm Event                            | Max. US Level (m) | Max. DS Level (m) | Max. Avg. Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Avg. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Total Lost Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) |
|--------------------|----------------------------------------|-------------------|-------------------|---------------------|-------------------|-------------------|---------------------|-------------------|---------------------------|--------------------------|------------------------|--------------------|-----------------------------|-----------------------------|
| Swale              | FEH: 30 years: +0 %: 15 mins: Summer   | 4.679             | 4.532             | 4.571               | 0.082             | 0.032             | 0.071               | 9.3               | 0.813                     | 0.000                    | 0.000                  | 7.7                | 4.022                       | 2                           |
| Swale (1)          | FEH: 30 years: +0 %: 960 mins: Winter  | 4.462             | 4.462             | 4.415               | 0.320             | 0.412             | 0.365               | 7.2               | 12.818                    | 0.000                    | 0.000                  | 6.7                | 159.599                     | 19                          |
| Swale (2)          | FEH: 30 years: +0 %: 960 mins: Winter  | 4.461             | 4.462             | 4.415               | 0.319             | 0.412             | 0.365               | 0.9               | 12.859                    | 0.000                    | 0.000                  | 0.4                | 9.329                       |                             |
| Swale (3)          | FEH: 30 years: +0 %: 1440 mins: Summer | 3.767             | 3.766             | 3.599               | 0.084             | 0.416             | 0.249               | 3.3               | 26.786                    | 0.000                    | 0.000                  | 3.3                | 455.519                     | 135                         |
| Basin              | FEH: 30 years: +0 %: 960 mins: Winter  | 4.462             | 4.462             | 4.462               | 0.672             | 0.672             | 0.672               | 26.6              | 475.354                   | 0.000                    | 0.000                  | 3.4                | 320.959                     | 1193                        |

|                                                                   |                                                                            |                        |                          |                                                                                     |
|-------------------------------------------------------------------|----------------------------------------------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                                                        |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith                                                    | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
|                                                                   | Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase |                        |                          |                                                                                     |
| Company Address:<br>MJA Consulting                                |                                                                            |                        |                          |                                                                                     |

| Percentage Available (%) | Status     |
|--------------------------|------------|
| 95.874                   | OK         |
| 82.039                   | OK         |
| 82.060                   | OK         |
| 15.861                   | Flood Risk |
| 50.213                   | OK         |

|                                                                            |                                    |                        |                          |                                                                                     |
|----------------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations          | Date:<br>25/07/2024                |                        |                          |  |
|                                                                            | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |



**FEH: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Avg. Depth**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. Avg. Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Avg. Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Total Lost Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) |
|--------------------|------------------------------------------|-------------------|-------------------|---------------------|-------------------|-------------------|---------------------|-------------------|---------------------------|--------------------------|------------------------|--------------------|-----------------------------|-----------------------------|
| Swale              | FEH: 100 years: +45 %: 1440 mins: Winter | 4.941             | 4.941             | 4.893               | 0.344             | 0.441             | 0.393               | 1.0               | 15.377                    | 0.000                    | 0.000                  | 1.0                | 32.430                      | 287                         |
| Swale (1)          | FEH: 100 years: +45 %: 1440 mins: Winter | 4.942             | 4.941             | 4.895               | 0.799             | 0.891             | 0.845               | 9.8               | 63.250                    | 0.000                    | 0.000                  | 7.3                | 289.267                     | 86                          |
| Swale (2)          | FEH: 100 years: +45 %: 1440 mins: Winter | 4.941             | 4.941             | 4.895               | 0.798             | 0.891             | 0.845               | 2.7               | 63.488                    | 0.000                    | 0.000                  | 0.6                | 25.216                      |                             |
| Swale (3)          | FEH: 100 years: +45 %: 2160 mins: Winter | 3.767             | 3.766             | 3.599               | 0.084             | 0.416             | 0.249               | 3.3               | 26.786                    | 0.000                    | 0.000                  | 3.3                | 701.274                     | 140                         |
| Basin              | FEH: 100 years: +45 %: 1440 mins: Winter | 4.941             | 4.941             | 4.941               | 1.151             | 1.151             | 1.151               | 33.5              | 945.034                   | 0.000                    | 0.000                  | 3.4                | 494.415                     | 2457                        |

|                                                                            |                                    |                        |                          |                                                                                     |
|----------------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations          | Date:<br>25/07/2024                |                        |                          |  |
|                                                                            | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |

| Percentage Available (%) | Status     |
|--------------------------|------------|
| 21.968                   | OK         |
| 11.378                   | OK         |
| 11.427                   | OK         |
| 15.861                   | Flood Risk |
| 1.021                    | OK         |

|                                                                    |                                    |                        |                          |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |



FEH: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

| Connection | Storm Event                         | Connection Type | From | To | Upstream Cover Level (m) | Max. US Water Level (m) | Max. Flow Depth (m) | Discharge Volume (m³) | Max. Velocity (m/s) | Flow / Capacity | Max. Flow (L/s) | Status |
|------------|-------------------------------------|-----------------|------|----|--------------------------|-------------------------|---------------------|-----------------------|---------------------|-----------------|-----------------|--------|
| 1.000      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 1    | 3  | 7.000                    | 6.048                   | 0.081               | 1.680                 | 0.3                 | 0.1             | 3.5             | OK     |
| 2.000      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 2    | 3  | 7.150                    | 6.006                   | 0.085               | 4.172                 | 0.7                 | 0.14            | 9.5             | OK     |
| 1.001      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 3    | 4  | 7.000                    | 5.914                   | 0.106               | 7.165                 | 0.8                 | 0.46            | 14.1            | OK     |
| 1.002      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 4    | 5  | 7.500                    | 5.837                   | 0.081               | 7.143                 | 1.0                 | 0.36            | 13.1            | OK     |
| 1.003      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 5    | 6  | 7.350                    | 5.705                   | 0.067               | 7.126                 | 1.2                 | 0.17            | 12.3            | OK     |
| 1.004      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 6    | 7  | 6.800                    | 5.268                   | 0.066               | 7.108                 | 1.2                 | 0.17            | 11.7            | OK     |
| 1.005      | FEH: 1 years: +0 %: 30 mins: Summer | Pipe            | 7    | 8  | 6.800                    | 5.144                   | 0.065               | 10.265                | 1.2                 | 0.17            | 11.9            | OK     |
| 1.006      | FEH: 1 years: +0 %: 30 mins: Summer | Pipe            | 8    | 9  | 6.400                    | 4.706                   | 0.063               | 11.314                | 1.4                 | 0.16            | 13.1            | OK     |
| 3.000      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 11   | 12 | 6.350                    | 5.070                   | 0.070               | 3.135                 | 0.6                 | 0.2             | 6.8             | OK     |
| 3.001      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 12   | 13 | 6.100                    | 4.951                   | 0.081               | 3.253                 | 0.5                 | 0.18            | 6.5             | OK     |
| 3.002      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 13   | 14 | 6.050                    | 4.932                   | 0.090               | 4.447                 | 0.6                 | 0.27            | 8.8             | OK     |
| 3.003      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 14   | 15 | 5.950                    | 4.909                   | 0.114               | 8.362                 | 0.7                 | 0.19            | 17.0            | OK     |
| 3.004      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 15   | 16 | 6.150                    | 4.778                   | 0.105               | 8.688                 | 0.7                 | 0.21            | 16.6            | OK     |
| 3.005      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 16   | 9  | 6.300                    | 4.682                   | 0.108               | 10.887                | 0.9                 | 0.26            | 19.8            | OK     |
| 1.007      | FEH: 1 years: +0 %: 15 mins: Summer | Pipe            | 9    | 10 | 6.300                    | 4.465                   | 0.119               | 19.004                | 0.9                 | 0.08            | 31.9            | OK     |
| 1.008      | FEH: 1 years: +0 %: 30 mins: Summer | Pipe            | 10   | 17 | 5.600                    | 4.424                   | 0.136               | 26.412                | 0.8                 | 0.16            | 30.7            | OK     |
| 1.009      | FEH: 1 years: +0 %: 30 mins: Summer | Pipe            | 17   | 18 | 5.600                    | 4.318                   | 0.142               | 28.627                | 0.8                 | 0.19            | 33.3            | OK     |

|                                                                    |                                    |                        |                          |                                                                                     |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |  |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
| Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |                                                                                     |

|       |                                             |      |           |           |       |       |       |         |     |      |      |                |
|-------|---------------------------------------------|------|-----------|-----------|-------|-------|-------|---------|-----|------|------|----------------|
| 1.010 | FEH: 1 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | 18        | 19        | 5.500 | 4.287 | 0.140 | 29.687  | 0.8 | 0.18 | 34.4 | OK             |
| 1.011 | FEH: 1 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | 19        | 20        | 5.100 | 4.193 | 0.141 | 29.647  | 0.8 | 0.18 | 34.3 | OK             |
| 1.012 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 20        | 21        | 5.050 | 4.141 | 0.143 | 21.434  | 0.8 | 0.19 | 35.8 | OK             |
| 1.013 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 21        | 22        | 5.000 | 4.075 | 0.141 | 21.294  | 0.9 | 0.21 | 37.8 | OK             |
| 4.000 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 26        | 27        | 6.900 | 5.582 | 0.064 | 3.447   | 0.7 | 0.15 | 6.7  | OK             |
| 4.001 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 27        | 28        | 6.800 | 5.486 | 0.064 | 4.451   | 0.9 | 0.16 | 8.6  | OK             |
| 4.002 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 28        | 29        | 6.700 | 5.382 | 0.067 | 4.440   | 0.8 | 0.16 | 8.2  | OK             |
| 4.003 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 29        | 30        | 6.550 | 5.212 | 0.087 | 6.226   | 0.8 | 0.22 | 11.6 | OK             |
| 4.004 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 30        | 31        | 6.400 | 4.952 | 0.099 | 9.426   | 1.1 | 0.35 | 18.1 | OK             |
| 4.005 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 31        | 32        | 6.500 | 4.865 | 0.090 | 9.409   | 1.2 | 0.34 | 17.3 | OK             |
| 4.006 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 32        | 33        | 6.450 | 4.635 | 0.074 | 9.386   | 1.2 | 0.15 | 16.6 | OK             |
| 4.007 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 33        | 34        | 6.250 | 4.573 | 0.150 | 10.358  | 0.5 | 0.1  | 18.4 | OK             |
| 6.000 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 24        | 25        | 6.150 | 4.261 | 0.140 | 0.000   | 0.4 | 0.25 | 13.4 | OK             |
| 5.000 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | Swale     | 34        | 5.400 | 4.540 | 0.072 | 1.220   | 0.2 | 0.01 | 2.0  | OK             |
| 4.008 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 34        | Swale (1) | 5.350 | 4.278 | 0.121 | 11.168  | 0.7 | 0.21 | 19.0 | OK             |
| 4.009 | FEH: 1 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | Swale (1) | 25        | 5.350 | 4.168 | 0.135 | 15.641  | 0.6 | 0.18 | 17.8 | OK             |
| 7.000 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | Swale (2) | 25        | 5.350 | 4.116 | 0.126 | 0.002   | 0.1 | 0.03 | 3.0  | OK             |
| 4.010 | FEH: 1 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | 25        | Basin     | 5.350 | 4.165 | 0.134 | 23.670  | 0.9 | 0.44 | 26.6 | OK             |
| 1.015 | FEH: 1 years:<br>+0 %: 1440<br>mins: Summer | Pipe | Basin     | 23        | 5.250 | 4.106 | 0.316 | 322.835 | 0.1 | 0.03 | 3.3  | OK             |
| 1.016 | FEH: 1 years:<br>+0 %: 1440<br>mins: Summer | Pipe | 23        | Swale (3) | 5.250 | 4.106 | 0.060 | 322.738 | 0.5 | 0.05 | 3.3  | Surchar<br>ged |
| 1.014 | FEH: 1 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 22        | Basin     | 5.250 | 3.988 | 0.104 | 23.306  | 1.5 | 0.23 | 40.6 | OK             |

|                                                                    |                                    |                        |                          |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |





FEH: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

| Connection | Storm Event                          | Connection Type | From | To | Upstream Cover Level (m) | Max. US Water Level (m) | Max. Flow Depth (m) | Discharge Volume (m³) | Max. Velocity (m/s) | Flow / Capacity | Max. Flow (L/s) | Status     |
|------------|--------------------------------------|-----------------|------|----|--------------------------|-------------------------|---------------------|-----------------------|---------------------|-----------------|-----------------|------------|
| 1.000      | FEH: 30 years: +0 %: 30 mins: Summer | Pipe            | 1    | 3  | 7.000                    | 6.074                   | 0.147               | 7.106                 | 0.3                 | 0.24            | 8.2             | OK         |
| 2.000      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 2    | 3  | 7.150                    | 6.143                   | 0.225               | 13.650                | 0.7                 | 0.43            | 29.5            | OK         |
| 1.001      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 3    | 4  | 7.000                    | 6.107                   | 0.225               | 23.509                | 1.1                 | 1.45            | 43.8            | Surcharged |
| 1.002      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 4    | 5  | 7.500                    | 5.946                   | 0.168               | 23.489                | 1.3                 | 1.15            | 41.8            | OK         |
| 1.003      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 5    | 6  | 7.350                    | 5.770                   | 0.137               | 23.468                | 1.6                 | 0.57            | 40.6            | OK         |
| 1.004      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 6    | 7  | 6.800                    | 5.344                   | 0.138               | 23.445                | 1.6                 | 0.57            | 39.6            | OK         |
| 1.005      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 7    | 8  | 6.800                    | 5.211                   | 0.137               | 24.380                | 1.6                 | 0.58            | 41.0            | OK         |
| 1.006      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 8    | 9  | 6.400                    | 4.782                   | 0.130               | 26.860                | 1.9                 | 0.54            | 45.4            | OK         |
| 3.000      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 11   | 12 | 6.350                    | 5.139                   | 0.160               | 10.249                | 0.7                 | 0.65            | 22.6            | OK         |
| 3.001      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 12   | 13 | 6.100                    | 5.062                   | 0.193               | 10.657                | 0.6                 | 0.57            | 21.0            | OK         |
| 3.002      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 13   | 14 | 6.050                    | 5.044                   | 0.197               | 14.570                | 0.8                 | 0.9             | 29.0            | OK         |
| 3.003      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 14   | 15 | 5.950                    | 5.011                   | 0.224               | 27.359                | 1.0                 | 0.64            | 56.1            | OK         |
| 3.004      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 15   | 16 | 6.150                    | 4.897                   | 0.230               | 28.826                | 1.0                 | 0.71            | 55.7            | OK         |
| 3.005      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 16   | 9  | 6.300                    | 4.814                   | 0.224               | 36.079                | 1.2                 | 0.9             | 68.1            | OK         |
| 1.007      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 9    | 10 | 6.300                    | 4.612                   | 0.265               | 62.920                | 1.2                 | 0.28            | 112.4           | OK         |
| 1.008      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 10   | 17 | 5.600                    | 4.568                   | 0.286               | 62.855                | 1.0                 | 0.55            | 105.7           | OK         |
| 1.009      | FEH: 30 years: +0 %: 15 mins: Summer | Pipe            | 17   | 18 | 5.600                    | 4.473                   | 0.289               | 68.080                | 1.0                 | 0.63            | 109.6           | OK         |

|                                                                   |                                                                    |                        |                          |                                                                                     |
|-------------------------------------------------------------------|--------------------------------------------------------------------|------------------------|--------------------------|-------------------------------------------------------------------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations | Date:<br>25/07/2024                                                |                        |                          |  |
|                                                                   | Designed by:<br>S.Smith                                            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |                                                                                     |
|                                                                   | Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase |                        |                          |                                                                                     |
|                                                                   | Company Address:<br>MJA Consulting                                 |                        |                          |                                                                                     |

|       |                                              |      |           |           |       |       |       |         |     |      |       |                |
|-------|----------------------------------------------|------|-----------|-----------|-------|-------|-------|---------|-----|------|-------|----------------|
| 1.010 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 18        | 19        | 5.500 | 4.426 | 0.274 | 70.565  | 1.1 | 0.57 | 108.6 | OK             |
| 1.011 | FEH: 30 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | 19        | 20        | 5.100 | 4.335 | 0.280 | 91.078  | 1.0 | 0.56 | 104.9 | OK             |
| 1.012 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 20        | 21        | 5.050 | 4.280 | 0.278 | 71.644  | 1.1 | 0.57 | 108.9 | OK             |
| 1.013 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 21        | 22        | 5.000 | 4.206 | 0.261 | 70.946  | 1.2 | 0.63 | 114.9 | OK             |
| 4.000 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 26        | 27        | 6.900 | 5.646 | 0.130 | 11.296  | 0.9 | 0.5  | 22.0  | OK             |
| 4.001 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 27        | 28        | 6.800 | 5.555 | 0.132 | 14.585  | 1.2 | 0.55 | 28.6  | OK             |
| 4.002 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 28        | 29        | 6.700 | 5.448 | 0.141 | 14.564  | 1.1 | 0.52 | 27.5  | OK             |
| 4.003 | FEH: 30 years:<br>+0 %: 15 mins:<br>Winter   | Pipe | 29        | 30        | 6.550 | 5.281 | 0.217 | 20.427  | 0.9 | 0.71 | 37.2  | OK             |
| 4.004 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 30        | 31        | 6.400 | 5.170 | 0.225 | 30.927  | 1.4 | 1.11 | 57.6  | Surchar<br>ged |
| 4.005 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 31        | 32        | 6.500 | 5.028 | 0.210 | 30.910  | 1.4 | 1.07 | 54.9  | Surchar<br>ged |
| 4.006 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 32        | 33        | 6.450 | 4.713 | 0.141 | 30.880  | 1.6 | 0.48 | 53.5  | OK             |
| 4.007 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 33        | 34        | 6.250 | 4.629 | 0.237 | 34.048  | 1.0 | 0.34 | 60.0  | OK             |
| 6.000 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 24        | 25        | 6.150 | 4.358 | 0.213 | 0.000   | 0.8 | 0.85 | 45.0  | Surchar<br>ged |
| 5.000 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | Swale     | 34        | 5.400 | 4.571 | 0.138 | 4.022   | 0.2 | 0.03 | 7.7   | OK             |
| 4.008 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 34        | Swale (1) | 5.350 | 4.395 | 0.223 | 37.639  | 1.2 | 0.72 | 66.2  | OK             |
| 4.009 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | Swale (1) | 25        | 5.350 | 4.302 | 0.294 | 37.523  | 0.8 | 0.6  | 58.2  | OK             |
| 7.000 | FEH: 30 years:<br>+0 %: 30 mins:<br>Summer   | Pipe | Swale (2) | 25        | 5.350 | 4.252 | 0.264 | 0.000   | 0.2 | 0.11 | 11.3  | OK             |
| 4.010 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 25        | Basin     | 5.350 | 4.316 | 0.258 | 56.921  | 1.2 | 1.32 | 80.5  | OK             |
| 1.015 | FEH: 30 years:<br>+0 %: 2880<br>mins: Winter | Pipe | Basin     | 23        | 5.250 | 4.396 | 0.450 | 811.476 | 0.1 | 0.04 | 4.3   | Surchar<br>ged |
| 1.016 | FEH: 30 years:<br>+0 %: 480<br>mins: Winter  | Pipe | 23        | Swale (3) | 5.250 | 4.409 | 0.060 | 158.765 | 0.6 | 0.05 | 3.3   | Surchar<br>ged |
| 1.014 | FEH: 30 years:<br>+0 %: 15 mins:<br>Summer   | Pipe | 22        | Basin     | 5.250 | 4.097 | 0.208 | 76.318  | 2.0 | 0.68 | 120.7 | OK             |

|                                                                    |                                    |                        |                          |
|--------------------------------------------------------------------|------------------------------------|------------------------|--------------------------|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  | Date:<br>25/07/2024                |                        |                          |
|                                                                    | Designed by:<br>S.Smith            | Checked by:<br>S.Smith | Approved By:<br>C.Pendle |
| Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase | Company Address:<br>MJA Consulting |                        |                          |





FEH: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Flow

| Connection | Storm Event                            | Connection Type | From | To | Upstream Cover Level (m) | Max. US Water Level (m) | Max. Flow Depth (m) | Discharge Volume (m³) | Max. Velocity (m/s) | Flow / Capacity | Max. Flow (L/s) | Status     |
|------------|----------------------------------------|-----------------|------|----|--------------------------|-------------------------|---------------------|-----------------------|---------------------|-----------------|-----------------|------------|
| 1.000      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 1    | 3  | 7.000                    | 7.004                   | 0.225               | 12.416                | 0.7                 | 0.86            | 29.3            | Flood      |
| 2.000      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 2    | 3  | 7.150                    | 7.150                   | 0.225               | 30.336                | 1.5                 | 0.85            | 59.2            | Flood      |
| 1.001      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 3    | 4  | 7.000                    | 7.000                   | 0.225               | 52.369                | 1.9                 | 2.52            | 76.3            | Flood      |
| 1.002      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 4    | 5  | 7.500                    | 6.583                   | 0.225               | 52.336                | 1.8                 | 2.02            | 73.2            | Surcharged |
| 1.003      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 5    | 6  | 7.350                    | 6.241                   | 0.225               | 52.299                | 1.7                 | 0.95            | 67.3            | Surcharged |
| 1.004      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 6    | 7  | 6.800                    | 5.886                   | 0.225               | 52.339                | 1.7                 | 0.98            | 68.0            | Surcharged |
| 1.005      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 7    | 8  | 6.800                    | 5.662                   | 0.225               | 54.477                | 1.8                 | 1.01            | 71.6            | Surcharged |
| 1.006      | FEH: 100 years: +45 %: 15 mins: Winter | Pipe            | 8    | 9  | 6.400                    | 5.147                   | 0.225               | 60.019                | 2.0                 | 0.93            | 78.2            | Surcharged |
| 3.000      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 11   | 12 | 6.350                    | 6.171                   | 0.225               | 22.823                | 1.1                 | 1.21            | 42.2            | Flood Risk |
| 3.001      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 12   | 13 | 6.100                    | 5.979                   | 0.225               | 23.787                | 0.9                 | 0.95            | 35.0            | Flood Risk |
| 3.002      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 13   | 14 | 6.050                    | 5.927                   | 0.225               | 32.538                | 1.2                 | 1.5             | 48.2            | Flood Risk |
| 3.003      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 14   | 15 | 5.950                    | 5.858                   | 0.300               | 60.932                | 1.4                 | 1.17            | 102.0           | Flood Risk |
| 3.004      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 15   | 16 | 6.150                    | 5.569                   | 0.300               | 64.475                | 1.4                 | 1.3             | 102.2           | Surcharged |
| 3.005      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 16   | 9  | 6.300                    | 5.335                   | 0.300               | 80.277                | 1.9                 | 1.75            | 132.3           | Surcharged |
| 1.007      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 9    | 10 | 6.300                    | 5.037                   | 0.450               | 140.543               | 1.2                 | 0.49            | 192.6           | Surcharged |
| 1.008      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 10   | 17 | 5.600                    | 4.989                   | 0.450               | 140.486               | 1.2                 | 0.97            | 185.8           | Surcharged |
| 1.009      | FEH: 100 years: +45 %: 15 mins: Summer | Pipe            | 17   | 18 | 5.600                    | 4.830                   | 0.450               | 151.745               | 1.3                 | 1.19            | 207.0           | Surcharged |

|                                                                    |  |  |  |                                    |  |                        |  |                                                                                     |  |  |  |
|--------------------------------------------------------------------|--|--|--|------------------------------------|--|------------------------|--|-------------------------------------------------------------------------------------|--|--|--|
| Project:<br>Land west of Manor Farm<br>Surface Water Calculations  |  |  |  | Date:<br>25/07/2024                |  |                        |  |  |  |  |  |
|                                                                    |  |  |  | Designed by:<br>S.Smith            |  | Checked by:<br>S.Smith |  |                                                                                     |  |  |  |
| Report Details:<br>Type: Connections Summary<br>Storm Phase: Phase |  |  |  | Company Address:<br>MJA Consulting |  |                        |  |                                                                                     |  |  |  |

|       |                                               |      |           |           |       |       |       |         |     |      |       |            |
|-------|-----------------------------------------------|------|-----------|-----------|-------|-------|-------|---------|-----|------|-------|------------|
| 1.010 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 18        | 19        | 5.500 | 4.760 | 0.450 | 156.713 | 1.3 | 1.13 | 213.8 | Surchar    |
| 1.011 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 19        | 20        | 5.100 | 4.613 | 0.450 | 154.877 | 1.3 | 1.11 | 206.8 | Surchar    |
| 1.012 | FEH: 100 years:<br>+45 %: 30<br>mins: Summer  | Pipe | 20        | 21        | 5.050 | 4.516 | 0.450 | 192.693 | 1.3 | 1.09 | 209.4 | Surchar    |
| 1.013 | FEH: 100 years:<br>+45 %: 30<br>mins: Summer  | Pipe | 21        | 22        | 5.000 | 4.392 | 0.450 | 188.696 | 1.3 | 1.13 | 208.1 | Surchar    |
| 4.000 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 26        | 27        | 6.900 | 6.735 | 0.225 | 25.131  | 1.0 | 0.88 | 38.7  | Flood Risk |
| 4.001 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 27        | 28        | 6.800 | 6.734 | 0.225 | 32.480  | 1.1 | 0.86 | 44.8  | Flood Risk |
| 4.002 | FEH: 100 years:<br>+45 %: 15<br>mins: Winter  | Pipe | 28        | 29        | 6.700 | 6.555 | 0.225 | 32.531  | 1.2 | 0.92 | 48.5  | Flood Risk |
| 4.003 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 29        | 30        | 6.550 | 6.551 | 0.225 | 45.612  | 1.8 | 1.4  | 73.5  | Flood      |
| 4.004 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 30        | 31        | 6.400 | 6.094 | 0.225 | 68.940  | 2.5 | 1.93 | 100.4 | Surchar    |
| 4.005 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 31        | 32        | 6.500 | 5.671 | 0.225 | 68.920  | 2.4 | 1.85 | 94.4  | Surchar    |
| 4.006 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 32        | 33        | 6.450 | 4.891 | 0.300 | 68.893  | 1.5 | 0.83 | 91.8  | Surchar    |
| 4.007 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 33        | 34        | 6.250 | 4.827 | 0.300 | 75.876  | 1.4 | 0.58 | 101.9 | Surchar    |
| 6.000 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 24        | 25        | 6.150 | 4.540 | 0.300 | 0.000   | 1.4 | 1.88 | 99.9  | Surchar    |
| 5.000 | FEH: 100 years:<br>+45 %: 15<br>mins: Winter  | Pipe | Swale     | 34        | 5.400 | 4.611 | 0.300 | 8.962   | 0.3 | 0.05 | 14.9  | OK         |
| 4.008 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 34        | Swale (1) | 5.350 | 4.655 | 0.300 | 84.010  | 1.6 | 1.25 | 114.8 | Surchar    |
| 4.009 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | Swale (1) | 25        | 5.350 | 4.532 | 0.300 | 80.827  | 1.4 | 1.02 | 100.2 | Surchar    |
| 7.000 | FEH: 100 years:<br>+45 %: 15<br>mins: Winter  | Pipe | Swale (2) | 25        | 5.350 | 4.447 | 0.300 | 0.000   | 0.4 | 0.24 | 25.8  | Surchar    |
| 4.010 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | 25        | Basin     | 5.350 | 4.496 | 0.300 | 119.758 | 1.9 | 2.15 | 131.1 | Surchar    |
| 1.015 | FEH: 100 years:<br>+45 %: 15<br>mins: Summer  | Pipe | Basin     | 23        | 5.250 | 4.269 | 0.450 | 5.136   | 0.4 | 0.09 | 10.2  | Surchar    |
| 1.016 | FEH: 100 years:<br>+45 %: 480<br>mins: Winter | Pipe | 23        | Swale (3) | 5.250 | 4.841 | 0.059 | 158.522 | 0.6 | 0.05 | 3.3   | Surchar    |
| 1.014 | FEH: 100 years:<br>+45 %: 30<br>mins: Summer  | Pipe | 22        | Basin     | 5.250 | 4.361 | 0.450 | 203.574 | 2.1 | 1.27 | 224.6 | Surchar    |




---

## **APPENDIX E**

### **PUBLIC SEWER RECORDS**

# SEWER RECORDS PAGE 1 OF 2

106371



105793

469656

O.S. REF.

**SU7006SW**

Title: Land at Manor Farm Lower Road

Drawn by: mondaln

Scale: 1:2500

Date: 23/06/2015

The positions of pipes shown on this plan are believed to be correct, but Southern Water Services Ltd accept no responsibility in the event of inaccuracy.  
The actual positions should be determined on site.

WARNING: BAC pipes are constructed of Bonded Asbestos Cement  
WARNING: Unknown (UNK) materials may include Bonded Asbestos Cement

Based upon Ordnance Survey Digital Data with the permission of the controller of H.M.S.O. Crown Copyright Reserved  
Licence No. WU 288530.



470601

## SEWER RECORDS PAGE 2 OF 2

| Node  | Cover | Invert | Size  | Material | Shape | Node  | Cover  | Invert | Size | Material | Shape | Node | Cover | Invert | Size | Material | Shape | Node | Cover | Invert | Size | Material | Shape |
|-------|-------|--------|-------|----------|-------|-------|--------|--------|------|----------|-------|------|-------|--------|------|----------|-------|------|-------|--------|------|----------|-------|
| 0201X | 9.3   | 6.73   | 225   | VC       | CIRC  | 81CDX | 11.035 |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 0202X | 8.89  |        | UNK   | UNK      | CIRC  | 81DDX | 10.67  | 9.37   | 100  | VC       | CIRC  | *    |       |        |      |          |       |      |       |        |      |          |       |
| 0251X | 8.8   | 8.29   | 150   | CI       | CIRC  | 81DDY | 10.67  |        | UNK  | UNK      | CIRC  | *    |       |        |      |          |       |      |       |        |      |          |       |
| 0302X | 8.37  | 6.16   | 225   | VC       | CIRC  | 8201X | 10.92  | 10.43  | 100  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 0303X |       |        | UNK   | UNK      | CIRC  | 820DX | 10.62  | 9.36   | 100  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 0305X |       |        | UNK   | UNK      | CIRC  | 821DX | 10.81  | 9.68   | 100  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 0307X |       |        | UNK   | UNK      | CIRC  | 822DX | 10.91  | 10.91  | UNK  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1101X | 6.99  | 3.87   | 300   | VC       | CIRC  | 8302X | 18.89  |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1102X | 6.86  | 3.08   | 525   | CP       | CIRC  | 9101X | 9.19   | 7.13   | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1201X | 8.25  | 6.28   | 225   | VC       | CIRC  | 9102X |        |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1202X | 8.14  |        | UNK   | UNK      | CIRC  | 9150X | 9.06   | 8.45   | 225  | CP       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1203X | 7.28  | 4.05   | 300   | VC       | CIRC  | 9201X | 9.22   | 6.95   | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1204X | 6.84  |        | UNK   | UNK      | CIRC  | 9202X | 9.81   | 8.07   | 150  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 1301X | 6.66  |        | UNK   | UNK      | CIRC  | 9203X | 9.22   | 6.79   | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 2001X | 4.7   | 2.63   | 525   | CP       | CIRC  | 9204X | 11.56  | 8.76   | 150  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 2201X | 4.28  |        | UNK   | UNK      | CIRC  | 9205X |        |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 2302X | 7.06  | 6.54   | 150   | CI       | CIRC  | 920DX |        |        | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 2901X | 3.65  | 2.48   | 525   | CP       | CIRC  | 921DX |        |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 3901X | 3.25  |        | OTHER | CP       | CIRC  | 9251X | 9.37   | 8.86   | 225  | CP       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 4901X | 2.84  |        | UNK   | UNK      | CIRC  | 9252X | 9.57   | 8.86   | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 5801X | 3.01  | 0.11   | OTHER | CP       | CIRC  | 925DX |        |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 6051X | 10.09 | 7.8    | 375   | CP       | CIRC  | 9350X | 12.67  | 11.36  | 225  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 6101X | 18.76 | 7.93   | 300   | CP       | CIRC  | 9351X | 14.01  | 12.08  | 150  | VC       | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 6201X | 20.65 |        | 175   | VC       | CIRC  | 9352X |        |        | UNK  | UNK      | CIRC  |      |       |        |      |          |       |      |       |        |      |          |       |
| 6250X | 20.69 | 19.83  | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 6251X | 20.78 | 19.86  | 225   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 6252X | 19.34 | 18.1   | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7950X | 10.05 |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7001X | 14.16 | 7.84   | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7050X | 12.62 | 9.73   | 375   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7051X | 10.52 | 8.88   | 375   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7101X | 12.76 | 7.55   | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7102X | 12.99 | 7.51   | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7103X | 14.66 | 11.26  | 150   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7104X | 16.7  | 14.14  | 150   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7104Y | 16.7  |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7151X | 16.53 | 15.05  | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7152X | 13.08 | 11.13  | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7153X | 13.23 | 10.63  | 375   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7154X | 13.12 | 11.58  | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 715IX | 11.16 |        | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7202X | 16.59 | 14.87  | 175   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7203X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7251X | 21.57 | 20.75  | 225   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7301X | 22.4  | 21.21  | 175   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7302X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7303X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7303Y |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7304X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7305X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7306X |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 732DX |       |        | 175   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 733DX |       |        | 175   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7350X | 23.11 | 21.89  | 225   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 7351X | 22.19 | 21.35  | 225   | CP       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 8101X | 10.86 |        | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 8102X |       |        | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 810DX |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 811DX |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 812DX |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 813DY |       |        | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 813DX |       |        | UNK   | UNK      | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 814DX |       |        | 225   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 81ADX | 10.32 | 8.85   | 100   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |
| 81BDX | 10.35 |        | 100   | VC       | CIRC  |       |        |        |      |          |       |      |       |        |      |          |       |      |       |        |      |          |       |

| LINE STYLES / COLOURS                                                                                                                                                                                                                                                                                                                                    | MATERIALS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | LEGEND - SEWERS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | SHAPES (S)                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Brown<br>Foul<br>Foul Bypass Sewer<br>Foul Vacuum Main<br>Foul Rising Main<br>Combined<br>Combined Bypass Sewer<br>Combined Rising Main<br>Lateral Drain<br>Building Over Agreement Area<br>Treated Effluent<br>Sludge<br>Sewer Catchment<br>Section 104 Area<br>Surface Water<br>Surface Water Rising Main<br>Private<br>Access Shaft<br>Decommissioned | AK Alkathane<br>BAC Bonded Asbestos Cement<br>BNC Brick (Common)<br>BRE Brick (Engineering)<br>CC Concrete Box Culvert<br>CI Cast Iron<br>CO Concrete (In-Situ)<br>CP Concrete (Pre-Cast)<br>CSB Concrete Segments (bolted)<br>CSU Concrete Segments (unbolted)<br>DI Ductile Iron<br>GRC Glass Reinforced Concrete<br>GRP Glass Reinforced Plastic<br>MAC Masonry in regular Courses<br>MAR Masonry in random Courses<br>PE Polyethylene<br>PF Pitch Fibre<br>PP Polypropylene<br>PVC Polyvinyl Chloride<br>RPM Reinforced Plastic Mesh<br>SI Spun Iron<br>ST Steel<br>VC Vitreous Clay<br>XXX Other<br>ZZZ Unknown | Manhole (BW)<br>Manhole (FAC)<br>Lamp hole (BW)<br>Lamp hole (FAC)<br>Pumping Station (BW)<br>Pumping Station (FAC)<br>Slide entry manhole (BW)<br>Slide entry manhole (FAC)<br>Blind shaft (BW)<br>Blind shaft (FAC)<br>Ejector station (BW)<br>Ejector station (FAC)<br>Watertight door (BW)<br>Watertight door (FAC)<br>Flashing ch. M-e (BW)<br>Flashing ch. M-e (FAC)<br>Flashing ch. No-e (BW)<br>Flashing ch. No-e (FAC)<br>Domestic Chamber<br>Washout (BW)<br>Washout (FAC)<br>Rodding Eye (BW)<br>Rodding Eye (FAC)<br>Gauging point (BW)<br>Gauging point (FAC)<br>Intercept chamber (BW)<br>Intercept chamber (FAC)<br>Storm Tank (BW)<br>Storm Tank (FAC)<br>Valve chamber (BW)<br>Valve chamber (FAC)<br>Label ellipses<br>Dumpty/S24 manhole<br>Outfall<br>Perastock chamber<br>Dampdown<br>Backdrop manhole<br>Other (x)<br>Other<br>Change in sewer (x)<br>Change in sewer<br>Reflex valve<br>Flap valve<br>Cascade<br>Anode<br>Valve<br>Closed Valve<br>Air Valve<br>Hatch box (BW)<br>Hatch box (FAC)<br>Direction arrow<br>Emptying valve<br>Catchpit<br>Scotsway<br>Inlet<br>Blending Pond | Wastewater treatment works<br>Marine treatment works<br>Outfall headworks<br>Vent<br>Vent column<br>Tidal storage tank<br>Blank end<br>Head of Public Sewer<br>Micro Pumping Station<br>Arch<br>Rectangular<br>Semi<br>Square<br>Circular<br>Egg<br>Horseshoe<br>X Other<br>1st digit: hundred metre starting identifier<br>2nd digit: hundred metre ending identifier<br>3rd digit: sewer type identifier<br>4th digit: next sequential node |

Drawn by: mondaln

Title: Land at Manor Farm Lower Road

Date: 23/06/2015

Southern Water

## APPENDIX F

### SUDS COMPATIBILITY MATRIX

| SuDS Type                               | Description                                                                                                                                                                                                                                                                                                       | Suitable for this site                                                              | Comments                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|-----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Green Roofs</b>                      | Green roofs comprise a multi-layered system that covers the roof of a building with vegetation cover over a drainage layer. They are designed to intercept and retain rainfall, reducing the volume of runoff and attenuating                                                                                     |    | Living Roofs would not be technically feasible at this development due to factors such as loadings, steep roof pitch of proposed dwellings, visual impact and high maintenance burden to homeowners.                                                                                                                                                                                                                                         |
| <b>Rainwater Harvesting</b>             | Re-using rainwater for non-potable purposes such as irrigation and toilet flushing.                                                                                                                                                                                                                               |    | Rainwater harvesting cannot be relied upon to guarantee a reduction in the volume of water leaving the site as it relies upon tanks having available capacity.<br>During intense/prolonged periods of rainfall it is likely that the tanks will be full and will overflow into the system.<br>These systems can also be a high maintenance burden for residential home owners.<br>Cost benefit of system is not recovered until 10-15 years. |
| <b>Soakaways</b>                        | Soakaways provide stormwater attenuation, stormwater treatment and groundwater recharge.                                                                                                                                                                                                                          |    | Onsite infiltration via soakaways is not feasible in the superficial and upper chalk geology. However deep borehole soakaways could be used in this instance where infiltration rates are 1x10 <sup>-4</sup> m/s about 15m below ground level.                                                                                                                                                                                               |
| <b>Filter Strip / Trenches / Swales</b> | Filter strips are linear grassed or vegetated strips of land / channels designed to accept runoff as overland sheet flow from impermeable surfaces usually located adjacent road or parking areas and used to treat infiltrated or convey runoff.                                                                 |  | Potentially viable on this site.                                                                                                                                                                                                                                                                                                                                                                                                             |
| <b>Permeable Paving</b>                 | Pervious pavements provide a pavement suitable for pedestrian and vehicular traffic, while allowing rainwater to infiltrate through the surface and into the underlying layers. The water is temporarily stored before infiltration to the ground, reuse, or discharge to a watercourse or other drainage system. |  | Potentially on private drives / parking areas/ roads. This would improve water quality into the ground and subsequent aquifer/river.                                                                                                                                                                                                                                                                                                         |
| <b>Bio Retention</b>                    | Bioretention areas are shallow landscaped depressions which are typically under-drained and rely on engineered soils and enhanced vegetation and filtration to remove pollution and reduce runoff downstream. They are aimed at managing and treating runoff from frequent rainfall events.                       |  | A bio retention pond could be utilised at this development if the receiving waterbody is considered sensitive and additional treatment is required. Although likely not required.                                                                                                                                                                                                                                                            |
| <b>Ponds / Basins</b>                   | Ponds can be used to store and treat water. 'Wet' ponds have a constant body of water and run-off is additional, while 'dry' ponds are empty during periods without rainfall. Ponds can be designed to allow infiltration into the ground or to store water for a period of time before discharge.                |  | A pond / basin can be utilised at this development to provide attenuation and improvements in water quality. There is sufficient open space.                                                                                                                                                                                                                                                                                                 |
| <b>Underground Storage</b>              | Underground large diameter Concrete pipes or Geocellular Tanks to reduce and attenuate peak flows                                                                                                                                                                                                                 |  | Underground storage tanks can be utilised at this development if required.                                                                                                                                                                                                                                                                                                                                                                   |



## **Appendix G**

### **SUDS MANAGEMENT AND MAINTENANCE PLAN**

PROPOSED RESIDENTIAL DEVELOPMENT  
LAND SOUTH OF, LOWER ROAD, AND WEST OF OLD MANOR FARM,  
HAVANT,  
HAMPSHIRE

## SUDS MANAGEMENT & MAINTENANCE PLAN

BARGATE HOMES LTD

REVISION B  
JULY 2024

REF: SS/21/0433/6430



## DOCUMENT CONTROL RECORD

### Document Issue:

| Rev | Date     | Issue Status                 | Prepared by | Checked by |
|-----|----------|------------------------------|-------------|------------|
| -   | 24.09.21 | First Issue                  | S. Smith    | C. Pendle  |
| A   | 22.07.24 | Updated to current design    | S. Smith    | C. Pendle  |
| B   | 30.07.24 | Updated to client's comments | S. Smith    | C. Pendle  |

### References:

The SUDS manual – CIRIA C753 (2015) ISBN 9780-86017-760-9

National Planning Policy Framework (NPPF) – Communities and Local Government  
Technical Guidance - Flood Risk & Coastal Change (March 2012)



## 1 Introduction

- 1.1 This document sets out the principles for the long term management and maintenance of the proposed surface water Sustainable Drainage Systems (SuDS) installed at the residential development at land adjacent to Lower Road, Bedhampton.
- 1.2 The purpose of this document is to set out the basis of the development SuDS Maintenance Plan and to ensure that the adopting management company is entrusted with a robust inspection and maintenance programme, ensuring the optimum operation of the surface water drainage network is continually maintained for the lifetime of the development and to prevent the increased risk of flooding both on and off site in accordance with the National Planning Policy Framework (NPPF).
- 1.3 The activities listed in this document are generic to the relative SuDS types and represent the minimum maintenance and inspection requirements, however additional tasks or varied maintenance frequency may be instructed by the maintenance company as required. Specific maintenance needs of the SuDS elements should be monitored and maintenance schedules adjusted to suit requirements.
- 1.4 The installed SuDS system at this development are the initial responsibility of Bargate Homes. Following installation and after an initial period (TBC) of operation, all SuDS are to be transferred to an appointed Management Company. An agreement shall be set up by Bargate Homes, who shall confirm in writing to the Principle Planning Officer at Hampshire County Council when the maintenance agreement is completed and is operative.
- 1.5 The Management Company will then be responsible for maintaining the surface water system including all SuDS in perpetuity. All property owners should be advised that an annual management fee will need to be paid to the management company for this service.
- 1.6 All those responsible for maintenance should follow relevant Health and Safety legislation (Health and Safety at Work Regulations, 1999) for all activities listed within this report including lone working, if relevant) and risk assessments should always be undertaken.
- 1.7 Any contractor employed by the Management Company shall carry out periodic maintenance of all such SuDS in accordance with the schedules listed in this report. Inspection checks shall be carried out by a qualified and competent person, at the minimum intervals listed within the schedules and the appropriate work carried out.
- 1.8 This report is to read in conjunction with MJA drawing '001 Drainage Strategy' for the location of all SuDS elements present within the development. Reference should also be made to the detailed landscape proposals for the proposed treatment / maintenance regime for all landscape features. The operations contained within this plan shall (where feasible) be in conjunction with routine grounds maintenance operations to the surrounding landscape.

## 2 SuDS Layout & Design

- 2.1 The storm water drainage strategy for the proposed development is to utilise a range of SuDS features to attenuate all surface water runoff from impermeable areas, with a restricted discharge via a flow control into ditch via overland flow.
- 2.2 The proposed storm water system consists of the following drainage and SuDS components:
- Attenuation Basin
  - Storm water pipe work and road gullies
  - Permeable block paving
  - Flow control chambers
  - Overland Overflow Outfall Pond
- 2.3 There are three categories of maintenance activities referred to in this report:
- **Regular maintenance** (including inspections and monitoring).  
Consists of basic tasks done on a frequent and predictable schedule, including vegetation management, litter and debris removal, and inspections.
  - **Occasional maintenance**  
Comprises tasks that are likely to be required periodically, but on a much less frequent and predictable basis than the routine tasks (sediment removal is an example).
  - **Remedial maintenance**  
Comprises intermittent tasks that may be required to rectify faults associated with the system, although the likelihood of faults can be minimised by good design.  
Where remedial work is found to be necessary, it is likely to be due to site-specific characteristics or unforeseen events, and as such timings are difficult to predict.
- 2.4 It is also important that measures are taken to protect and ensure continued operation of drainage features during the construction phase. All road gullies will be blocked until the site is complete. Mesh will be placed over the outfalls and swales to prevent construction silts clogging up the drainage system and basins.

### **3 SUDS Management & Maintenance**

#### **3.1 Storm water pipe work and road gullies**

- 3.2 The key maintenance requirement for the upstream surface water drainage system includes the removal of sediments and debris from the system as required.
- 3.3 All storm water pipe work should be visually inspected a minimum of monthly for the first three months after installation and then a minimum of once year. As road gullies are the first on the treatment train and susceptible to higher silt loadings, these will need to be inspected a minimum of monthly for the first three months after installation and then a minimum of every four months.
- 3.4 During this inspection identify any gully pots or pipes that require remedial maintenance such removal of sediment, debris, leaves and litter as required. This involves the removal all protective covers and grids and the cleaning out of channels or gully pots by hand or with suitable jetting equipment.
- 3.5 During the inspections the general operation and structural integrity of all components should be recorded and repaired as required.

#### **3.6 Flow Control Chamber**

- 3.7 The key maintenance requirement for the flow control chamber will be the inspection of the units for blockages of the vortex flow control unit and silt removal from sump of chamber.
- 3.8 The hydraulic vortex flow control unit has no moving parts and is self-activating, requiring minimal maintenance. After initial installation, it is recommended that the unit be inspected monthly for three months.
- 3.9 Thereafter the manhole chamber and control device should be inspected at least every six months to verify the condition and operation of the unit and check for blockages within the inlet of the chamber and of the flow control device. During these inspections, accumulated silts should be removed and the sump cleaned out using a conventional sump vacuum cleaner. Flow Controls are fitted with a pivoting by-pass door, which allows the manhole chamber to be drained down should blockages occur.

#### **3.10 Overland Overflow Outfall Pond and Swales**

- 3.11 The outfall pond and swales should be visually inspected a minimum of monthly for the first three months after installation and then a minimum of twice a year. Accumulated sediments, debris and any overgrown vegetative material should be removed. Any reeds should be maintained in line with the landscape management plan.

### **3.12 Attenuation Basins**

Key Maintenance Requirements:

- Litter/trash removal
- Inlet/outlet headwall inspection and cleaning
- Vegetation management
- Sediment monitoring and removal when required

- 3.13 Regular inspection and maintenance is important for the effective operation of the attenuation basin. The basin will be subject to a routine monitoring and maintenance schedule as part of the general site management. This will be carried out at intervals detailed below, and shall comprise of the following operations:  
Collection and removal of all litter/large debris from the attenuation pond, inlets, outflows, and water margins once a month.  
Monthly inspection of the attenuation ponds to check the following, and repair as necessary:
1. Any failure in the operation of the inlet and outlet headwalls unless adopted by others in which case they will be notified of any observed defect.
  2. Any damage or erosion to the perimeter edges and slopes of the attenuation ponds.
- 3.14 Please see landscape management plan for further details of planting and management.
- 3.15 An annual check carried out by a suitably qualified person, to assess the condition and operation of the attenuation basin inlet and outflow, and the accumulation of silt/sediment.
- 3.16 A record of maintenance visits and remedial operations shall be maintained.
- 3.17 **Desilting of Attenuation Basins**  
In addition to regular routine items, SuDS maintenance will be carried out which may include de-silting the attenuation ponds, usually on a 10-15 year cycle depending on the on-going silt level checking. This can be an intrusive operation when carried out within housing areas and prior to any planned desilting or dredging, consultation will be undertaken with both the LLFA and the Environment Agency.
- 3.18 Before any desilting operations are carried out, residents and members of the public in the general area will be informed and those in the immediate vicinity will be notified in writing well in advance of commencement of works.
- 3.19 The desilting work will be carried out under the supervision of consulting engineers and to a pre-agreed method statement. Such a method statement should be submitted in writing to the local authority and agreed in advance of the commencement of the works.
- 3.20 Prior to desilting works commencing, a suitably qualified ecologist shall be appointed to undertake an assessment of the ecological interest within the pond and its margins. In the event that the attenuation ponds develop particular ecological interest, then careful consideration will be given to the timing of this operation.

### **3.21 Permeable Block Paving**

- 3.22 Note: Loose materials such as sand, cement soil or other loose substances should not be stored directly on top of the permeable blocks without the use of an impenetrable sheet.
- 3.23 To ensure the continual optimal performance of the permeable paving, it is recommended that the following maintenance should be carried out. The following guidelines are offered as an initial regime, but maybe either increased or decreased by the management company depending on the local environment and any external contributing factors.
- 3.24 Permeable pavements should be visually inspected a minimum of monthly for the first three months after installation and then a minimum of three times a year, preferably during and after heavy rainfall to check effective operation and identify areas of ponding. These inspections should occur close to the end of winter (March), mid-summer (July) and after the autumn (November).
- 3.25 During this inspection identify any areas that require remedial maintenance such as topping up of jointing grit or removal of vegetation, weeds, silts and sediments that may be clogging the joints between the blocks. Small areas such as driveways can be swept with a hand bristle broom, for larger areas such as parking courts a lorry mounted rotary brush and vacuum sweeper device can be used. Weeds can be removed from the surface through the controlled application of proprietary non-persistent contact herbicides. Those containing Glyphosate are the most suitable.
- 3.26 Care should be taken to ensure that only the detritus is removed from the joints and avoid removal of the jointing material. If required, joints should be replenished with aggregate material to lip of paver using specific 6-2mm single size grit using a stiff brush to sweep the material in ensuring joints are filled. Do not replace the jointing grit with sand as this will stop the permeable system from working.
- 3.27 For winter maintenance, the controlled use of de-icing may be used without causing significant detrimental effects towards the permeable pavements performance. When used carefully, the use of these chlorides will not result in an increase in the chloride levels in the local ground.
- 3.28 Contamination of the permeable block paving from routine landscape maintenance such as grass clippings from mowing, hedge trimming, mulching plant beds etc. should be prevented. If contamination occurs the debris should be immediately swept, collected and removed by the homeowner or landscape operative.
- 3.29 Depending on the amount of usage and the environment the permeable pavement has received and been exposed to, the sub base laying course material including geotextile membranes/ grids may require either replacement or cleaning after a 25 to 30 year period. This would be evident if the infiltration rate of the paving became prolonged, allowing ponding to develop. Should this occur, the uplifting and cleaning or replacing of the laying course maybe considered. The laying course material, jointing and blocks can be reused once cleaned, minimising costs.

- 3.30 Replacement sub-base material to be used should be a clean 4/20mm coarse graded aggregate to BS EN13242:2002. Jointing material between the blocks should be 6-2mm single size grit to the joints. Refer to MJA Consulting construction detail drawings for type of geotextile membrane/ geogrids to be used.
- 3.31 Materials removed from the voids or the layers below the surface may contain heavy metals and hydrocarbons and may need to be disposed of as controlled waste. Sediment testing should be carried out before disposal to confirm its classification and appropriate disposal methods.

*Permeable Paving Operation and Maintenance Requirements*

| Maintenance schedule   | Required action                                                                                                                                   | Frequency                                                                                                                                                                |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Regular maintenance    | Brushing and vacuuming.                                                                                                                           | Three times/year at end of winter, mid-summer, after autumn leaf fall, or as required based on site-specific observations of clogging or manufacturers' recommendations. |
| Occasional maintenance | Stabilise and mow contributing and adjacent areas.                                                                                                | As required.                                                                                                                                                             |
|                        | Removal of weed.                                                                                                                                  | As required.                                                                                                                                                             |
| Remedial actions       | Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50 mm of the level of the paving.         | As required.                                                                                                                                                             |
|                        | Remedial work to any depressions, rutting and cracked or broken blocks considered detrimental to the structural performance or a hazard to users. | As required.                                                                                                                                                             |
|                        | Rehabilitation of surface and upper sub-structure.                                                                                                | As required (if infiltration performance is reduced as a result of significant clogging).                                                                                |
| Monitoring             | Initial inspection.                                                                                                                               | Monthly for 3 months after installation                                                                                                                                  |
|                        | Inspect for evidence of poor operation and/or weed growth. If required take remedial action.                                                      | 3-monthly, 48 h after large storms.                                                                                                                                      |
|                        | Inspect silt accumulation rates and establish appropriate brushing frequencies.                                                                   | Annually.                                                                                                                                                                |
|                        | Monitor inspection chambers.                                                                                                                      | Annually.                                                                                                                                                                |

## **4 Contact Information**

For further information on the management and maintenance of SuDS on the development please contact:

MJA Consulting  
Ipsum Court  
24 The Quadrant  
Abingdon Science Park  
Oxfordshire  
OX14 3YS

Tel: 01235 555173  
Email: [mail@mjaconsulting.co.uk](mailto:mail@mjaconsulting.co.uk)



**MJA CONSULTING**  
Civil & Structural Engineers

Monarch House • Abingdon Science Park  
Barton Lane • Abingdon • Oxon • OX14 3NB  
Tel: (01235) 555173 • [www.mjaconsulting.co.uk](http://www.mjaconsulting.co.uk)