Skate Park

West Brook

Recreation Ground

FLOOD STORAGE AREA

Pedestrian access gate indicative location

Pedestrian and maintenance access gate indicative location

Sub-station (Indicative)

Pump station

Plot 1 | Plot 2 | Plot 3 | Plot 4 | Plot 5 | Plot 6 | Plot 7 | Plot 8 | Plot 9 | Plot 10 | Plot 11 | Plot 12 | Plot 13 | Plot 14 | Plot 15 | Plot 16 | Plot 17 | Plot 18 | Plot 19 | Plot 20 | Plot 21 | Plot 22 | Plot 23 | Plot 24 | Plot 25 | Plot 26 | Plot 27 | Plot 28 | Plot 29 | Plot 30 | Plot 31 | Plot 32 | Plot 33 | Plot 34 | Plot 35 | Plot 36 | Plot 37 | Plot 38 | Plot 39 | Plot 40 | Plot 41 | Plot 42 | Plot 43 | Plot 44

Ornamental mix 1
6 No. CsPiF 20%
6 No. HsB 20%
3 No. MsA 10%
5 No. VbD 15%
8 No. WfFP 20%

Ornamental mix 2
6 No. AxGC 20%
5 No. BsAN 15%
4 No. CAP 15%
6 No. Cp 20%
4 No. DkMR 15%
5 No. SjAW 15%

Ornamental mix 3
5 No. CsP 20%
4 No. EfEnG 15%
8 No. Hr 20%
6 No. MsG 15%
6 No. PsBS 15%
6 No. PtOL 15%

Native scrub mix
41 No. CaS 10%
164 No. CsV 40%
103 No. CmoS 25%
21 No. Lp 5%
21 No. RcS 5%
21 No. ScS 5%
41 No. VoS 10%

Native hedgerow mix
18 No. AcS 10%
18 No. AgF 10%
18 No. CmoS 10%
87 No. CsmoS 50%
18 No. PspS 10%
18 No. RcaS 10%

Ornamental mix 4
9 No. AlS 5%
12 No. Cp 20%
9 No. CsPiF 15%
12 No. Hr 20%
9 No. MsML 15%
9 No. PsBS 15%

Ornamental mix 5
10 No. CsP 20%
10 No. HsB 20%
8 No. MsA 10%
8 No. VbD 15%
14 No. WfFP 20%

Ornamental mix 6
10 No. AxGC 20%
11 No. BsAN 15%
8 No. CAP 15%
15 No. Cp 20%
8 No. DkMR 15%
11 No. SjAW 15%

Ornamental mix 7
7 No. CsP 20%
5 No. EfEnG 15%
5 No. Hr 20%
5 No. MsG 15%
5 No. PsBS 15%
5 No. PtOL 15%

Ornamental mix 8
16 No. AxGC 20%
12 No. BsAN 15%
14 No. Cp 20%
9 No. DkMR 15%
12 No. SjAW 15%

Ornamental mix 9
17 No. AxGC 20%
13 No. BsAN 15%
10 No. CAP 15%
17 No. Cp 20%
10 No. DkMR 15%
13 No. SjAW 15%

Native scrub mix
30 No. CaS 10%
118 No. CsV 40%
74 No. CmoS 25%
15 No. Lp 5%
15 No. RcS 5%
15 No. ScS 5%
30 No. VoS 10%

Native scrub mix
23 No. CaS 10%
90 No. CsV 40%
57 No. CmoS 25%
12 No. Lp 5%
12 No. RcS 5%
12 No. ScS 5%
23 No. VoS 10%

LEGEND

- Site boundary
- Existing tree to be retained and protected. Refer to arboricultural information for further detail
- Existing vegetation and/or hedgerow to be retained and protected. Refer to arboricultural information for further detail

Proposed soft landscaping

- Tree planting, refer to detail refer to detail GLS_090_151_1700
- Ornamental hedge - Double staggered 1.2m high in front gardens and 1.8m high elsewhere
- Double staggered mixed native hedgerow To be planted in groups of 7-9no. of each species
- Ornamental shrub planting
- Native scrub planting mix To be planted in groups of 7-9no. of each species
- Good quality hardwearing lawn
- Species rich neutral grassland EMS Meadow Mix for Loam soils from Emorsgate or similar seeded at 4g/m2
- Wetland meadow EMB Meadow Mixture for Wetlands from Emorsgate or similar seeded at 4g/m2

NOTES:

To be read in conjunction with:

- Landscape general arrangement plan GLS_090_151_1300
- Detailed hard landscape plans GLS_090_151_1600
- Landscape specification GLS_090_151_1801
- Landscape management plan GLS_090_151_1802

Plant schedule

Trees

Number	Abbreviation	Species	Height	Girth	Specification
1	AcC	Acer campestre 'Elsrijk'	400-450cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
2	AgRH	Amelanchier x grandiflora 'Robin Hill'	400-450cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
6	Bn	Betula nigra	400-450cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
5	Bpe	Betula pendula	350-400cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
4	Cbe	Carpinus betulus	350-400cm	12-14cm	Heavy Standard 'Clear Stem min. 200 RB
4	CmF	Crataegus monogyna	350-400cm	12-14cm	Heavy Standard 'Clear Stem min. 200 RB
4	JMP	Prunus 'Pandora'	400-450cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
4	Ppa	Prunus padus	350-400cm	12-14cm	Heavy Standard 'Clear Stem min. 200 RB
4	SAs	Sorbus aria 'Lutescens'	400-450cm	8-10cm	Extra Heavy Standard 'Clear Stem min. 200 RB
5	Sau	Sorbus aucuparia	350-400cm	12-14cm	Heavy Standard 'Clear Stem min. 200 RB
6	Tex	Tilia x euchlora	350-400cm	12-14cm	Heavy Standard 'Clear Stem min. 200 RB

Total 55

Mixed native hedgerow planting

Number of Plants	Abbreviation	Species	Specification	Height	Density	
86		Ac	Acer campestre	Transplant, Bushy, BR	60-80cm	0.4Cnr Double Staggered at 0.4m offset
88		AgF	Alnus glutinosa	Transplant, Bushy, BR	60-80cm	0.4Cnr Double Staggered at 0.4m offset
86		Cor	Corylus avellana	Bushy, BR	60-80cm	0.4Cnr Double Staggered at 0.4m offset
87		Cmo	Crataegus monogyna	Transplant, Bushy, BR	60-80cm	0.4Cnr Double Staggered at 0.4m offset
88		Psp	Prunus spinosa	Bushy, BR	60-80cm	0.4Cnr Double Staggered at 0.4m offset
91		Rca	Rosa canina	Bushy, BR	140-60cm	0.4Cnr Double Staggered at 0.4m offset

Total 177

Single species hedge planting

Number of Plants	Abbreviation	Species	Specification	Height	Pot Size	Density
459	GiS	Griselinia littoralis	Bushy -C	60-80cm	3L	0.5Cnr Double Staggered at 0.3m offset

Total 459

Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
64	BSp	Brachyglottis 'Sunshine'	Bushy -C	40-60cm	3L	3/m²
66	CBM	Ceanothus 'Blue Mound'	Bushy -C	40-60cm	3L	3/m²
146	CpAF	Cistus purpureus 'Alan Fradd'	Bushy -C	30-40cm	3L	4/m²
131	EfEnG	Euonymus fortunei 'Emerald 'n' Gold'	Bushy -C	20-30cm	3L	4/m²
100	FMP	Fuchsia 'Mrs Popple'	Bushy -C	40-60cm	3L	3/m²
100	HMW	Hebe 'Mrs Winder'	Bushy -C	30-40cm	3L	3/m²
113	HP	Hebe pinguifolia 'Pagei'	Bushy -C	30-40cm	3L	4/m²
111	LaH	Lavandula angustifolia 'Hidcote'	Bushy -C	30-40cm	3L	4/m²
77	PhGC	Pachysandra terminalis 'Green Carpet'	Bushy -C	15-30cm	2L	5/m²
69	PtTT	Pittosporum tenuifolium 'Tom Thumb'	Bushy -C	30-40cm	3L	4/m²
115	PtOL	Prunus lusitanica 'Otto Luyken'	Bushy -C	30-40cm	3L	3/m²
74	ShdPS	Sarcococca hookeriana dig. 'Purple Stem	Bushy -C	30-40cm	3L	4/m²
131	SjKW	Skimmia japonica 'Kew White'	Bushy -C	30-40cm	3L	4/m²

Total 1167

Herbaceous

Number	Abbreviation	Species	Specification	Pot Size	Density
99	BeP	Bergenia cordifolia 'Purpurea'	PC - Full Pot	1L	4/m²

Total 99

Grasses

Number	Abbreviation	Species	Specification	Pot Size	Density
128	CmS	Carex morrowii 'Silver Scepter'	PC - Full Pot	1L	4/m²

Total 128

Ornamental mix 1

CsPiF	Cornus sanguinea 'Midwinter Fire'	Bushy -C	40-60cm	3L	1/m²
HsB	Hydrangea serrata 'Bluebird'	Bushy -C	40-60cm	3L	1/m²
MsA	Malvaria aquifolium 'Apollo'	Bushy -C	30-50cm	3L	1/m²
VbD	Viburnum bodnantense 'Dawn'	Bushy -C	40-60cm	3L	1/m²
V d	Viburnum davidii	Bushy -C	40-60cm	3L	1/m²
WfFP	Weigela florida 'Foliis Purpureis'	Bushy -C	40-60cm	3L	4/m²

Ornamental mix 2

AxGC	Abelia grandiflora 'Compacta'	Bushy -C	30-40cm	3L	4/m²
BsAN	Berberis thunbergii 'Atropurpurea Nana	Bushy -C	30-40cm	3L	4/m²
CAP	Choisya 'Aztec Pearl'	Bushy -C	40-60cm	3L	3/m²
Cp	Cistus purpureus	Bushy -C	30-40cm	3L	4/m²
DkMR	Deutzia hybrida 'Mont Rose'	Bushy -C	30-40cm	3L	3/m²
SjAW	Spiraea japonica 'Anthony Waterer'	Bushy -C	30-40cm	3L	4/m²

Ornamental mix 3

AS	Anemanthele lessoniana	Full Pot		1L	8/m²
Cp	Cistus purpureus	Bushy -C	30-40cm	3L	4/m²
CsPiF	Cornus sanguinea 'Midwinter Fire'	Bushy -C	30-40cm	3L	4/m²
Hr	Hebe rakaiensis	Bushy -C	30-40cm	3L	4/m²
MsML	Malvaria sinensis 'Morning Light'	Full Pot		1L	8/m²
PsBS	Perovskia 'Blue Spire'	Bushy -C	30-40cm	3L	4/m²

FOR PLANNING

Scale @ A0

0 1 2 3 4 5 6 7 8 9 10m

Scale 1:200

NORTH

Rev	Date	Drawn	Checked
A	03.12.24	LM	JM

Updated in line with layout changes and comments

B	04.12.24	AP	

Bollard position shown. Acoustic fence line colour amended to align with General Arrangement Plan

Date: 11.06.24

Drawn by: LM | Checked by: AE

Drg No: GLS_090_151_1500 | Rev: B

Project: Land West of Coldharbour Farm Road Emsworth

Title: Landscape Planting Plan

Client: DOSWELL PROJECTS

Green Landscape Studio Limited – The Lakeside Centre, Lakeside Country Park, Wilde Lane, Botley, Hampshire – Telephone 01329 450039 – www.gls-studio.co.uk

This drawing and the works depicted are the copyright of Green Landscape Studio Ltd. and may not be reproduced or adapted except as to fair permission. No liability will be accepted for amendments made by other persons.