NOTES

1. DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS ONLY, IF IN DOUBT ASK.
2. ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS AND ARCHITECTS DRAWINGS AND SPECIFICATIONS.

0M 5M 10M

FOUL SEWER CURRENTLY 100MM⌀ LAID AT 1 IN 24 TO DEMARCATION CHAMBER AND 1 IN 80 TO FOUL SEWER IN CARRIAGEWAY IS NOT ADEQUATE FOR 78 BED CARE HOME PLUS 5NO DWELLINGS (PLOTS 1 TO 5). SEWER IS TO BE REPLACED WITH 150mm⌀ PIPE. LATERAL CONNECTION TO BE VITRIFIED CLAY.

IT IS CRITICAL THAT TIE IN INVERT LEVELS ARE CHECKED AND REPORTED BACK TO THE ENGINEER PRIOR TO LAYING ANY NEW DRAINAGE TO ALLOW ADJUSTMENTS TO BE MADE IF NECESSARY

CONNECT LAND DRAIN INTO PIPE BEDDING

T1	TENDER ISSUE	RN
31.05.24	-	-
REVISION		DRAWN
DATE		CHECKED

Client:
ANAVO DEVELOPMENTS LIMITED

Project Title:
HAVANT :
HAVANT CARE HOME
BARTONS ROAD, HAVANT

Drawing Title:
PROPOSED DRAINAGE LAYOUT
SHEET 3 OF 4

Drawn By: RN	Scales: 1:100@A1
Date: APRIL 2024	Drawing Number: 11063-502
Checked By: ANR	Rev: T1
Date: APRIL 2024	

Drawing Status: TENDER

NJP Consulting Engineers Limited
20 St Andrews Crescent
Cardiff CF10 3DD

Tel: 029 2072 9500
Email: info@njpuk.com
Web: www.njpuk.com