



Project	
PLOT 4A, Unit 5	
D u n s b u r y P a r k	

Specification Title	Discipline	Document	Clause/ No	Ref		Rev
Tree Schedule	L	SPEC		Q31		D
	Document Status Planning					

Originating Manager Responsible		
QA System – Checks		Date
Written by	PC	27-02-2020
Checked		
Authorised		

Revisions

[illegible]

PROJECT: Dunsbury Park, Plot 4A

JOB NO. LP2123

Species	Girth and Height (cm)	Times Transplanted	Clear stem (CS) or Feathered (F)	Classification	Notes	No.	Rate
Betula Pendula	20-25	X4	CS	WRB	2.1m clear stem, full round head	28	
Acer campestre	20-25	X4	CS	WRB	2.1m clear stem, full round head	11	
Carpinus betulus 'Streetwise'	20-25	X4	CS	WRB	2.1m clear stem, full round head	3	
Quercus robur	20-25	X4	CS	WRB	2.1m clear stem, full round head	5	

ABBREVIATIONS:

T = Transplant, W = Whip, F = Feathered, HS = Half Standard, S = Standard, SS = Select Standard, HS = Heavy Standard, EHS = Extra Heavy Standard, SM = Semi Mature, MS = Multi-Stemmed, O = Open Ground, RW = Root Wrapped, WRB = Wire Rootball