

CLIENT NAME	CONTACT NUMBER	QUOTATION DATE	JOB NUMBER
Mr Walsh	07810008421 stephenwalsh9@gmail.com	5/10/20	J20249
SITE ADDRESS		INSPECTED BY	Matt Godwin
105 Havant Rd Emsworth PO10 7LF		SITE PLAN ATTACHED	No
		COMMENCEMENT DATE	TBA
JOB DESCRIPTION			
TREE NUMBER (price ex. VAT @20%)	SPECIES/ location	WORK REQUIRED	
T1	Lime within rear garden western boundary. Close proximity to dwelling	crown lift to crown break by the removal of 75mm branch work only (epicormic growth) Create a maximum of 3m clearance from dwelling by the removal of 1 x Eastern lateral branch of approximately 100mm in diameter and multiple 50mm branches.	
T2	Lime Eastern aspect of dwelling	Create a 3m clearance from dwelling by shortening laterals back to previous reduction points.	
G1	Griselinia Hedge running parallel to Road, mixed vegetation parallel to decking and 1 x Apple within court yard garden adjacent office.	Trim hedge to maximum capacity whilst retaining greenery Trim lateral growth to clear decking path. Reduce Apple by up to 2m in height and rebalance crown according.	
T3	Chestnut within front garden adjacent to road.	Large cavity present On Eastern aspect of main stem, showing good signs of occlusion. The tree is subject to a lapsed pollard, with the possibility of week unions. Frequency of use is very high. Crown vitality good shown by leaf and twig density. Crown reduce in height by a maximum of 3m from tips and lateral branch work by up to 2m from tips Crown lift over road to 6m from ground level	
T4	Chestnut adjacent T3.	Crown vitality poor shown on western aspect due to historic poor pruning works by previous occupier along with decay on western buttress along with signs of bleeding Canker.	

		Rebalance crown by reducing in height by a maximum of 1m from tips reduce Northern and southern lateral branch work by up to 3m from branch tips, crown lift over road to 6m from ground level.
		Re survey within 18months from date of quotation