


LANDSCAPE SPECIFICATION

GENERAL
All work shall be carried out in accordance with BS 4428 Code of Practice for General Landscape Operations

TOPSOIL
Topsoil removed from the construction area will be stored on site for re-use in the planting beds and will be stored in accordance with BS3882
Topsoil shall be free of pernicious weeds and roots, rubbish and debris, building and other foreign matter, which shall all be removed off site, and shall not be contaminated by chemicals.

PLANTING
Plants to be to BS3936 Part 1 to the sizes and mixes specified All plants shall be British grown and from approved sources.
Tree pits to be 1m square and 600mm deep with 3 no. 50mm dia. stakes per plant. Use Abraform Yellow Stem reinforcement
50g tablet per plant to be incorporated at the time of planting. All plant handling shall comply with the Code of Practice for plant handling 'The National Plant Specification ' produced by the HTA, Sep 1997.
Planting shall be carried out between November and March.
All shrub planting areas shall have a minimum of 400mm depth of topsoil. Prior to planting the soil shall be broken down to a fine tilth and any stones in excess of 50mm removed from the surface. Top of topsoil after cultivations shall be 50mm below DPC and 50mm below timber edge-boards.
Climbing plants shall be set 300mm from base of wall.
Planted areas other than central courtyard bed shall be covered by 50m medium grade, well-rotted bark mulch, bringing levels to those indicated on the Landscape general arrangement drawing.

MAINTENANCE
All maintenance to be carried out for a Maintenance Period of 1 year after completion of planting.
Shrub beds shall be kept free of weeds. Chemical herbicide is to be used on docks, and other pernicious weeds.
In accordance with manufacturers directions. Weeds between herbaceous plants are to be removed by hand. Levels of bark mulch are to be maintained at minimum depth of 50mm throughout the Maintenance Period.
Any dead plants shall be replaced in the next planting season within the Maintenance Period, to ensure establishment.
Pruning of shrubs shall be carried out as required to promote a healthy growth. At the end of the growing season the shrubs are to be checked and all dead wood, broken or damaged branches are to be cut out.
Pruning of flowering shrubs for bushy growth shall conform to the following timetable.
a. Shrubs that flower in winter shall be pruned in Spring.
b. Shrubs that flower in march to July shall be pruned immediately after flowering.
c. Shrubs that flower from July to September shall be cut back to old wood in January/February.
Any shrubs, climbers or other plants found to be dead, defective or missing at the end of the Maintenance Period shall be replaced by the Contractor with plants equal to the original at his own cost

Planting Bed A
(raised - 675mm)

Planting Bed B

Planting Bed C

Planting Bed D
(raised - 675mm)

Planting Schedule

Shrubs					Number of Plants				
Abbreviation	Species	Height	Diameter	Pot Size	Density	Bed A	Bed B	Bed C	Bed D
Chot. tern	Choisya ternata	30-60cm		3L	4/m²	2 No.	3 No.	5 No.	3 No.
Skim. 'Rubella'	Skimmia japonica 'Rubella'	30-60cm		3L	4/m²	2 No.	2 No.	8 No.	0 No.
Hebe 'N.B.'	Hebe 'Nicola's Blush'	40-60cm		5-7.5L	4/m²	1 No.	3 No.	8 No.	2 No.
Lava. angu 'Hidcote'	Lavandula angustifolia 'Hidcote'	30-60cm		5-7.5L	0.33Ctr	5 No.	6 No.	4 No.	3 No.
Vinc. mino 'GJ'	Vinca minor 'Gertrude Jekyll'			3L	0.4Ctr	7 No.	8 No.	10 No.	4 No.
				Totals		17 No.	20 No.	33 No.	12 No.

Trees				
Species	Girth	Height	Specification	Number of Plants
Prunus Serrulata	14-16cm	4.0-4.5m	Rootball	92 No.

Bulbs	130 No.	130 No.	130 No.	130 No.

0 1M 2M 10M
1:200@A1 2M

SCALE 1/200
DATE August 20
CONTRACTOR MUST CHECK ALL DIMENSIONS ON SITE BEFORE DRAWING ANY TO BE SCALED FROM. DISCREPANCIES MUST BE REPORTED TO THE ARCHITECT BEFORE PROCEEDING
© COPYRIGHT
AUTHOR PG

TITLE Residential Developments
Land to the Rear of 11, East Street
DETAIL Comprehensive Landscaping Plan
DRAWING No 20/04/LS01

PETER GALLOWAY PARTNERSHIP
pgp ARCHITECTS
HAVANT
TEL. 02392 483153 MOB. 07808 483362
E-MAIL: peter@pgparchitects.co.uk