

This drawing is the property of AKSWard Limited. The drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the written consent of AKSWard Limited.
Do NOT scale from this drawing. AKSWard takes no responsibility for errors during photographic reproduction or printing. Any discrepancy's are to be reported to the engineer immediately.


GENERAL NOTES

- All setting out to be in accordance with the Architects drawings. Any discrepancies between the Engineers and the Architects drawings to be referred to the Architect before proceeding. Dimensions must not be scaled.
- All materials to Highways Agency "Specification for highways works."
- Contractor to confirm CBR at formation level.
- Soft Spots in subgrade:
Excavate to remove soft or degraded material, then backfill with specified granular sub-base material and compact
- All Paving blocks / slabs to be laid in accordance with current Interpave Guidance documents
- All in-situ concrete works to be carried out in accordance with The Concrete Society Technical Report No 66. External In-situ Concrete Paving.
- Concrete joint sealant to comply with Highways Agency Manual of contract documents for highway works MCHW1, clause 1017.




IDENTIFIES RISKS DURING THE CONSTRUCTION PROCESS ON THE DRAWINGS:

NOTE: The list below and notes on the drawing identify risks which are deemed to be unusual, abnormal, residual or unexpected to a competent contractor carrying out the works. These notes relate to risks which we have been unable to design out.




ASPHALT ACCESS ROAD		
Assumed CBR >15% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	30mm	AC10 close surf PD6691 Annex B. Binder grade 100/150.
Binder Course	60mm	AC20 dense bin PD6691 Annex B. Binder 100/150.
Base Course	100mm	AC32 base PD6691 Annex B. Binder 100/150.
Sub Base	150mm	Type 1 Material in accordance with Specification for Highway Works Clause 803
Geotextile / Geogrid		Terram 1000

Alternative foundation thickness subject to CBR value:
- 15% > CBR > 6% Sub-base: 200mm Type 1
- 6% > CBR > 4% Sub-base: 250mm Type 1
- 4% > CBR > 3% Sub-base: 300mm Type 1
- 3% > CBR > 2% Sub-base: 350mm Type 1 + NAUE Combigrid 40/40
- 2% > CBR Seek consultant advice




ASPHALT FOOTPATH PEDESTRIAN		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	25mm	AC 6 medium surface course PD 6691 Annex B
Binder Course	50mm	AC 20 dense binder course PD 6691 Annex B
Sub base	150mm	Type 1 Material in accordance with Specification for Highway Works Clause 803
Geotextile		Terram 1000



ASPHALT FOOTPATH CROSSOVER		
Assumed CBR >15% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	30mm	AC10 close surf PD6691 Annex B. Binder grade 100/150.
Binder Course	60mm	AC20 dense bin PD6691 Annex B. Binder 100/150.
Sub Base	150mm	Type 1 Material in accordance with Specification for Highway Works Clause 803
Geotextile / Geogrid		Terram 1000


Alternative foundation thickness subject to CBR value:
- 15% > CBR > 6% Sub-base: 200mm Type 1
- 6% > CBR > 4% Sub-base: 250mm Type 1
- 4% > CBR > 3% Sub-base: 300mm Type 1
- 3% > CBR > 2% Sub-base: 350mm Type 1 + NAUE Combigrid 40/40
- 2% > CBR Seek consultant advice



PEDESTRIAN BLOCK PAVING		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	60mm	100 x 200mm concrete blocks to Architects detail. Jointing material to block manufacturers specification. Allow for topping up of jointing material 3 months after completion.
Laying Course	30mm	Sand (To interpave spec)
Sub base	150mm	Type 1 Material in accordance with Specification for Highway Works Clause 803
Geotextile		Terram 1000

PERMEABLE BLOCK PAVING NO INFILTRATION (CARS & VANS ONLY)		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	80mm	Permeable concrete block with interlocking nibs to Architects detail. Jointing material to block manufacturers specification. Allow for topping up of jointing material 3 months after completion.
Laying Course	50mm	Angular bedding material to BS EN 13242 and in accordance with the paving block manufacturer.
Base Course	70mm	AC32 40/60, in accordance with BS EN 13108-1. Temporary access for construction traffic. Prior to installation of the paving units the AC is cleaned to removed mud and detritus, cored with 75mm dia holes on a 750mm orthogonal grid to form CAC (cored asphalt concrete). The holes are filled with laying course aggregate.
Sub base	350mm	Coarse graded aggregate (CGA) to comply with BS EN 13242 (BSI 2007 or BS 12620 (BSI 2008). Deemed to comply Type 3 sub base 0mm-40mm SHW Serier 800 or Coarse graded aggregate 4mm-20mm BS7533-13. Laid in maximum 150mm layer
Geogrid		NAUE combigrid 40/40.
Impermeable Membrane		HDPE membrane with fully welded membrane




- Cutting Blocks; use a diamond bladed saw. Block splitters are NOT permitted
- Small slender cuts less than 25% NOT permitted.
- Joint space; blocks to be tightly butted
- Edge restraints shall be installed along the exposed perimeter and to drainage items and other penetrations within the pavement






TYPICAL SECTION THROUGH DISTRIBUTION PIPE

CONCRETE SLAB PAVING PEDESTRIAN		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	50mm	Paving slab to Architects specification. Jointing to manufacturers specification
Laying Course	30mm	Sand (To interpave spec)
Sub base	150mm	Type 1 Material in accordance with Specification for Highway Works Clause 803
Geotextile		Terram 1000


SELF-BINDING GRAVEL PATH (PEDESTRIAN ACCESS ONLY)		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	50mm	Self-binding gravel to Landscape Architect's specification
Sub base	150mm	Coarse graded aggregate (CGA) to comply with BS EN 13242 (BSI 2007 or BS 12620 (BSI 2008). Deemed to comply Type 3 sub base 0mm-40mm SHW Serier 800 or Coarse graded aggregate 4mm-20mm BS7533-13. Laid in maximum 150mm layer
Geotextile		Terram 1000



TYPICAL DROP KERB CONFIGURATION




JUNCTION BETWEEN TANKED PERMEABLE PAVING & TARMAC
(Formation to be proof rolled prior to construction)



RAISED TABLE DETAIL

Scale 1:20



CARS & VANS ONLY PERMEABLE BLOCK PAVING OVER CELLWEB		
Assumed CBR >3% (Subgrade to be proof rolled)		
Layer	Thickness	Material
Surface Course	80mm	Permeable concrete block with interlocking nibs to Architects detail. Jointing material to block manufacturers specification. Allow for topping up of jointing material 3 months after completion.
Laying Course	50mm	Angular bedding material to BS EN 13242 and in accordance with the paving block manufacturer.
Base Course	70mm	AC32 40/60, in accordance with BS EN 13108-1. Temporary access for construction traffic. Prior to installation of the paving units the AC is cleaned to removed mud and detritus, cored with 75mm dia holes on a 750mm orthogonal grid to form CAC (cored asphalt concrete). The holes are filled with laying course aggregate.
Cellweb	150mm	Filled with open graded sub-base, clean angular stone Type 4/20 or Type 20/40. Refer to BS7533-13:2009 and to the Design Manual for Roads and Bridges (DMRB), with min 25mm overfill.
Geotextile / Geogrid		Treetex T300 Geotextile or equivalent

C01	Construction issue	KD	GT	08.07.20
T01	Issued for Tender	NJ	GT	15.05.20
P02	Preliminary Issue	NJ	GT	23.03.20
P01	First issue	NJ	GT	14.02.20

Rev.	Amendment	Dm	Chkd	Date
Drp. Status				

CONSTRUCTION A1

AKSWard²

CONSTRUCTION CONSULTANTS

Seacourt Tower West Way Oxford OX2 0JJ	☐ London ☐ Hitchin ☒ Oxford ☐ Southampton ☐ Birmingham
---	--

Tel: 01865 240071
Fax: 01865 248006
e-mail: oxford@aksward.com
web: www.aksward.com

Client	DREW SMITH LIMITED
--------	--------------------

Project **Colt Industrial Estate Havant**

Title **Road and Footpath Construction Details Private Areas**

Reviewed Scheme GT Date 14.02.20

Reviewed Final GT Date 08.07.20

Scales at A1 NTS Project No. **S198061**

Project Ref. Originator Zone Level Type Role Drg No. Rev.

CIE AKSW XX XX DR C 9120 - C01