

Notes:

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

IN ADDITION TO THE HAZARDOUSNESS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING CONSTRUCTION:

- Installation methodology to be incorporated into the design
- Where it has not been possible to mitigate the hazard by design then the residual hazard is highlighted on the relevant drawing with this symbol

MAINTENANCE / CLEANING:

- No special measures required

DECOMMISSIONING / DEMOLITION:

- Reverse of installation methodology

IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT

FOR GENERAL NOTES SEE DRAWING S-00

FOR SECTIONS PLEASE SEE DRAWINGS 1100 & 1101

450mm thick RC Slab
Self Weight = 24kN/m²
Superimposed Dead Load = 5kN/m²
Live Load = 15kN/m²

The pile locations to be hand dug to a depth of 0.75m to ensure that no large roots would be damaged. If roots are found, the pile location to be shifted to avoid them.

Ditch

Bus

New 1.8m high clo
boarded fence

Proposed Laurel
hedge to act as
screen between
properties

PLOT 1
5 BED DWELLING