1 The Grove Felpham West Sussex PO22 7EY	Woodcroft SW Design
Date 07/08/2019 12:51 File FC2789 Woodcroft- sw de...	Designed by mh Checked by
Micro Drainage	Network 2017.1.2

Summary of Results for 90 minute 1 year Summer (Storm)

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF
Analysis Timestep Fine Inertia Status OFF
DTS Status ON

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status
1.000	SWS13	67.147	-0.103	0.000	0.21		3.5	OK
1.001	SWS12	66.958	-0.116	0.000	0.12		4.8	OK
1.002	SWS11	65.681	-0.194	0.000	0.05		4.7	OK
2.000	SWS10.1	65.345	-0.180	0.000	0.09		6.2	OK
1.003	SWS10	64.714	-0.227	0.000	0.13		13.5	OK
1.004	SWS9	64.439	-0.215	0.000	0.18		13.4	OK
1.005	SWS8	63.098	-1.012	0.000	0.03		22.5	OK
3.000	Dummy	62.933	-0.225	0.000	0.00		0.0	OK
3.001	SW7.3	62.929	-0.225	0.000	0.00		0.0	OK
3.002	SW7.1	63.080	-0.795	0.000	0.00	0.0	1.1	OK
1.006	SWS7	63.080	-0.990	0.000	0.03		19.8	OK
1.007	SWS6	63.077	-0.983	0.000	0.04		19.3	OK
4.000	SWS5.1	65.277	-0.198	0.000	0.03		3.8	OK
1.008	SWS5	63.070	-0.976	0.000	0.03		27.1	OK
1.009	SWS4	63.057	-0.751	0.000	0.05		32.2	OK
1.010	SWS3	63.046	-0.006	0.000	0.42		26.4	OK
1.011	SWS2	62.795	-0.193	0.000	0.27		26.4	OK

©1982-2017 XP Solutions