

From: Anthony Cave
Sent: 27 November 2019 15:25
To: Eaves, David
Cc: Haigh, Sascha
Subject: APP/18/00453 Reserved Matters Bartons Road Havant - Condition 3

Good Afternoon David,

Please see below and attached the response from Roger Bullivant Limited regarding **APP/18/00453 Reserved Matters** Condition 3.

We have attached a copy of the boreholes that you provided for the project which confirm the comments made by JD (Consultee Comments) that the chalk is expected to be encountered at least 20m below the existing ground level. Above the chalk is the London Clay. Roger Bullivant installed piles to a maximum depth of 13.0m below ground level (varied from 7.0-13.0m) and Vibro stone columns to a maximum depth of 6.0m below ground level. This means that there is at least 7.0m of London Clay beneath the toe of the pile before the chalk is encountered and 14.0m in the case of the Vibro stone columns. As such the piling and vibro stone column works will not have any impact on the chalk aquifer.

We trust the above is self-explanatory, should you have further questions please don't hesitate to contact us.

I look forward to receiving any comments or discharge of this condition.

Kind regards

Anthony Cave
Technical Manager

Bellway Homes Limited (Wessex)

Ringwood
Hampshire
BH24 1EU



Bellway is proud to be supporting Cancer Research UK as their charity of the year.