



Existing signage to be replaced



f1

Internally illuminated Fascia
600mm(h)
Existing building letters to be removed and area made good. New internally illuminated fascia with push through letters to be installed. Push-through letters to be positioned centrally above entrance doors.
To be installed with dimmer switch
Qty - 1

b4

Building Letters
330mm 'W' cap height
Letters to be removed and area made good. Panels to be replaced with new grey panels
Qty - 1

t1

3m Totem
Existing totem to be removed and new totem to be installed in the same location.
Totem to be single sided.
Qty - 1



b5

Building Letters
Panel to be removed and area made good. Render to be painted white and new letters installed
Exact size of letters TBC.
Qty - 1




5

Welcome letters
59mm Cap height
Existing shopping hours vinyl to be removed, all residue cleaned and glazing made good. New sets of welcome letters to be installed on to glazing.
Qty - 1



6

Directional Panel
856mm(w)
Whole sign to be removed and area made good. New sign to be installed in same location.
Artwork TBC
Qty - 1




7

Partner Parking
550mm(w)
Existing sign to be removed and new sign installed in same location.
Qty - 4



8

No pedestrian access
300mm(w)
Existing sign to be replaced with DFT sign.
Qty - 1



9

Max Height & Bump bar
4207mm(w) *Exact size TBC*
Existing panel and bump bar to be replaced with the latest standards.
Signage contractor to confirm available space. Max Height TBC
Qty - 1