

Park Wood – Tree works specification (TPO on whole site)

Tree No	Tagged	Species	Age	Height	Diameter	Vitality	Description	Recommendations & spec:
G1	Orange paint dots	Ash x3	Semi-mature	15m	Up to 30cm	In decline	Crown: Advanced Ash Dieback symptoms. Stem: Minor ivy in places Root Zone: N/A Site Factors: TPO. Adjacent to an A road. Public footpath & cycle lane adjacent. Trees on bund adjacent to ditch. Part(s) at risk of failure: Whole trees or branches. L.O.F: 2. Possible&probable Targets: Zone A: A road. Public footpath & cycle lane adjacent. Zone B: Footpath Wildlife/habitat considerations: N/A. No PRFs, ivy minor. Selective felling will not significantly affect potential bat foraging route.	Fell to ground level. Arisings: Chip brush & remove cord from site.
G2	Orange paint dots	Ash x6	Semi-mature	15m	Up to 30cm	In decline	Crown: Advanced Ash Dieback symptoms. Stem: Minor ivy in places Root Zone: N/A Site Factors: TPO. Adjacent to an A road. Public footpath & cycle lane adjacent. Trees on bund adjacent to ditch. Part(s) at risk of failure: Whole trees or branches. L.O.F: 2. Possible&probable Targets: Zone A: A road. Public footpath & cycle lane adjacent. Zone B: Footpath Wildlife/habitat considerations: N/A. No PRFs, ivy minor. Selective felling will not significantly affect potential bat foraging route.	Fell to ground level. Arisings: Chip brush & remove cord from site.
T1	Orange paint dot	Ash	Semi-mature	15m	30cm	In decline	Crown: Advanced Ash Dieback symptoms. Stem: Minor ivy in places Root Zone: N/A Site Factors: TPO. Dense ground cover surrounding tree. Part(s) at risk of failure: Whole tree. L.O.F: 2. Possible&probable Targets: Zone A: Back garden of neighbouring property. Wildlife/habitat considerations: N/A. No PRFs, ivy minor.	Fell to ground level. Arisings: Stack in wood
T2	No	Goat Willow	Over mature	8m	80cm	Normal	Crown: Failed branches & stems at previous reduction points. Stem: 3 stems. Central one has failed & is now a stub. Ivy on some areas of stem. Root Zone: N/A Site Factors: TPO. Dense vegetation surrounding tree. Part(s) at risk of failure: Upper branch sections. L.O.F: 2. Possible&probable Targets: Zone A: Back garden of neighbouring property Wildlife/habitat considerations: PRF in central stub&ivy. No signs of bats visible. Low risk.	RETAIN CENTRAL STEM UNTOUCHED. Retain ivy. Pollard upper stem/branches at approx 5m. Arisings: Stack in wood.
T3	Orange paint dot	Oak	Young	8m	25cm	In decline	Crown: Half dead Stem: N/A Root Zone: Some bark damage at base. Site Factors: TPO Part(s) at risk of failure: Branches L.O.F: 2. Possible&probable Targets: Zone B: Footpath & bench Wildlife/habitat considerations: N/A	Fell to ground level. Arisings: Stack in wood

DO NOT STACK ARISINGS WITHIN 2M OF FOOTPATHS, DITCHES OR INFRASTRUCTURE.

