



Tree No	Species	Category	RPA Radius	Tree Works	Tree No	Species	Category	RPA Radius	Tree Works	Tree No	Species	Category	RPA Radius	Tree Works			
All retained trees & hedges				Carry out safety check and lift over site to 3-4m as necessary.	All retained trees & hedges				Carry out safety check and lift over site to 3-4m as necessary.	All retained trees & hedges				Carry out safety check and lift over site to 3-4m as necessary.			
	T1	Sycamore	B	5.4		-	T26	Sycamore	B		7.8	-	T44	Poplar	U	7.2	Extant consent to be felled
	T2	Sycamore	B	4.8		-	T27	Sycamore	B		7.2	-	G45	Sycamore, cherry	C	5.4	-
	T3	Yew	C	4.8		-	G28	Sycamore	C		6.0	-	T46	Holly	C	3.6	-
	T4	Yew	B	6.6		-	T29	Ash	B		6.0	-	T47	Sycamore	B	4.2	-
	G5	Yew, laurel, cypress, bay, cherry	C	6.0		Felled under extant consent	G30	Lime, cherry, ash, cypress	C		12.0	-	T48	Oak	C	3.0	Fell
	G6	Sycamore	C	8.4		Felled under extant consent	T31	Cherry	C		7.2	-	T49	Oak	C	3.6	Fell
	G7	Sycamore	C	7.2		Felled under extant consent	T32	Bay	C		15.0	Felled under extant consent	G50	Sycamore	B	7.2	Remove two smaller stems to leave the main tree
	G8	Acacia	C	3.0		Felled under extant consent	T33	Poplar	C		6.0	-	T51	Bay	C	4.8	Fell
	G9	Sycamore	C	5.4		Felled under extant consent	T34	Poplar	C		7.2	-	G52	Holly, bay, laurel	C	3.6	Fell one tree
	T10	Acacia	C	6.6		Felled under extant consent	T35	Poplar	C		3.6	-					
	G13	Laurel, bay, buddleia	C	3.6		Felled under extant consent	T36	Monterey cypress	C		6.0	-					
	G15	Laurel, goat willow	C	7.2		Felled under extant consent	T37	Monterey cypress	C		5.4	-					
	T16	Ash	C	4.8		Felled under extant consent	T38	Western red cedar	B		5.4	-					
	T17	Beech	C	3.6		Felled under extant consent	G39	Western red cedar, cypress	C		4.2	Extant consent to be felled					
G22	Holly, bay	C	2.4	Cut back lateral growth	T40	Poplar	C	7.2	Extant consent to be felled								
T23	Yew	B	7.8	-	T41	Poplar	C	5.4	Extant consent to be felled								
T24	Oak	B	5.7	-	T42	Poplar	C	5.4	Extant consent to be felled								
T25	Cedar	B	14.1	-	T43	Poplar	C	5.4	Extant consent to be felled								

- | | | |
|---|---|--------------------------------|
|  | BS category B | Trees of moderate quality |
|  | BS category C | Trees of low quality |
|  | BS category U | Trees unsuitable for retention |
|  | Trees to be removed | |
|  | Proposed layout | |
|  | Approved site under construction | |
|  | Approved site not yet under construction | |
|  | Estimated tree positions not included on original land survey and/or adjusted crown spreads | |
|  | Construction exclusion zone (CEZ) to be protected by fencing and/or ground protection | |
|  | Precautinary area where new surfacing will be installed using a three dimensional cell base and porous wearing course | |
|  | Construction exclusion zone protected by ground protection | |
|  | Root protection area (RPA) boundaries for category B trees | |