TREES

A	Ash
AL	Alder
AP	Apple
B	Beech
C	Cedar
CB	Copper Beech
CH	Cherry
CY	Cypress
E	Elm
EL	Elder
EU	Eucalyptus
F	Fir
FM	Field Maple
FR	Fruit
HZ	Hazel
HC	Horse Chestnut
HO	Holm Oak
HW	Hawthorn
HY	Holly
JM	Japanese Maple
LB	Laburnum
LM	Lime
LO	Locust Tree
LR	Laurel
M	Maple
MG	Magnolia
OK	Oak
P	Pine
PA	Palm
PL	Plane
PM	Plum
PO	Poplar
PP	Pissardii Plum
PR	Pear
R	Redwood
RD	Red Oak
RH	Rhododendron
RO	Rowan
SB	Silver Birch
SC	Sweet Chestnut
SP	Scots Pine
SU	Spruce
SY	Sycamore
U	Unidentified
W	Willow
WN	Walnut
Y	Yew

Species / Dia / Spread (max) / Ht
e.g. OK / 0.6 / 8 / 15

KEY

BT	British Telecom
BOL	Bollard
CB	Control Box
CL	Cover Level
CTV	Cable Television
EL	Electric
EP	Electricity Pole
FH	Fire Hydrant
GSV	Gas Stop Valve
HT	Height
HVC	High Voltage Cable
IC	Inspection Cover
IL	Invert Level
LP	Lamp Post
MH	Man-Hole
MKR	Marker
MW	Monitoring Well
O/H	Overhead
G	Road Gully
PB	Post Box
PC	Pram Crossing
RNP	Road Name Plate
RS	Road Sign
S/A	Soakaway
ST	Stay / Strut
SV	Stop Valve (Unidentified)
TB	Telephone Box
TC	Telecom
TH	Trial Hole
TL	Traffic Light
TP	Telegraph Pole
UTL	Unable to Lift
VP	Vent pipe
WM	Water Meter
WSV	Water Stop Valve

FENCES

BWF	Barbed Wire Fence
CBF	Closed Board Fence
CP	Concrete Post
CPF	Chestnut Paling Fence
CWF	Chicken Wire Fence
IRF	Iron Railing Fence
PKF	Picket Fence
PRF	Post & Rail Fence
PWF	Post & Wire Fence
SCF	Security Fence
SP	Steel Post
WMF	Wire Mesh Fence
WPF	Wood Panel Fence

SURVEY STATIONS

Name	Easting	Northing	Height	Type
S1	470868.438	99738.849	6.150	Nail
S2	470766.598	99763.985	6.048	Nail
S3	470969.727	99717.708	6.079	Nail
S4	470874.762	99794.775	5.941	Peg
S5	470892.752	99864.630	5.952	Peg
S6	470771.590	99892.579	5.492	Peg
S7	470681.440	99864.643	5.857	Peg
S10	471094.742	100188.088	5.019	Peg
S12	470861.807	100225.840	4.793	Peg
S13	471103.008	100187.407	4.885	Peg
EP1	470894.062	99984.677	7.505	Nail
EP2	470765.997	99891.367	7.224	Nail
EP3	470658.901	99813.340	7.887	Nail

Revision B - May 2018
Survey extended to north outfall
Revision A - April 2017
Survey extended to the north

NOTES:

The survey grid has been related to a local determination of OS National Grid using a flat earth projection and metric scale factor of 1, centred on Station S1. Levels are related to OS datum determined from the National GPS Network using OSGM02.

No assumptions should be made regarding the interconnection of manholes. Drainage details have been obtained from surface inspection and should be verified if of critical importance.

The position and height of adjacent buildings have been obtained using higher level reflectorless measurement and may not take account of single storey extensions or conservatories below the line of sight.

Geomatic Surveyors

siteline

Unit E, Woodside
34 Parham Drive
Eastleigh
SO50 4NU

t: 023 8081 1081
f: 023 8081 1012
w: siteline.co.uk

BARRATT DAVID WILSON	Client
LAND AT SINAH LANE HAYLING ISLAND HAMPSHIRE	Contract
SITE SURVEY	Title
36HX001B - Sheet 5 of 7	Drawing No.
JUNE 2016	Date
1:250 (A0)	Scale
MJR/ST/MU	Surveyor