

KEY:

- ACCESS TRACK
- PERIMETER DRAIN
- BALANCING LAGOON DRAIN
- BALANCING LAGOON OVERFLOW DITCH
- ENVIRONMENTAL INFRASTRUCTURE
- COMPOUND FENCE
- LAGOON
- WOODLAND PLANTING AREA
- MEADOW GRASSLAND AREA

WOODLAND PLANT SCHEDULE

- WOODLAND GRASS SEED
Emergence EPI (or similar approved) 4g/m²
- NATIVE WOODLAND MIX
- TREES (60%)
- Acer campestre 10
 - Betula pendula 10
 - Corylus avellana 10
 - Castanea sativa 10
 - Corylus avellana 5
 - Ilex aquifolium 5
 - Prunus spinosa 10
 - Quercus petraea 5
 - Quercus robur 15
- SHRUB UNDERSTOREY (40%)
- Cornus avellana 10
 - Fraxinus excelsior 10
 - Ligustrum vulgare 20
 - Prunus spinosa 20
 - Viburnum lantana 10
- All plants to be 600-900mm bare root or cell grown whips.
To be planted in random groups of 5-15 species at 2-3m centres (random density)

MEADOW PLANT SCHEDULE

- MEADOW GRASS SEED
Emergence EPI2 (or similar approved) 4g/m²

SPECIFICATION

Ground Preparation and Planting to be undertaken as detailed in Restoration Scheme

Plants to be protected by individual guards not height 1.2m or by deer exclusion fencing around woodland blocks. Site perimeter chainlink fencing is deemed equivalent to deer exclusion fence for the external boundary of the woodland area.

MAINTENANCE

All plants material to be maintained in accordance with the details in the Aftercare Scheme



REV	DESCRIPTION	BY	CHK	APP	DATE
1	EMBERS HOUSE 12 EMBERS ROAD SOUTHLEIGH, HANTS SO43 7AE				
2	TEL: +44 (0)23 8028 3226 FAX: +44 (0)23 8028 3223 E-mail: embers@embers.co.uk				
3	Client: VEOLOIA				
4	Project: SOUTHLEIGH LANDFILL SITE				
5	Drawing Title: POST SETTLEMENT RESTORATION CONTOURS AND LANDSCAPE PLAN				
6	Office Project No. 8146 Drawn Date: 10/12/15	Drawing No. RL-P-01 Issue 0 Approved Date:	Revision 0	Scale @ A1 1:1250	