

[illegible][illegible]

Manhole Ref	Level	Invert (m)	Depth (m)	Const./ Constr. (m)	Cover/ Grade
S1	7.50	6.40	1.10	B	B125
S2	7.37	6.40	0.97	B	D400
S3	7.32	6.40	0.92	B	D400
S4	7.15	6.40	0.75	B	D400
S5	7.15	6.40	0.75	B	D400
S6	7.15	6.40	0.75	B	D400
S7	7.15	6.40	0.75	B	D400
S8	7.15	6.40	0.75	B	D400
S9	7.15	6.40	0.75	B	B125
S10	7.15	6.40	0.75	B	D400
S11	7.15	6.40	0.75	B	D400
S12	7.15	6.40	0.75	B	D400
S13	7.15	6.40	0.75	B	B125
S14	7.38	6.40	0.98	B	D400
S15	7.15	6.40	0.75	B	B125
S16	7.15	6.40	0.75	B	B125
S17	7.42	6.40	1.02	B	B125
S18	6.75	6.00	0.75	B	B125
S19	6.75	6.00	0.75	B	D400
S20	6.75	6.00	0.75	B	D400
S21	7.15	6.40	0.75	B	D400
S22	7.15	6.40	0.75	B	D400

Foul Monitors		Schedule			Cover/ Grade
Manhole Ref	Cover Level	Invert Level (m)	Depth/ Constr	Size/ tion	
F1	7.15	3.43	3.72	B	D400
F1a	7.15	2.97	4.18	B	D400
F2	7.15	3.99	3.16	B	D400
F3	7.15	4.17	2.98	B	D400
F4	7.15	4.75	2.40	B	D400
F5	7.15	5.47	1.68	B	D400
F6	7.15	5.62	1.53	B	D400
F7	7.15	4.74	2.41	B	D400
F8	7.15	5.17	1.98	B	D400
F9	7.15	5.25	1.40	B	D400
F10	7.15	5.99	1.16	B	D400
F11	7.20	6.25	1.05	B	D400
F12	7.40	6.05	1.35	B	D400
F13	7.38	6.03	1.35	B	D400

REFER TO HDL DRG. Nos. 14-2260-510
FOR EXTERNAL WORKS /DRAINAGE DETAILS

SIZE OF SOAKAWAYS SUBJECT TO RESULT OF
PERCOLATION TESTS

SOAKAWAYS TO BE LOCATED A MINIMUM OF
5m FROM ANY FOUNDATION

Vehicle	Assignment	Days off	Days on	Days off
C9	CONSTRUCTION	HLJ/06/17	HLJ/06/17	HLJ/06/17
C8	CONSTRUCTION	HLJ/06/17	HLJ/06/17	HLJ/06/17
C7	CONSTRUCTION	HLJ/09/16	HLJ/09/16	HLJ/09/16
C6	CONSTRUCTION	HLJ/09/16	HLJ/09/16	HLJ/09/16
ORIGINAL DRAWING SIZE = A1				
C&B REF.				
X-REFS :				
C&B REF.				