

TREE WORK SCHEDULE.

Site : The Green Cottage. 23 Langstone High Street, PO9 1RY.

Trees in a Conservation Area Notification.

Tree Ref Number	Tree Species and Description	Reason for Work	Work Description
T1	Magnolia. Height : 5.5m Tree has poor conformation; One stem kinked and subsiding. Further stem has tight bifurcation with included bark.	Tree poorly located close to buildings/structures; Close to house and 500mm from tall boundary wall between properties and brick out building. Very spreading crown significantly in contact with fabric of house with potential to cause damage. Tree has poor conformation.	- Fell
T2	Fig. Height : 5.5m 5 stems from ground level. Extensive decay evident at point of main stems union. Some stems have collapsed and further stem subsidence ongoing. Decay is also evident at numerous pruning wounds throughout tree Stem to South is in contact with 3m brick boundary wall between properties.	Tree in a state of ongoing collapse due to poor conformation and extensive decay.	- Fell
T3	Macrocarpa. Height 9-10m Crown spread (metres) : North-8-9, South 3, East 5, West 3.5.	Tree poorly located at edge of driveway.Stem/limbs in contact with neighbouring boundary fence. Majority of crown over-extending a neighbouring property to North. Tight union of limbs with included bark in crown to North. Failed hung-up branches and significant deadwood in crown.	- Fell - Plant suitable replacement specimen tree in border along South of drive.

TREE LOCATION PLAN.

Site : The Green Cottage. 23 Langstone High Street, PO9 1RY

Trees in a Conservation Area

