



LEGEND:

SYM.	DESCRIPTION
	BOUNDARY OF DEVELOPMENT SITE
	EXISTING BUILDINGS TO BE RETAINED
	PROPOSED CARAVAN BASES
	EXISTING TREES TO BE RETAINED
	EXISTING HEDGES / SCRUB TO BE RETAINED
	PROPOSED WOODLAND PLANTING.
	PROPOSED SPECIMEN TREES
	PROPOSED WILDFLOWER MEADOW AREAS
	PROPOSED MOWN GRASS AREAS
	EXISTING AMENITY GRASS AREAS
	EXISTING WATER BODIES
	PROPOSED ACCESS ROADS / PARKING BAYS
	PROPOSED PATHS & PEDESTRIAN AREAS
	PROPOSED DECK AREAS AROUND CENTRAL COMPLEX

NOTES:

- PROVIDE MINIMUM DEPTH OF TOPSOIL TO PLANTED AREAS AS FOLLOWS: GRASS AREAS : 200MM, SHRUB PLANTING: 450MM, AND TREE PITS: 750MM.
- TREE PITS SHALL BE BACKFILLED WITH A PRE-MIXED SOIL/ COMPOST MIXTURE INCORPORATING A SLOW RELEASE FERTILIZER.
- SPECIMEN TREES TO BE DOUBLE STAKED WITH SINGLE CROSSBAR.
- TO EACH TREE, TRANSPLANT AND CONTAINER GROWN PLANTING STATION THE CONTRACTOR SHALL SUPPLY AND INCORPORATE A SLOW RELEASE FERTILIZER.
- CONTAINER GROWN STOCK SHALL BE PLANTED IN A PIT EXCAVATED TO SUFFICIENT DEPTH AND WIDTH TO ACCOMMODATE THE PLANT WITHOUT DISTURBING THE ROOTS.
- TRANSPLANT PITS SHALL BE EXCAVATED TO A DEPTH OF 300MM DIAMETER AND 300MM DEPTH BELOW EXISTING GROUND LEVEL. ALL PITS SHALL BE EXCAVATED TO SUFFICIENT DEPTH AND WIDTH TO ACCOMMODATE THE PLANT WITHOUT DISTURBING ITS ROOTS. DURING BACKFILLING THE FINAL SOIL LEVEL AROUND THE TRANSPLANT SHOULD BE RAISED TO 40MM ABOVE THE SURROUNDING SOIL LEVEL.
- ORNAMENTAL PLANTING AREAS SHALL BE CULTIVATED TO A MEDIUM TILTH AND 300MM DEEP. A SLOW RELEASE FERTILIZER SHALL BE INCORPORATED IN A SECOND PASS FOLLOWING INITIAL CULTIVATION. THE CONTRACTOR SHALL PLACE A 50MM LAYER OF ORGANIC MULCH TO COVER THE COMPLETE AREA OF ORNAMENTAL PLANTING AREAS. BEFORE APPLICATION OF THE MULCH THE AREA SHALL BE WEED FREE. THE CONTRACTOR SHALL PLACE A 75MM DEPTH LAYER OF ORGANIC MULCH TO A CIRCLE 500MM RADIUS AROUND THE BASE OF ALL STANDARD TREES WITHIN GRASS AREAS. BEFORE APPLICATION OF THE MULCH THE AREAS SHALL BE WEED FREE.
- PLANTING BEDS SHOULD BE KEPT COMPLETELY WEED FREE AND DEPTH OF MULCH MAINTAINED AT 50MM DEPTH.
- RABBIT GUARDS MAY BE REQUIRED, EITHER INDIVIDUAL GUARDS OR FENCING.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LOCATION OF SERVICES PRIOR TO PLANTING. TREES WITHIN PLANTING MIXES SHOULD BE PLACED AWAY FROM ANY OVERHEAD POWER LINES.