LEGEND

- Site boundary
- Existing tree to be retained and protected. Refer to arboricultural information for further detail
- Existing vegetation and/or hedgerow to be retained and protected. Refer to arboricultural information for further detail

Proposed soft landscaping

- Tree planting, refer to detail refer to detail GLS_090_151_1700
- Ornamental hedge - Double staggered 1.2m high in front gardens and 1.8m high elsewhere
- Double staggered mixed native hedgerow To be planted in groups of 7-9no. of each species
- Ornamental shrub planting
- Native scrub planting mix To be planted in groups of 7-9no. of each species
- Good quality hardwearing lawn
- Species rich neutral grassland EMS Meadow Mix for Loam soils from Emorsgate or similar seeded at 4g/m2
- Wetland meadow EMB Meadow Mixture for Wetlands from Emorsgate or similar seeded at 4g/m2

NOTES:

To be read in conjunction with:

- Landscape general arrangement plan GLS_090_151_1300
- Detailed hard landscape plans GLS_090_151_1600
- Landscape specification GLS_090_151_1801
- Landscape management plan GLS_090_151_1802

Plant schedule

Trees					
Number	Abbreviation	Species	Height	Girth	Specification
3	Ac	Acer campestre 'Elsrijk'	400-450cm	8-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
2	AgRH	Amelanchier x grandiflora 'Robin Hill'	400-450cm	8-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
6	Bn	Betula nigra	400-450cm	8-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
1	Bpe	Betula pendula	350-400cm	12-14cm	Heavy Standard -Clear Stem min. 200 RB
4	Ce	Carpinus betulus	350-400cm	12-14cm	Heavy Standard -Clear Stem min. 200 RB
4	Ccol	Corylus colurna	400-450cm	18-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
3	Cbe	Crataegus broweana	400-450cm	8-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
4	Pp	Prunus padus	350-400cm	12-14cm	Heavy Standard -Clear Stem min. 200 RB
3	Sau	Sorbus aria 'Lutescens'	400-450cm	8-18cm	Extra Heavy Standard -Clear Stem min. 200 RB
1	Ssu	Sorbus aucuparia	350-400cm	12-14cm	Heavy Standard -Clear Stem min. 200 RB
2	Tec	Tilia x europaea	350-400cm	12-14cm	Heavy Standard -Clear Stem min. 200 RB
Total 30					

Mixed native hedgerow planting

Number of Plants	Abbreviation	Species	Specification	Height	Pot Size	Density
95	Ac	Acer campestre	Transplant /Bushy	80-80cm	80-80cm	4-5/m Double Staggered at 0.4m offset
95	Ag	Alnus glutinosa	Transplant /Bushy	80-80cm	80-80cm	4-5/m Double Staggered at 0.4m offset
95	Cav	Corylus avellana	Bushy /BR	60-80cm	80-80cm	4-5/m Double Staggered at 0.4m offset
468	Cmo	Crataegus monogyna	Transplant /Bushy	80-80cm	80-80cm	4-5/m Double Staggered at 0.4m offset
95	Psp	Prunus spinosa	Bushy /BR	60-80cm	80-80cm	4-5/m Double Staggered at 0.4m offset
95	Rca	Rosa canina	Bushy /BR	40-60cm	80-80cm	4-5/m Double Staggered at 0.4m offset
Total 943						

Single species hedge planting

Number of Plants	Abbreviation	Species	Specification	Height	Pot Size	Density
659	Ed	Euonymus fortunei	Bushy /C	60-80cm	3L	5/m Double Staggered at 0.3m offset
Total 659						

Shrubs

Number	Abbreviation	Species	Specification	Height	Pot Size	Density
44	Bsp	Brachyglottis 'Sunshine'	Bushy /C	40-60cm	3L	1/m²
41	CBM	Ceanothus 'Blue Mound'	Bushy /C	40-60cm	3L	1/m²
66	CpAF	Cistus ×pauranus 'Alan Fradd'	Bushy /C	30-40cm	3L	4/m²
131	EfEnG	Euonymus fortunei 'Emerald 'n' Gold'	Bushy /C	20-30cm	3L	4/m²
106	FMP	Fuchsia 'Mrs Popple'	Bushy /C	40-60cm	3L	1/m²
22	HMW	Hebe 'Mrs Winder'	Bushy /C	30-40cm	3L	4/m²
33	Hr	Lavandula angustifolia	Bushy /C	30-40cm	3L	4/m²
18	LaH	Lavandula angustifolia 'Hidcote'	Bushy /C	30-40cm	3L	4/m²
33	PrGC	Pachysandra terminalis 'Green Carpet'	Bushy /C	15-20cm	3L	5/m²
43	PrTT	Pittosporum tenuifolium 'Tom Thumb'	Bushy /C	30-40cm	3L	4/m²
115	PlOL	Prunus laurocerasus 'Otto Luyken'	Bushy /C	30-40cm	3L	3/m²
74	ShdPS	Sarcococca hookeriana var. humilis 'Purple Stem'	Bushy /C	30-40cm	3L	4/m²
73	SjKW	Skimmia japonica 'Kew White'	Bushy /C	30-40cm	3L	4/m²
Total 1175						

Herbaceous

Number	Abbreviation	Species	Specification	Pot Size	Density
99	BcP	Bergenia cordifolia 'Purpurea'	C Full Pot	3L	4/m²
Total 99					

Grasses

Number	Abbreviation	Species	Specification	Pot Size	Density
128	CmSS	Carex morrowii 'Silver Sceptre'	C Full Pot	3L	4/m²
Total 128					

Ornamental mix 1

Abbreviation	Species	Specification	Height	Pot Size	Min Species Density
CuPP	Cornus sanguinea 'Midwinter Fire'	Bushy /C	30-40cm	3L	1/m²
HuB	Hydrangea serrata 'Blue Bird'	Bushy /C	40-60cm	3L	1/m²
MsA	Viburnum tinus 'Apodil'	Bushy /C	30-30cm	3L	1/m²
VbD	Viburnum bodnantense 'Dawn'	Bushy /C	40-60cm	3L	1/m²
V d	Viburnum davidii	Bushy /C	40-60cm	3L	1/m²
WFP	Weigela florida 'Foliis Purpureis'	Bushy /C	40-60cm	3L	1/m²

Ornamental mix 2

Abbreviation	Species	Specification	Height	Pot Size	Min Species Density
AvGC	Abelia grandiflora 'Confetti'	Bushy /C	30-40cm	3L	4/m²
BaAN	Berberis thunbergii 'Atropurpurea Nana'	Bushy /C	30-40cm	3L	4/m²
CAP	Choisya 'Aztec Pearl'	Bushy /C	40-60cm	3L	1/m²
Cp	Cistus purpureus	Bushy /C	30-40cm	3L	4/m²
DMR	Deutzia hybrida 'Mont Rose'	Bushy /C	30-40cm	3L	4/m²
SjAV	Spiraea japonica 'Anthony Waterer'	Bushy /C	30-40cm	3L	4/m²

Ornamental mix 3

Abbreviation	Species	Specification	Height	Pot Size	Min Species Density
Al	Anemanthele lessoniana	Full Pot		3L	4/m²
Cp	Cistus purpureus	Bushy /C	30-40cm	3L	4/m²
CuPP	Cornus sanguinea 'Midwinter Fire'	Bushy /C	30-40cm	3L	4/m²
He	Hebe rakaiensis	Bushy /C	30-40cm	3L	4/m²
MsML	Miscanthus sinensis 'Morning Light'	Full Pot		3L	4/m²
PeBS	Pennisetum 'Blue Spire'	Bushy /C	30-40cm	3L	4/m²

FOR TENDER

Scale @ A0

0 1 2 3 4 5 6 7 8 9 10m

Scale 1:200

NORTH

Rev	Date	Drawn	Checked

Date: 11.06.24

Drawn by: LM

Checked by: AE

Drg No: GLS_090_151_1500

Rev:

Project: Land West of Coldharbour Farm Road Emsworth

Title: Landscape Planning Plan

Client: DOSWELL PROJECTS

GREENLANDSCAPE

Green Landscape Studio Limited - The Lakeside Centre, Lakeside Country Park, Wide Lane, Eastleigh, Hampshire - Telephone 01278 450059 - www.glstudio.co.uk
This drawing and the ideas depicted are the copyright of Green Landscape Studio Ltd and may not be reproduced or amended except by written permission. No liability will be accepted for amendments made by other persons.