

Thank you for consulting us on the drainage details relating to Phase 2 of the development. The LLFA is commenting on the details submitted to discharge conditions 28 and 29.

The proportion of runoff from the redeveloped Zone 3B (Phase 2) was determined to be 55.44 l/s, this has been reduced further to 19.1 l/s in this latest application. It is stated that the volume of attenuation will remain the same as previously agreed. The calculations show that the volume of attenuation is appropriate for the design storm when discharging at this reduced rate. Parts (a), (b), (c), (d), and (g) of condition 28 have been considered sufficiently, however for (e) and (f) a numerical assessment of the treatment potential of the proposed SuDS features should be presented in accordance with the simple index approach outline in The SUDS Manual. This should include evidence of the indices for proprietary treatment systems such as the separator proposed.

Some details relating to Condition 29 do not appear to be on the website, please advise (13508 – Havant Phase 2: - [Engineers Response to planning condition 29](#) (including [Drawing Ref. 13508-129](#), [CCTV survey carried out by Greenhatch Surveys](#) and Drawing Ref 13508-121).

Regards

Tom Callaway

Senior Flood and Water Management Project Officer
Flood and Water Management

thomas.callaway@hants.gov.uk
www.hants.gov.uk