



Note:
All drawings to be read in conjunction with all other drawings as noted on issue sheet.

All existing signage to be removed and discarded as McDonald's PM instruction. Any firing holes, electrical cable penetrations etc to be made good, flush with surrounding finishes.

All surfaces that are to be re-sprayed, must be firstly treated with suitable primers as agreed with the McDonald's PM, prior to receiving new paint finish.

Drive thru booths including Servo-side to be clad in timber effect alu panels full height with inset brake strips and curved corner. Alcoves in between booths are to be clad in full height alu panels finished in khaki green ref: RAL 6015.



This drawing has been reviewed and signed off by McDonald's Restaurants Ltd
any errors, changes or discrepancies should be reported to the McDonald's
project manager and designers prior to commencing work on site

Name (PM): _____ Date: _____

Signature: _____

GENERAL NOTES:
All works are to be undertaken in accordance with the Building Regulations and the latest British Standards.
All proprietary materials and products are to be used strictly in accordance with the manufacturers recommendations.
All dimensions to be checked on site prior to construction.



C7 Architects Ltd
PM House,
Riverway Industrial Estate,
Peasmarsh, Surrey
GU3 1LZ

