



NOTES

- 1 This drawing to be read in conjunction with all relevant Architects and Engineers drawings and specifications.
- 2 Dimensions are in millimetres unless noted otherwise.
- 3 Original topographic survey undertaken by 3D Services Limited.
For full topographic survey information see drawing 19/08/01 by 3D Services.
All levels based on O.S. by G.P.S.
- 4 Existing levels shown thus: $+5.775$
- 5 Before excavation commences, the Contractor shall ascertain the depths, sizes and locations of all services to be crossed. Any conflicts in levels between new works and existing services shall be notified to the Engineer.
- 6 Kerb types are shown thus:
 - $\rightarrow$ K1 - 115mm Face Kerb (See STD.02.25)
 - $\rightarrow$ K3 - 6mm / 25mm Dropped Kerb (See STD.02.25)
 - $\rightarrow$ K4 - Flush Kerb (See STD.02.25)
 - $\rightarrow$ T - Transition Kerb (See drawings STD.02.25)
 - $\rightarrow$ E - Precast Concrete Edging 50 x 150mm EF
 - $\rightarrow$ R - 125mm face Marshalls Keykerb KL (half battered)
- 7 Finishes Schedule:

All formations shall be inspected and any soft or deleterious material shall be excavated and replaced with well compacted Class 6F4 / 6F5 material. The resultant formation shall be proof rolled. Recycled sub-base and capping materials in accordance with The Specification for Highway Works shall be acceptable.

PERMEABLE PAVING OVER ATTENUATION TANK
Construction : 80mm Formpave Aquaflow Concrete Blocks, or equivalent
Herringbone Bond (Block Type to be confirmed)
40mm of 6mm Nominal Sized Basalt Aggregate, or Equivalent

- Terram 1000 Geotextile, or equivalent

Depth Varies : Type 3 Permeable Sub - Base

- Terram 1000 Geotextile to top and sides of tank

PERMEABLE BLOCK PAVED PARKING AREA AND ACCESS
Construction : 80mm Formpave Aquaflow Concrete Blocks, or equivalent
Herringbone Bond (Block Type to be confirmed)
40mm of 6mm Nominal Sized Basalt Aggregate, or Equivalent

- Terram 1000 Geotextile, or equivalent

280mm Type 3 Permeable Sub - Base

- Triax Tx160 Geogrid by Tensar, or equivalent

400mm Total

GRASSGUARD DRAINAGE CHANNEL
Construction : 100mm Grassguard 130 (topsoil / seeded)
30mm 6mm nom. sized Aggregate
200mm Type 3 sub base with 30% humus mix

- Firm Formation

330mm Total

ADOPTABLE BELLMOUTH ENTRANCE (subject to agreement with Hants CC)
Construction : 50mm Hot Rolled Asphalt with High Stone Content.
HRA 30/14 surf (40/50 pen)
60mm 20mm Binder Course - 100 / 150 pen (AC 20 dense bin)
125mm 32mm Road Base - 100 / 150 pen (AC 32 base)
265mm Type 1 Sub - Base, Recycled Granular Material as detailed in the HCC Specification
500mm Total

FOOTWAYS
Construction : See drawing STD.02.35
over, 6F5 capping fill as required

SOFT LANDSCAPING

P8	RETAIL UNIT FFL SHOWN AT 6.450m.	-	PF-14-02-22
P7	SWALE DETAILED TO SOUTH EAST OF BUILDING. HEADWALLS ADDED.	-	PF-12-05-21
P6	PRECAST BOX CULVERTS SHOWN AS STORAGE TANKS IN LIEU OF PLASTIC CRATE SYSTEM.	-	PF-09-04-21
P5	DRAINAGE CHANNEL REPOSITIONED.	-	PF-20-11-20
P4	REDRAWN WITH FINISHED FLOOR LEVEL = 6.650m.	-	PF-29-10-20
P3	REDRAWN WITH FINISHED FLOOR LEVEL = 6.450m.	-	PF-15-06-20
P2	REDRAWN WITH FINISHED FLOOR LEVEL = 6.200m.	-	PF-29-05-20

REV	DESCRIPTION	CHECKED	DATE
-----	-------------	---------	------

Archibald Shaw
Consulting Civil & Structural Engineers
One Little London, Chichester, West Sussex PO19 1PP
Telephone: 01243 786471 www.archibaldshaw.co.uk

CLIENT
Hamlet Homes

PROJECT
Elm Grove
Hayling Island
Surfacing

DRAWN BY PF	CHECKED BY VC	DESIGNED BY VC/PF
SCALE @ A1 1:200	© DATE May, 2020	STATUS Planning
JOB NO. 30666	DRAWING NO. EX.02	REVISION P8