

COPYRIGHT - THIS DRAWING AND ANY AKILLARY DRAWINGS OR DATA ARE COPYRIGHT OF NIJHUIS H2OK LTD AND MAY NOT BE USED, COPIED OR AMENDED FOR ANY PURPOSE WHATSOEVER WITHOUT WRITTEN APPROVAL.

NOTES

1. THIS DRAWING IS COPYRIGHT. REFER TO DETAILS ABOVE.
2. THIS DRAWING IS ONLY TO BE USED FOR THE PURPOSES DESCRIBED IN THE STATUS BOX BELOW. WORK TO FIGURED DIMENSIONS ONLY, DO NOT SCALE.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS, DETAILS AND SPECIFICATIONS PERTAINING TO THE WORK DESCRIBED.
4. MATERIALS AND WORKMANSHIP SHALL COMPLY TO THE APPROPRIATE BRITISH STANDARDS AND CODES OF PRACTICE UNLESS OTHERWISE STATED.
5. THE ACTIVITIES REQUIRED TO CONSTRUCT THE WORK, SHOWN ON DRAWINGS CLEARLY MARKED FOR CONSTRUCTION, MAY BE SUBJECT TO THE PROVISIONS OF THE CONSTRUCTION (DESIGN AND MANAGEMENT) REGULATIONS 2015. THE CONTRACTOR AND CLIENT MUST ENSURE THAT THEY ARE ADEQUATELY CONVERSANT WITH THESE REGULATIONS AND THAT THE APPROPRIATE PROCEDURES REQUIRED UNDER THE REGULATIONS ARE OBSERVED AT ALL TIMES.
6. DESIGN RISK ASSESSMENT

A RISK ASSESSMENT RELATING TO POTENTIAL HAZARDS ASSOCIATED WITH THE CONSTRUCTION, OPERATION AND DEMOLITION OF THE WORK DESCRIBED WITHIN THIS DRAWING, IN SO FAR AS IT HAS BEEN DESIGNED BY NIJHUIS H2OK LTD, HAS BEEN UNDERTAKEN. RISKS SO IDENTIFIED HAVE BEEN ELIMINATED BY DESIGN WHEREVER PRACTICABLE. THE SITUATION WITH REGARD TO RESIDUAL RISKS IS AS FOLLOWS:

THE WORK IS AT AN EARLY PLANNING STAGE AND IS NOT SUFFICIENTLY ADVANCED TO ALLOW A MEANINGFUL ASSESSMENT OF RISKS TO BE UNDERTAKEN AT THIS TIME.

KEY

- SITE BOUNDARY
- SW SEWER (TO BE CONSTRUCTED PRIOR TO COMMENCEMENT OF ANY EARTHWORKS)
- PRIVATE CONVEYANCE TRENCH (TO BE CONSTRUCTED PRIOR TO COMMENCEMENT OF ANY EARTHWORKS)
- PROPOSED SURFACE WATER MANHOLE
- PROPOSED PRIVATE SURFACE WATER POLYPROPYLENE INSPECTION CHAMBER (475ø P.P.I.C.)
- OVERLAND FLOW ROUTES

NOTE:
A TEMPORARY BUND SILT CONTROL BARRIER SHOULD BE SET UP AROUND THE DOWNSTREAM PERIMETER OF THE SITE / PHASE PRIOR TO CARRYING OUT EARTH WORKS TO ENSURE RUN-OFF DOES NOT CARRY SILTS OR TOP SOIL MATERIAL OFF THE SITE.
POST INSTALLATION OF SILT FENCE THE CONVEYANCE TRENCH, SURFACE WATER SEWERS AND ALL OTHER SURFACE WATER INFRASTRUCTURE TO BE CONSTRUCTED PRIOR TO FURTHER WORKS.


31/08/17	HG	-	-	A	PRELIMINARY ISSUE
DATE:	DRWN:	CHKD:	APPR:	REV:	NOTES:
PROJECT MANAGER:-					HANNAH GRAHAM
ASSISTANT:-					-
DRAWN DATE:-					AUGUST 2017
SCALE & SHEET SIZE:-					1500@ A1

PRELIMINARY



- Waste to Value (AD/Biogas)
- Industrial Effluent Treatment
- Sewage Treatment
- Flood Risk Management/SUDS
- Design Consultancy
- Service and Maintenance

Nijhuis H2OK Ltd. | rh2ok@nijhuisindustries.com | www.nijhuisindustries.com/consultancy
Head Office: +44 (0)333 7000 007 |



CLIENT:
A & M ARCHITECTURAL PARTNERSHIP
LLP

PROJECT:
MILL RYTHE HOLIDAY PARK

DRAWING TITLE:
SURFACE WATER DRAINAGE

PROJECT No.	DRAWING No.	REV.
J-11713	3002	A