POPPY PAVING
69 Serpentine Road
Widley
Waterlooville
Hants
PO7 5EE
02392 354233
07521704810

Poppy Paving Ltd

PART OF WHYMARK SERVICES LTD
COUNCIL APPROVED
CHECKATRADE APPROVED,
MARSHALLS APPROVED

IAN WARD
20 WEDGEWOOD WAY
WATERLOOVILLE
PO8 8RW
07786 776764
3 / 10 / 2021

BLOCKPAVE DRIVE EXTENTION 65sqMETRES.

EXCAVATE GROUND AND INSTALL SOAKAWAY WITH PLASTIC CRATING AND GROUND PIPE TO GUTTERING DOWNPIPE AREA.
COVER WITH TERAM AND SHINGLE THEN SOIL/GRESS.
REMOVE OLD FENCE AND GATE AND REBUILD TO NEW AREA WITH NEW CONCRETE POSTS CONCRETE GRAVEL BOARDS AND PANNELS WHERE NEEDED
EXCAVATE WHERE NECESSARY TO A DEPTH OF 200mm AND LAY TERAM WEED CONTROLL FABRIC.
SUPPLY / INSTALL 7 METRES OF CONCRETE EDGINGS TO NEIGHBOURS FENCE LINE.
INFILL WITH 120mm OF TYPE 1 STONE AND COMPACTED TO LEVELS.
REMOVE OLD EDGINGS FROM EXCISTING DRIVE, JOIN ON AND LAY BRACKEN PAVING ON A 30mm SCREED BED OF SHARP SAND / WASHED GRIT COMPACTED.
BRUSH WITH KILN DRIED SAND AND COMPACT TO NEW LEVELS.

£9,700
ALL INCLUSIVE
WITH 5 YEAR GUARANTEE

LOOK FORWARD TO HEARING FROM YOU SOON

MANY THANKS