SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTES:
DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 1
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties.
- Proposed climbing plants to be trained up adjacent wall/ fence/pergola with galvanised wires and hook set 250mm apart with support canes removed prior to planting
- Proposed *Euonymus* hedge planting to be planted in a single row at 300mm centres
- Proposed *Viburnum tinus 'Eve Price'* hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed native mix to be planted in groups of 5-7no. of each species and as above
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Existing grassland to be retained, where there are patches, seed with EG10 Tussock grass seed mix as supplied by Emorsgate and sown at 5 grams per msq, or similar and approved
- Small areas of angular chipping
- Cut lines
- Planting Schedule on Sheet 2

Rev	Date	Details	Drawn

ACD ENVIRONMENTAL

HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane, Malmesbury, SN16 0ES
Tel: 01666 825646

4 & 5 The Old Mill, Fry's Yard, Bridge Street, Godalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

Taylor Wimpey

scheme: Fathom's Reach Hayling Island
client: Taylor Wimpey
drawing: Landscape Proposals
date: Nov 2021
scale: 1:200@A1
drawing no: TWSC23569 11 Sheet 2
drawn: LS checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Planting Schedule

Trees

Species Name	Girth	Height	Density	Specification	No.
Arbutus unedo		1.5-1.8m	Counted	RB	2 -
Ilex aquifolium		40-60cm	0.5Ctr	BR	51 -
Salix caprea		40-60cm	0.5Ctr	BR	105 -
Acer campestre		60-80cm	0.5Ctr	C	51 -
Prunus spinosa		60-80cm	0.5Ctr	BR	105 -
Crataegus monogyna		60-80cm	0.5Ctr	C	105 -
Carpinus betulus 'lucas'	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	25 -
Acer campestre 'Elsrijk'	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	3 -
Carpinus betulus	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	3 -
Betula utilis jacquemontii	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	10 -
Salix caprea	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	1 -
Acer campestre	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	2 -
Magnolia grandiflora 'Galissonière'	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	1 -
Acer rubrum 'October Glory'	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	5 -
Ulmus 'New Horizon'	10-12cm	350-400cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	1 -
Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	2 -
Alnus glutinosa 'Laciniata'	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	2 -
Betula pubescens	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	1 -

Conifers

Species Name	Height	Pot Size	Specification	Density	No.
Juniperus virginiana 'Grey Owl'			Bushy	4/m²	43 -

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Abelia grandiflora 'Compacta'	30-40cm	5L	Bushy :C	4/m²	146 -
Amelanchier lamarckii	175-200cm		Bushy :C	Counted	4 -
Camellia 'Black Lace'	30-40cm	3L	Bushy	2/m²	14 -
Camellia japonica 'Jupiter'	40-60cm		C	Counted	1 -
Carpinus betulus	30-40cm	5-7.5L	Bushy	0.5Ctr Double Staggered at 0.3m offset	346 -
Cornus alba 'Sibirica'	60-80cm	5L	Bushy	4/m²	12 -
Cornus alba 'Sibirica'	40-60cm	5L	Bushy	0.5Ctr	43 -
Cornus sanguinea	40-60cm	5L	Branched	0.5Ctr	43 -
Crataegus monogyna	30-40cm	5-7.5L	Bushy	0.5Ctr Double Staggered at 0.3m offset	85 -
Cytisus 'Lena'	60-80cm	15L		Counted	1 -
Euonymus fortunei 'Emerald Gaiety'	30-40cm	5L	Bushy	4/m²	191 -
Euonymus japonicus 'Jean Hugues'	30-40cm	5-7.5L	Bushy	0.3Ctr	81 -
Fushia 'Margret'	15-20cm	3L	Bushy	5/m²	25 -
Griselinia littoralis	30-40cm	5-7.5L	Bushy	0.5Ctr Double Staggered at 0.3m offset	388 -
Hebe albicans	30-40cm	5L	Bushy	4/m²	15 -
Hypericum 'Hidcote'	30-40cm	3L	Bushy	4/m²	104 -
Magnolia 'Betty'	175-200cm		Bushy :C	Counted	4 -
Mahonia aquifolium 'Apollo'	40-60cm	5L	Bushy :C	2/m²	27 -
Myrtus communis tarentina	30-40cm	3L	Bushy	4/m²	9 -
Osmanthus burkwoodii	30-40cm	3L	Bushy	4/m²	57 -
Philadelphus 'Manteau d'Hermine'	40-60cm	5L-7.5L	Bushy	4/m²	61 -
Photinia fraseri 'Little Red Robin'	30-40cm	5L	Bushy	4/m²	20 -
Photinia fraseri 'Red Robin'	40-60cm	5L	Bushy	0.5Ctr	43 -
Pieris 'Flaming Silver'	30-40cm	3L	Bushy	4/m²	78 -
Pittosporum tenuifol. 'Irene Patterson'	40-60cm	5L	Bushy	0.5Ctr	43 -
Pittosporum tenuifolium 'Golf Ball'	30-40cm	5L	Bushy	4/m²	95 -
Prunus laurocerasus	30-40cm	5-7.5L	Bushy	0.5Ctr Double Staggered at 0.3m offset	132 -
Salvia greggii 'Peach'	30-40cm	3L	Bushy	4/m²	51 -
Salvia officinalis 'Berggarten'	30-40cm	3L	Bushy	4/m²	91 -
Sambucus nigra	60-80cm		BR	0.5Ctr	51 -
Sarcococca ruscifolia	40-60cm	5L	Bushy	4/m²	128 -
Skimmia japonica 'Rubella'	30-40cm	3L	Bushy	4/m²	145 -
Viburnum davidii	30-40cm	3L	Bushy	4/m²	62 -
Viburnum opulus	60-80cm		BR	0.5Ctr	51 -
Viburnum opulus 'Compactum'	30-40cm	3L	Bushy	4/m²	21 -
Viburnum tinus 'Eve Price'	30-40cm	5-7.5L	Bushy	0.5Ctr Double Staggered at 0.3m offset	1128 -
Weigela 'Mont Blanc'	40-60cm	5L	Bushy	4/m²	14 -

Climbers

Species Name	Height	Pot Size	Specification	Density	No.
Jasminum officinale grandiflora	100-150cm	10L	Several Shoots :5 brks :3xCaned	Counted	4 -