HARRIS SURVEYS LEGEND

LAND SURVEY ABBREVIATIONS		BUILDING SURVEY ABBREVIATIONS	
AV	Air Valve	CEIL	Ceiling HT
B	Bollard	CEIL/C	Floor to Ceiling HT
BB	Bellano Beacon	AH	Arch HT
Bin	Litter Bin	BH	Beam HT
BLT	Basement Light	C 1.20	Floor to CSI HT
BP	Box Pipe	CSI 1.80	CSI to Head HT
BR	Bus Shelter	CB	Cupboard
B/S	Brick Setts	F/C	Floor to Ceiling
BT	British Telecom MH	HT	Height
BTB	British Telecom Box	RAD	Radiator
BTMH	British Telecom MH	S	Sink
BTP	British Telecom Post	SCU	Single Ceiling Up
C	Kerb Inlet	SL	Single Light
CPS	Concrete Paving Slabs	SP	Sprinkler HT
CTV	Cable Television	WHB	Wash Hand Basin
DP	Down Pipe		
DK	Drop Kerb		LEVEL ABBREVIATIONS
ECB	Electricity Cable Box	BL	Bed Level
ELCP	Electricity Cable Pit	CL	Cover Level
EP	Electricity Pole	EL	Eave Level
ER	Earthing Rod	FL	Floor Level
FB	Flower Bed	IL	Invert Level
FP	Finger Post Sign	RL	Road Level
FS	Flag Staff	RFL	Roof Level
FW	Foul Water	SL	Sump Level
G	Gully	SFL	Soffet Level
GV	Gas Valve	WL	Water Level
H	Hydrant		
IC	Inspection Cover		FENCE ABBREVIATIONS
KO	Kerb Outlet	BWF	Barbed Wire Fence
LB	Letter Box	CBF	Closed Board Fence
LP	Lamp Post	CIF	Corrugated Iron Fence
MH	Manhole	CLF	Chain Link Fence
Mkr	Marker	CPF	Chestnut Paling Fence
MS	Mile Stone	IRF	Iron Railing Fence
MYMH	Mercury Manhole	IWF	Interwoven Fence
NB	Notice Board	LLF	Larch Lap Fence
NP	Number Plate	OWF	Open Wood Fence
P	Post	PKF	Picket Fence
PM	Parking Meter	PRF	Post & Rail Fence
RE	Reading Eye	PWF	Post & Wire Fence
RP	Reflector Post	TLS	Trellis
RS	Road Sign		
RTB	Round Top Bollard		TREE ABBREVIATIONS
RWP	Rain Water Pipe	ALD	Alder
SC	Stop Cock	BCH	Beech
SP	Sign Post	CHY	Cherry
SPS	Stone Paving Slabs	CYP	Cypress
SV	Stop Valve	DEC	Deciduous
SW	Soil Vent	EVN	Evergreen
⚓	Survey Station	HAW	Hawthorn
Top	Stand Pipe	HCN	Horse Chestnut
TCB	Telephone Call Box	HOL	Holly
TL	Traffic Light	HRN	Hornbeam
TMC	Traffic Mast	LIM	Lime / Plane
TP	Telegraph Pole	POP	Poplar
TPS	Tactile Paving Slabs	ROD	Rhododendron
UTL	Unable to Lift	RWN	Rowan
VP	Vent Pipe	SBI	Silver Birch
WC	Water Cock IC	SWN	Sweet Chestnut
WM	Water Meter	SPU	Species Unknown
WO	Wash Out	WIL	Willow
WT	Water Trough	WNT	Walnut

Banking — Hedges & Vegetation — BUSHES HT 4.00

Gate

Building — HEDGE HT 4.00

Glass Roofed

Wall — 0.23 WALL HT 2.0 — Trees

Retaining Wall — RTW — Species Ø Size/Height

Sloping Masonry — SLW

Contours — 52.50 — Ordnance Survey & Temporary Benchmarks — OSBM 6.77m — TBM 5.35m

All underground services information shown on this plan cannot be guaranteed and users should satisfy themselves of the type, size and route before commencing work on site. Harris Surveys also cannot be held responsible for services or detail hidden or obscured at time of survey.

Tree species and sizes shown on this plan cannot be guaranteed and if critical should be verified by an arboriculturist. Tree spreads are averaged and tree heights are approximate for all other purposes.

This plan has been produced for the client detailed below to an agreed specification, and defines the limit of Harris Surveys Ltd's liability.

NORTH

SCALE 1 : 750 — 0m — 10m — 20m

REV	DATE	DESCRIPTION	BY

REVISIONS

e-mail: mail@Harrissurveys.co.uk

HARRIS SURVEYS LTD

CHEQUERS
WINCHESTER ROAD
WALTHAM CHASE
SOUTHAMPTON
HAMPSHIRE SO32 2LG
TEL: 01489 894394
FAX 01489 894394

Project Title:	Land at Cabbagefield Row off Calshot Road, Havant Hampshire		
Drawing Title:	Topographical Survey		
Client	Portsmouth City Council		
Dwg.No:	19230	Scale	A1 1:750
Drawn	SU	Date	April 2019

Level Note

All levels and grid based on Ordnance Survey Datum by GPS.