BARTONS ROAD

EASTLEIGH ROAD

B2148 HORNDEAN ROAD

LODGE HOUSE

COACH HOUSE

STABLES

SOUTHLEIGH PARK HOUSE

COURTYARD


LAWN

72m FIRE HOSE LENGTH EXCEEDS 45m PERMISSIBLE LENGTH AS PRESCRIBED IN B REGS PART B

45m FIRE HOSE LENGTH AS PRESCRIBED IN BUILDING REGS PART B

47m FIRE HOSE LENGTH EXCEEDS 45m PERMISSIBLE LENGTH AS PRESCRIBED IN B REGS PART B

58m FIRE HOSE LENGTH EXCEEDS 45m PERMISSIBLE LENGTH AS PRESCRIBED IN B REGS PART B



Dennis Sabre Fire Tender (LWB)

Overall Length	7.700m
Overall Width	2.430m
Overall Body Height	3.515m
Min Body Ground Clearance	0.397m
Track Width	2.380m
Lock to lock time	5.00s
Kerb to Kerb Turning Radius	7.400m

REV. No.	DATE	DESCRIPTION	DRAWN	CHECKED
P2	26.11.21	Second Issue	KTG	KTG
P1	04.05.21	First Issue	KTG	KTG

Client: BARGATE HOMES

Project: Southleigh Park
Eastleigh Road

Title: Fire appliance vehicle tracking layout

MJA CONSULTING
CIVIL & STRUCTURAL ENGINEERS
Ipsum Court, 24 The Quadrant,
Abingdon Science Park, Abingdon
Oxon, OX14 3YS
Tel: 01235 555173
Email: mail@mjaconsulting.co.uk

Scale:	Status:
1@500@A1	PRELIMINARY

Drawn:	Project Engineer	MJA Project No:	Date:
KTG	KTG	6281	26/11/2021

Drawing Number: 6281-MJA-SW-XX-DR-C-501 Rev: P2

© This drawing is the copyright of Michael A Jennings Associates Limited and may not be copied, altered or reproduced in any way without their permission.