## LEGEND

- RISING MAIN
- S1 — SURFACE WATER MANHOLE (SWMH)/ INSPECTION CHAMBER / ACCESS CHAMBER (SEE SCHEDULE FOR DETAILS).
- 100mm Dia. PVCu. SN4 STORM WATER DRAIN (U.N.O.)
- RWP — RAIN WATER DOWNPIPE (LOCATION AS ARCHITECTS DRGS).
- RE — RODDING EYE.
- FC PDT — CHARCON PERMAVOID DISTRIBUTION TANK(PDT) & FILTER CHAMBER(FC)
- FIN DRAIN
- F1 — FOUL WATER MANHOLE (FWMH)/ INSPECTION CHAMBER / ACCESS CHAMBER (SEE SCHEDULE FOR DETAILS).
- 100mm Dia. PVCu. SN4 FOUL WATER DRAIN (U.N.O.)
- SVP/SS/CG — SOIL VENT PIPE / STUB STACK/ CAPPED GULLEY (LOCATION AS ARCHITECTS DRGS).
- AAV — AIR ADMITTANCE VALVE
- FG — FOUL WATER FLOOR GULLY. (RODDABLE & AIRTIGHT SEAL IF CAPPED FOR FUTURE USE)
- SITE BOUNDARY
- ??.?? + — PROPOSED LEVEL.
- ??.?? + — EXISTING GROUND LEVEL.
- IL ?.?? — INVERT LEVEL
- ACCESS ROAD PERMEABLE BLOCK PAVING 350 SUB-BASE
- ACCESS ROAD PERMEABLE BLOCK PAVING 550 SUB-BASE
- PERMEABLE BLOCK PAVING PARKING AREA 350 SUB-BASE.
- PERMEABLE BLOCK PAVING 600 SUB-BASE.
- ROOT PROTECTION AREA
- ACCESS ROAD TO FOUL WATER PUMPING STATION
- FOOTWAY
- CHECK DAM
- TREE ROOT PROTECTION ZONE.

BLENDWORTH CRESCENT

FOUL MANHOLE
REF: 4402
CL: 12.36
IL: 11.16

FOR LEVELS TO ACCESS ROAD SEE DRAWINGS PMC238-510 & 512

EXISTING 525ø SW SEWER

HYDROBRAKE MANHOLE DISCHARGE 6.5L/S

HYDROBRAKE MANHOLE DISCHARGE 2L/S

SADDLE CONNECTION TO EXISTING SEWER

STORMWATER ATTENUATION TANK 2 No. 2m WIDE x 1m x 10m LONG BOX CULVERT

TYPE 3 ADOPTABLE FOUL WATER PUMPING STATION TO SPECIALIST DESIGN.

INLET MANHOLE
WET WELL
VALVE CHAMBER
KIOSK

CHECK SCALE 1:250@A1 / 1:500@A3

0m 10 20 30 40 50 60 CHECK SCALE 1:1@A1 / 1:2@A3

### NOTES

© This drawing is the copyright of ARCH Associates Limited. It may not be copied, altered or reproduced without their written authority. This drawing must not be scaled. IF IN DOUBT ASK.

### GENERAL NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS AND SPECIALISTS DRAWINGS AND DETAILS.
2. ALL FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.
3. ANY DISCREPANCIES BETWEEN THIS DRAWING AND OTHER INFORMATION IS TO BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF THE WORKS ON SITE.
4. THE MAIN CONTRACTOR SHALL BE RESPONSIBLE FOR THE SETTING OUT AND ACCURACY OF ALL DIMENSIONS.
5. THE CONTRACTOR IS TO ENSURE THE STABILITY AND STRUCTURAL INTEGRITY OF THE EXISTING PROPERTY AT ALL TIMES DURING WORKS AND IS TO BE RESPONSIBLE FOR ALL PROPPING AND SHORING AS REQUIRED.
6. MAIN CONTRACTOR TO PROVIDE AND FIX SUITABLE BRACING AND PROPPING FOR ALL ELEMENTS IN THE TEMPORARY CONDITION DURING CONSTRUCTION STAGE, SUCH AS TO ENSURE STRUCTURE STABILITY AT ALL TIMES.
7. IT IS THE CONTRACTORS SOLE RESPONSIBILITY FOR ASCERTAINING SAFE DISPOSAL OF ANY OFF-SITE EXCAVATED SPOIL. NO CLAIM RESULTING FROM ABNORMAL TIP REQUIREMENTS WILL BE ENTERTAINED.

### DRAINAGE

1. ALL MATERIALS AND WORKMANSHIP TO 'SEWERS FOR ADOPTION, 7th EDITION'
2. ALL MATERIALS AND WORKMANSHIP TO COMPLY WITH BS EN 752-1: 1996
3. WHEN USING VITRIFIED CLAY PIPEWORK WITH FLEXIBLE JOINTS, SUPERSTRENGTH SHALL BE USED. ALL ADOPTABLE WORKS SHALL USE V.C PIPEWORK. FOR NON-ADOPTED SYSTEM PVCU-SN4 CLASS PIPEWORK AND FITTINGS MAY BE SUBSTITUTED.
4. CONCRETE ENCASEMENT, MINIMUM 150 BED AND HAUNCH, TO BE USED ON PIPEWORK UNDER ROADS WITH LESS THAN 1200 COVER TO CROWN.
5. UNLESS OTHERWISE STATED, ALL PIPEWORK TO BE BEDDED AND SURROUNDED IN 10mm SINGLE SIZE AGGREGATE UP TO 450mm DIAMETER. FOR LARGER PIPEWORK, 20mm SHALL BE USED.
6. REFER TO MANHOLE SCHEDULE FOR SIZES, COVERS ETC.
7. ALL MATERIALS TO COMPLY WITH THE RELEVANT BS-EN, LATEST EDITION, FOR PIPEWORK AND FITTINGS.
8. UPON COMPLETION, ALL WORKS TO BE THOROUGHLY CLEANED BY FLUSHING.

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH DRAWING No. PMC238-551,552 & 553

COLOURED DRAWING
REQUEST A COLOURED COPY IF THIS STAMP IS NOT RED

### CDM REGULATIONS 2007

RUSHBY BREWSTER ASSOCIATES HAVE CONSIDERED AND, WHERE REASONABLY PRACTICABLE, AVOIDED FORESEEABLE RISKS IN THE PREPARATION OF THE DESIGN SHOWN ON THIS AND RELATED DRAWINGS. SIGNIFICANT RISKS WHICH REMAIN AND ASSOCIATED CONTROL MEASURES ARE IDENTIFIED BELOW AND SHOULD BE GIVEN PARTICULAR ATTENTION BY THE MAIN CONTRACTOR ON SITE.

| ACTIVITY | HAZARD | CONTROL |
|---|---|---|
| | | |

NOTE: THE ABOVE ASSESSMENT RECORDS ONLY THOSE ELEMENTS CONSIDERED UNUSUAL, DIFFICULT TO MANAGE OR OUTSIDE OF THE ANTICIPATED EXPERTISE OF A COMPETENT CONTRACTOR

| Revision | Date | Description | By |
|---|---|---|---|
| P2 | 25.11.16 | PLOTS 11-15 FFL AMENDED. | PJM |
| P1 | 23.11.16 | PRELIMINARY ISSUE FOR COMMENT | PJM |

ARCH ASSOCIATES
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
The Town House, St. George's Square, Bishops Waltham, Southampton, Hampshire, SO32 1AF.
Telephone: 01489 890004 Email: admin@archassociates.co.uk Web: www.archassociates.co.uk.

Client: PMC CONSTRUCTION
Architect: KENN SCADDAN ASSOCIATES LTD.
Project Title: BLENDWORTH CRESCENT, LEIGH PARK.
Drawing Title: DRAINAGE & EXTERNAL WORKS LAYOUT

| Project No. | Drawing No. | Revision | Scale | Paper Size | Date | Drawn by | Chkd. by |
|---|---|---|---|---|---|---|---|
| PMC238 | 501 | P2 | 1:250 | A1 | NOV.2016 | PJM | AWR |