Connect existing storm drain from No. 20 Barncroft Way into proposed drainage serving development via inspection chamber positioned on edge of footway

Existing Private 225 dia

Junction subject to S278 Agreement together with other offsite works. Refr to drawing number ES1143-278-01 for details

600mm deep inspection chamber to serve sales cabin

Temporary Sales Cabin

Connect into sewer on line connection fr Barncroft Wa above manho level. Connec to S106 Appr Southern Wa

S9 250dia

Street Lighting Specification:

Proposed 6 Meter nominal height post top tumblar steel lighting column, complete with post top mounted lantern. (WRTL Libra 24W PL-L luminaire with 5 degree tilt).
Column colour: Galvinised (no paint)
Swith regime: Dimmed (optical setting)

Rev.	Date	Details	Initials
A	07.07.15	Initial issue	MA

Drawing Status
PRELIMINARY

Project
Barncroft Way
Havant

Client
Bellway Homes

ESCHER · SILVERMAN
Civil & Structural Consulting Engineers
The Stables, Lone Barn Studios, Stanbridge Lane, Romsey, Hampshire. SO51 0HE.
Tel: 01794 521213. Fax: 01794 522195. email: mail@eschers.co.uk
www.eschersilverman.co.uk

Drawing Title
Engineering Details
Street Lighting Layout

Drawn	Checked	Scales	Paper Size	Date
MA	KAM	1:250	A2	07.15

Job No.	Drawing No.	Revision
ES1423	510–06	A

This drawing is the copyright of Escher Silverman and may not be copied, altered or reproduced in any form or passed to a third party without the consent of Escher Silverman. Do not scale from this drawing, use figured dimensions only.
Dimensions should be checked and verified on site and any discrepancies should be reported to Escher Silverman as soon as possible.