



NOTES

Soil Landscaping:

- All plants, workmanship and materials to comply with relevant British Standards and Codes of Practice.
- Landscaping operations shall be in accordance with BS 4428 and any imported soil shall be to BS 3882.
- All trees and shrubs to be retained should be protected during construction. All trees to be protected surrounded by a temporary fence. The fence should be positioned and retained at a distance from the trunk equal to the spread of the crown of the tree and at least 2.4m high. Tree protection fencing to line with BS 5837 'Trees in relation to construction'.
- All planting borders to be prepared before planting, incorporating organic chicken peat fertiliser.
- A 75mm thick layer of mulch should be spread over all planting borders to retain moisture and reduce competition from weeds. This will help to encourage rapid plant establishment.
- Topsoil should be provided to the following minimum depths: Grass - 150mm, Shrubs - 300mm, Trees - 750mm
- All planting borders to be filled with topsoil.
- All trees will be secured to suitable stakes relevant to the size and maturity of trees when planted. All trees should be planted with a suitable irrigation tube to ensure water is directed straight to the root of the tree.
- Tree planting close to existing or new walls, fences and hard paved surfaces shall avoid root directors or other measures to planting pits to facilitate sound growth and development and avoid root disturbance or damage to walls or footings.
- Tree positions to be checked on site against final alignment of drains and utility services and adjusted if required.

Maintenance:

- All planting borders and grassed / lawn areas to be have a regular watering programme until they have established, especially during periods of dry weather.
- Initial maintenance of landscaping should be carried out during fortnightly maintenance visits for the first six months after landscaping and construction has been completed.
- The areas beneath all planting areas should be kept weed free until the plants have established.
- Once plants have established, regular attention to the planting borders will still be necessary to ensure plants are maintained in a healthy state. This should include a trim to shape and top up of mulch every year in the autumn or spring.
- Light pruning of shrubs, to retain their shape should be carried out after flowering. Severe pruning should only be carried out during the winter months. Dead, diseased or damaged stems should be removed immediately.
- Regular monitoring of tree stakes and ties will be necessary to ensure that damage does not occur to the tree.
- Any damaged or broken stakes should be replaced immediately.
- All existing mature trees should be checked every three to five years for signs of decay and broken limbs due to storm damage and disease.
- New plants which do or fail to establish within 5 years of planting shall be replaced with plants of the same species

E	Drive revised, planting revised	mw 06.10.15	
D	Plan updated	mw 03.09.15	
C	Plan revised	mw 14.08.15	
B	House rotated	mw 04.08.15	
A	Layout revised	mw 30.07.15	
-	Original Issue		
Rev		Down / Date	Chk / Date
This drawing is copyright and must not be disclosed to third parties without permission Scaled dimensions are not to be used for construction			

4 Queensgate
Queens Road
Fareham
Hampshire
PO16 0NW

Tel: 01329 288911
Fax: 01329 221913
E-mail: admin@m2architecture.com

PROJECT

Proposed New Dwelling
7 North Close
Havant

CLIENT

S Bailey & F Askew

DRAWING TITLE

Site Plan

m2
architecture
architectural technologists

PROJECT NO.	DRAWING NO.	REV.	SCALE
15012	402	E	1:200

HAVANT BOROUGH
COUNCIL
- 9 OCT 2015
RECEIVED