

Our Ref: 22397/EB/PB/500Q

12th May 2015

FAO Mr Alwyn DeSouza
D & K Contracting Services Ltd
44 The Hundred
Romsey
Hampshire
SO51 8BX

Dear Alwyn,

Re: Ben Hall, Hambledon Road, Waterloooville, PO7 6XB

Further to your email dated 29/04/15 and our subsequent conversation we are pleased to quote for the following work.

1. Construct new dropped kerb including 2 x 6m wide crossing construction.
 - (a) Erect traffic control
 - (b) Remove & cart away existing hedgerow, n/e 6m wide
 - (c) Excavate to reduce dig n/e 32m² x 375mm deep (we have allowed 5m from road edge)
 - (d) Supply, lay & roll 225mm 6F2 sub-base n/e 32m²
 - (e) Supply and lay 6"x5" Fig2a kerbs to bellmouth n/e 18 lin m
 - (f) Supply and lay 150mm/20mm base course tarmac n/e 32m²
 - (g) Supply and lay 25mm/6mm wearing course tarmac n/e 32m²
 - (h) Remove all traffic control, sweep up and leave area clean & tidy

We have not allowed for any road opening applications or fees but could quote if you so wish.

We have allowed to carry out all the work in one single visit but be aware the wearing course may get damaged during construction works.

As you can appreciate details supplied are very sketchy and we hope we have interpreted your requirements correctly.