



32a Park Crescent
Emsworth

Mr G Willard

Tree Retentions & Removals Plan &
Tree Protection Plan Combined

project

client

title

drawn: bjh

scale: 1:50 @ A3


job: 0749

date: October 2014

Penne Haverston

3 Woodstock Cottages - South Harting - West Sussex - GU31 3PL
tel: 01750 852827 - mobile: 07769 520481 - email: barrett.haverston@btinternet.com - VAT Reg No. 881 25065 115

- = Tree to be retained and fully protected during development.
 - = The setting out positions for the 'Boxed Hoarding' form of Protective Fencing in accordance with BS5837:2012
- recommendations - Section 6.2**
- = The area of the original concrete floor that will be broken out and replaced with a new 300mm deep slab.
 - = The area of the original concrete floor which will be retained for as long as possible to act as ground protection and scaffold support which will ultimately be broken out and removed and then replaced with topsoil and planting.
 - = This shaded area will need to be covered with ground protection in accordance with BS5837:2012 - Section 6.2.3.3 b) to facilitate scaffold erection and vehicular movements around the build.
 - = This shaded area will be retained for as long as possible to act as ground protection and scaffold support which will ultimately be broken out and removed and then replaced with topsoil and planting.
 - = This area will initially need to be cleaned of all vegetation and then protected in accordance with BS5837:2012 - Section 6.2.3.3 b) to facilitate scaffold erection and vehicular movements around the build - ultimately it will be lifted and the area raked level before a geotextile membrane is laid with pegged board edging and then backfilled with small diameter washed gravel.



CLIENT:	Mrs and Mrs Willard - 30a Orchard Cottage Park Crescent Emsworth	DESCRIPTION:	Amended Position of Double Garage over Existing Footprint
PROJECT:	Replace Existing Garage with new Double Garage	SCALE:	1:50
DATE:	October 2014 - Revision 'A' 23.10.2014 Re-siting of Double Garage	REVISION:	DRAWING No: 13226/ 5

DRAWING MUST BE READ WITH NOTES. DIMENSIONS AND DETAILS TO BE CHECKED ON SITE BEFORE PRICING AND CONSTRUCTION

ADS
DESIGN
SERVICE

© COPYRIGHT RESERVED