



Root Rain Metro tree pit irrigation system as supplied by Green-Tech Industries or similar and approved

Pressure impregnated softwood stakes driven into ground with a minimum of 400mm below ground

The tree should be positioned in the hole so that the top of the rootball is level with the surrounding ground level

Backfilled material to be either originally excavated soil or imported soil to BS3882:2007. If judged to be of poor quality then suitable organic matter must be added.

To be backfilled in layers of 300mm, each layer to be lightly firmed in with heel, to exclude large voids

All components as supplied from GreenBlue Urban or similar and approved

Wire cage to be left on, and folded back/cut away around stem, if rootballed.

Rubber belting and spacer block attached with galvanised nails as supplied from Green-Tech Industries or similar and approved with tie height 1/3 stem height

Good quality mulch to be applied to a minimum of 75mm depth, and no more than 150mm, leaving the stem base clear and mulch

Tree pit to be no deeper than rootball, 600mm larger than rootball on all sides, and should be square