

Schedule of **EXTERNAL WORKS** to be carried out by **TESCO CONTRACTOR**

- B1

STAINLESS STEEL RAIL-Road bollards to be supplied and installed by TESCO APPOINTED CONTRACTOR. SEE B1 CENTRE TO PROVIDE 1200MM CLEAR ACCESS WITHIN FOR 2000mm REQUIREMENTS AND NOT TO EXCEED 1400MM CENTRE FOR RAIL-Road PROTECTION.
- DG 01

DEVELOPER TO PREPARE OPENINGS AND INSTALL FULL HEIGHT SHOP FRONTS, NEW SHOP FRONTS AND DOOR. SHOP FRONTS AND BI-PARTING DOORS TO BE PROVIDED AND INSTALLED BY DEVELOPER.
- WG 02

DEVELOPER TO INSTALL GLAZED ALUMINIUM FRAMED WINDOWS INTO 880x2047mm NEW OPENING FORMED AS PART OF SHELL WORKS. FRAMES TO BE PVC ALUMINIUM FINISHED DUSTY GREY TO RAL7037.
- DG 02

DEVELOPER TO FORM NEW 1210x4010mm OPENING AND TO INSTALL NEW STEEL ACCESS ESCAPE DOORS. DOOR TO BE PAINT FINISHED, COLOUR DUSTY GREY TO RAL7037. TESCO APPOINTED ARCHITECT TO OBTAIN NECESSARY PLANNING APPROVAL.
- DG 04

1020x4010mm OPENING TO BE PREPARED TO ACCOMMODATE ATM ACCESS DOOR (REFERENCED SIGN). PROVIDE OPENING SECURE AND HOMESIDE READY FOR INSTALLATION OF DOOR. DOOR TO BE PROVIDED AND INSTALLED BY TESCO APPOINTED CONTRACTOR.
- 1/2

SATELLITE DISH TO BE SUPPLIED AND FIXED BY TESCO APPOINTED CONTRACTOR TO EXISTING WALL IN LOCATION TO BE AGREED WITH LANDLORD. POSITION SHOWN INDICATING AS RECEPTION CHECK FOR AREA TO BE PERFORMED. SATELLITE DISHES MUST BE SOUTH FACING WITH A CLEAR LINE OF SITE.

External Works (Public Areas)

TESCO APPOINTED CONTRACTOR TO DEMARC PRIVACY/SECURE STANDING ZONE IN FRONT OF ATM UNIT.

External Works (Service Areas)

CONDENSER TO BE SUPPLIED AND INSTALLED BY TESCO APPOINTED CONTRACTOR LOCATED OUTDOOR CONCRETE PAD STANDING AS PART OF SHELL WORKS. CONDENSER TO BE A 118x410x485mm TWIN FAN FLAT BED OPERATING AT 100W AT 1000V DRAINING AND 200W AT 1000V DRAINING.

210x WALL MOUNTED A.C. UNITS SUPPLIED AND INSTALLED BY TESCO APPOINTED CONTRACTOR. AC UNITS TO SUPPLY SALES AREA AND ARE 1750x700x80mm HIGH. 100W OPERATING AT 1000V AT 1000V DRAINING.

110x WALL MOUNTED A.C. UNIT SUPPLIED AND INSTALLED BY TESCO APPOINTED CONTRACTOR. AC UNIT TO SUPPLY CASH OFFICE AND IS 1700x500x80mm HIGH. CASH OFFICE AC UNIT OPERATING AT 100W AT 1000V DRAINING.

UNIT TO BE AGREED AND/OR SALES AREA ACT WHERE WITHIN BUSINESS CHECK APPLY TESCO APPOINTED CONTRACTOR TO PROVIDE 1.8m HIGH CLOSE BOARDED TIMBER SERVICE YARD ACCESS GATES TO BE PROVIDED AND INSTALLED AS PER DETAILED DRAWING 4841LUX.

TESCO APPOINTED CONTRACTOR TO PROVIDE 1.8m HIGH CLOSE BOARDED TIMBER FENCE TO PERIMETER OF BIN STORE TO BE PROVIDED AS PER DETAILED DRAWING 4841LUX.

PROPOSED 150x100mm VENT AXIA FAN TO PROVIDE EXTRACT FROM STAFF ROOM TO BE SUPPLIED AND INSTALLED BY TESCO APPOINTED CONTRACTOR.

PROPOSED 150x100mm VENT AXIA FAN TO PROVIDE EXTRACT FROM TOILETS.

PROPOSED 300x200mm VENT AXIA FAN TO PROVIDE EXTRACT FROM BASE OFF COVER TO BE SUPPLIED AND INSTALLED BY TESCO APPOINTED CONTRACTOR.

Proposed West Elevation

Proposed North Elevation from Lavender Road

Proposed East Elevation from Frendstaple Road

Proposed South Elevation from

PROPOSED ELEVATIONS 1:100 @ A1

1:100 Scale A1 Sheet

C 02.05.13 External A.C. units moved, external steps amended.
B 04.04.13 Updated to BC recommendations
A 27.03.13 Shopfronts Amended

Revision:
0 1 2 3 4 5
bar in meters 1:200 @ A3
bar in meters 1:100 @ A1

0 10 20 30 40
title sheet scale bar in mm 1:2 @ A3
title sheet scale bar in mm 1:1 @ A1

Office 7, Gateway 1000
Arlington Business Park
Whittle Way
Stevenage
Hertfordshire
SG1 2FP

t: 01438 749400
f: 01438 749591

55 Newton Street
Manchester
M1 1ET

t: 01612286020
f: 01613360536
e: archerarchitects.co.uk
www.archerarchitects.co.uk

archer
architects

TESCO express

Project:
**LAVENDER ROAD
WATERLOOVILLE**

Drawing Title:
**FOR CONSTRUCTION
PROPOSED ELEVATIONS**

Scale:	Date:	Drawn:	Checked:
1:100@A1	04.04.13	JM	
Project No:	Drawing No:	Revision:	
4847	(C)203	C	