

Paving.
Marshall's saxon
Buff Paving



Gravel Garvel
to New car Park
area to match
existing surface
treatments.



NewTree/Hedge Scedule Species

Planting	Size	Girth/Height
T1	Flowering Cherry (Prunus spp)	12-14cm (mature Height 10-15m)
T2	Common Yew (Taxus Baccata)	1.2-1.5m(mature Height 10-15m)
T3	Common Yew (Taxus Baccata)	1.2-1.5m(mature Height 10-15m)
T4	Myrobalan Plum(Prunus cerasifera)	12-14cm (mature Height 10-15m)
T5	Common Beach (Fagus sylvatica)	10-12cm (Mature height 15-20m)
T6	Common Beach (Fagus sylvatica)	10-12cm (Mature height 15-20m)
T7	Variegated Norway maple(acer plataniodes)	10-12cm (Mature height 20 m)
T8	Pyris nivalis	12-14cm (mature height 10-15m)
T9	Pyris nivalis	12-14cm (mature height 10-15m)
T10	Common Yew (Taxus Baccata)	1.2-1.5m(mature Height 10-15m)
S1	Hazel Hedging (Corylus avellana)	1-2cm (mature height 10-15m)

Note hedging to be planted at 600-900mm in double staggered row at 500mm centres.

Hard Landscaping;The North elevation of the new building will have a small amount of paving adjacent to the doors; on a terrace overlooking the small garden. This area is indicated on the adjacent drawing and will be paved with Marshall's Saxon Buff paving.

The existing hard surfaces are a combination of tarmac and tarmac with gravel topping these areas as indicated on the adjacent plan will not be affected by the implementation of this proposal.

The new car park will be a Gravel surface. comprised with;
Plastic reinforcement grid on
Geotextile on
Compacted sub base on
Geogrid.

To provide both a permeable surface and protection to any adjacent tree roots.

Soft Landscaping;Apart from the formation of new levels where indicated on Plan 210 and 212 there will be no alterations to soft landscaping. Area affected by and adjacent to the construction works will be returned to grassland as per existing.

Fences;There are no plans for the imposition of new fences or other boundary treatment as part of the scope of these works.

Trees and Hedges ;New tree planitng is identified on this plan , all other information pertinent to trees is on CBA tress plans schedules and information. The tree have been chosen to replace the same species that will be lost when the build takes place. Tree planting will be implemented during the first planting season (spring) aftert the construction works have been completed.



1.

Ground Floor Plan

1:200

revisions & notes: A 09/04/14 ISSUED FOR CLIENT COMMENTS
B 28/04/14 ISSUED FOR PLANNING
C 26/08/14 AMENDMENTS ADDED. ISSUED FOR PLANNING

SAB
SAB
SAB

project: EXTENSION TO BELMONT
CASTLE
NURSING HOME
PORTSDOWN HILL ROAD
BEDHAMPTON

drawing name: Trees,Hard Landscaping,
Fences & Hedges Plan
status: Planning Application

date: April 14
scale: 1/200 @A1
drawn: SAB



Project No. 4055 drawing No. 1311 rev C