

Notes

GROUND WORKS:

All ground works and top soil to be in accordance with the project landscape specification

PLANTING ETC:

General plant stock to conform with BS 3936 and BS 5236 and planting to be undertaken in full accordance with the project landscape specification

All planting areas and isolated tree beds to be mulched with a medium grade bark mulch to a depth of 50mm

Foundations to lodges to be designed to take account of mature height of existing and proposed trees

MAINTENANCE:

Establishment maintenance for all planting for 1 year from planting date to include weed control and grass cutting







KEY :

- EXISTING TREES
- TREE PLANTING
- SHRUB PLANTING
- HEDGE PLANTING - lavandula
- GRASS Rolawn Minster Pro or similar shade tolerant grass seed.
- BLOCK PAVOURS Marshalls Keyblock Vintage - Bracken
- Existing Black Tarmac
- PAVING 400x400 Marshalls Saxon Textured Paving
- Gravel
- New Black Tarmac
- Bollard / Emergency Bulkhead — External Lighting

New Plant Schedule - Planter No. 1			
Shrubs	Species	Qty	Size
PJV	Pieris Japonica Veriegata	3	30-40cm
V	Vinca Minor	9	30-40cm
LH	Lavandula	4	40-60cm
PRR	Photinia x fraseri 'Red Robin'	3	40-60cm

Total - 19 plants

New Plant Schedule - Planter No. 2			
Shrubs	Species	Qty	Size
PJV	Pieris Japonica Veriegata	3	30-40cm
B	Buxus Sempervirens	5	30-40cm
V	Vinca Minor	15	30-40cm
EAB	Escallonia 'Apple Blossom'	4	40-60cm
LH	Lavandula	4	40-60cm
PRR	Photinia x fraseri 'Red Robin'	3	40-60cm
PS	Phyllostachys	5	40-60cm
ND	Nigella damascena	10	20-30cm

Total - 44 plants

New Plant Schedule - Planter No. 3			
Shrubs	Species	Qty	Size
HC	Houttuynia cordata	3	30-40cm
PJV	Pieris Japonica Veriegata	3	30-40cm
B	Buxus Sempervirens	5	30-40cm
V	Vinca Minor	15	30-40cm
EAB	Escallonia 'Apple Blossom'	4	40-60cm
LH	Lavandula	4	40-60cm
PRR	Photinia x fraseri 'Red Robin'	3	40-60cm

Total - 42 plants

New Plant Schedule - Planter No. 4			
Shrubs	Species	Qty	Size
PJV	Pieris Japonica Veriegata	3	30-40cm
V	Vinca Minor	9	30-40cm
LH	Lavandula	4	40-60cm
BM	Briza Mazim	3	40-60cm
PRR	Photinia x fraseri 'Red Robin'	3	40-60cm

Total - 22 plants

REVISION B PLANTING HAVING AMENDED - 02/01/14 - PG
REVISION A EXTENSIONS TO EXISTING BUILDING OMITTED - 04/12/13 - PG

SCALE 1/200

TITLE Residential Care Proposals Solent View Lodges

Formerly Hill Lodge
42, Bedhampton Hill Havant

DATE Oct. 2013

DETAIL Hard & Soft Landscaping Proposals

AUTHOR PG

DRAWING No 12/100/LP01

© COPYRIGHT

PETER GALLOWAY PARTNERSHIP
pgp ARCHITECTS
BURGAN HOUSE, 8/10 EAST STREET, HAVANT, HAMPSHIRE PO9 1AR
TEL 07808 483362
E-MAIL: peter@pgparchitects.co.uk