

27940 Homewell House, Havant
External Material Schedule:

Roof tiles:

9000 matching roof tiles have been reclaimed, currently being stored at the contractor's yard; this with the other salvaged roof tiles will be plenty to roof the whole development. (Physical sample submitted with current planning application)

Bricks:

Hanson – Autumn Glow, along with salvaged bricks from the demolition. (Physical sample submitted, panel constructed on site and agreed with current planning application)

Mortar:

Existing / repairs – NHL mortar
New build – natural mortar

Rain water goods:

Cast iron – colour Black

Windows:

Timber sash windows – colour white

Doors:

Entrance doors – 6 panel traditional timber doors to match existing – colour red, green and blue.

Paving:

Natural lime stone paving

External Lighting:

A lighting column with a lantern fitting to match the ones opposite the site has been shown within the extended grass area; this will have dusk till dawn sensor. These will be Square Victorian period lanterns – colour black. The lighting column will be 4000mm high and the external wall lights will be the same style. The bollard lights will also have dusk till dawn sensors.



Victorian square lantern, opposite site.