

Havant Borough Council
Planning Department
Public Service Plaza
Civic Centre Road
Havant
Hampshire,
PO9 2AX

Wednesday, October 24, 2012

Your Ref: APP/12/01011

FOA: Jack clark

Re: Tree Report

Dear Sirs

Further to your request for a tree report, I write in response to the tree to the north of the site, close to Long Copse Lane. I have attached a plan showing the tree referenced as T1.

The tree and roots will be protected during the works, with the following precautions undertaken:

Tree Protection

Tree protection fencing will be put in place for the duration of the building works to protect structure of tree as well as the roots. T1 is close to the construction and to enable access I would suggest ground protection to prevent compaction. In this case it is suggested that single thickness scaffold boards be placed on top of a scaffold frame and woodchip to prevent compaction of ground between the new structure and barrier fence.

Tree Protection Barriers

BS5837 requires that the RPA of all retained trees be protected from the effects of development by the installation of protective barriers. The protective barriers and should be installed and be maintained for the duration of the works.



Ground Protection

The temporary ground protection of T1 if required is recommended to be constructed of single thickness scaffold boards on top of either a driven scaffold frame or a compression resistant 100mm deep layer of woodchip.

Works Close to Tree

Any digging around the tree is to be carried out by hand. No use of heavy machinery will be allowed.

Yours Sincerely

Thomas Davies

Of Helyer Davies Architects Ltd

Helyer Davies Architects Ltd



Martin Helyer RIBA
For Helyer Design Ltd

1 The Old Flour Mill . Queen Street . Emsworth . Hampshire . PO10 7BT
mail@hdarchitects.co.uk www.hdarchitects.co.uk 01243 370 715