

16/05/11

11/00181 TPO

Roots, 24 Avenue Road, Hayling Island.

Oak – crown reduce by (1.5-2.5m) 15-25% and crown thin by 15-25%.

Proposal

Pruning as the tree branches obstruct the drive and public footpath.

Comments.

The English Oak in question is fine mature specimen located on the northern frontage of the property, immediately to the west of the front drive.

The Oak appears to have been pruned previously, and does currently encroach over the public highway and streetlamp.

The proposed works to reduce the canopy size of the Oak, and in doing so to clear the highway, appear to be reasonable at this time.

Consent Granted.

Roots, 24 Avenue Road, Hayling Island.

Mature English Oak located on the northern frontage of the property, immediately to the west of the front drive:

J01: BS3998:2010

J03: Crown reduce by no more than 1.5 metres overall.
Crown thinning in this case will be better achieved via the following operations:
Remove all deadwood, rubbing and crossing branches as necessary.
Clear the adjacent lamp column to vertically clear the top of the lamp column by no more than 1.0 metre, and to clear the sides of the lamp column by no more than 2.0 metres.

J09: 12 months from the date of this decision notice.

The applicant shall give at least 10 days notice of the proposed start date for the approved works.

David Harris
Arboricultural Consultant

Rek
can you respond
to supporting
e-mail too please.
Ta D