

**PROPOSED FIRST FLOOR ALTERATIONS AND DORMERS.
26, BACON LANE, HAYLING ISLAND, HANTS.**

FOR MR & MRS K. COCKER.

NOTE CHECK ALL MEASUREMENTS ON SITE PRIOR TO THE COMMENCEMENT OF WORK.

PROVIDE SMOKE DETECTORS TO BOTH FLOORS MAINS OPERATED AND INTERLINKED WITH BATTERY BACKUP.

ELECTRICAL INSTALLATION BY APPROVED CERTIFICATED ELECTRICIAN TO COMPLY WITH APPROVED DOCUMENT P. CERTIFICATE TO BE ISSUED ON COMPLETION OF WORK. BY COMPETENT APPROVED CERTIFICATED ELECTRICIAN USE ENERGY EFFICIENT LIGHT BULBS AND FITTINGS.

PROPOSED FIRST FLOOR

INSULATION TO BACKS OF STUDWORK EXPOSED TO ROOF SPACE 75MM CELOTEX GA BETWEEN STUDS THEN 12MM CELOTEX TB OVER AND 12.5MM PLASTERBOARD AND SET FINISH.

INSULATION TO SKILLINGS 100MM CELOTEX GA BETWEEN THEN 35MM CELOTEX TB OVER AND PLASTERBOARD AND SET MAINTAIN 50MM AIRGAP TO FELT.

INSULATION TO DORMER CHEEKS AND FACE 75MM CELOTEX GA BETWEEN STUDS AND 35MM CELOTEX TB OVER THEN PLASTERBOARD AND SET MAINTAIN AIR GAP TO FELT.

STUDWORK 100MMX50MM WELL BRACED TIMBER BUILT OFF DOUBLE JOISTS WHERE APPROPRIATE 30MM PLASTERBOARD AND SET BOTH SIDES INSERT 100MM GLASSWOOL BATTS MIN DENSITY 10KG/M3

EXISTING BLOCK WORK WALLS

date june 12
scale 1:50

FIRST

PETER J. WALKER MRICS
CHARTERED SURVEYOR
182 SEAFRONT, HAYLING ISLAND, HANTS.
PO11 9 AN

TEL: 02392 467571