ALL MEASUREMENTS TO BE CHECKED ON SITE.
ALL DIMENSIONS SHOWN IN MILLIMETRES.

SCALE
0m 1m 2m 3m 4m 5m 6m

Drawing modified by Paul Butcher - April 2012
to add scale and north arrow and outline retail area.

extg fire doors
form new opening
instal fire doors
and panic bolts
fire exit sign
2000
150 wall
ej
rp
MAIN CHURCH AREA
open grillage ceiling
with closed tiles where
shown on separate detail
3000
3500
LEADERS ROOM
ADMIN ROOM
full height wall
150 wall
enlarge opening
instal fire doors
panic bolts
ENTRANCE CORRIDOR
new fire exit sign
STORE
servery
KITCHEN
closed inset tile ceiling
5950
4750
STORE
3200
2100
up
dwn to gf.
ss.
LADIES
DISABLED WC
2800
1500
GENTS
joists
w.c.
basins
sprinkler inlet
high level
vent ducts
900 door
remove wall full height
LINK CORRIDOR
up 200
extg svp
new shop front
retail part of SU24
8.5 x 7.0m
UPPER MALL
SHOP
open grillage ceiling
YOUTH ROOM
no ceiling
high level
vent duct
new panic bolt
fire exit sign

See separate details for
- sprinkler system layout
- smoke detector system
- fire alarm system
- air conditioning / heating installation
- electrical layout / emergency lighting
- shop front designs

see drawing number 004/96
for general layout and detail notes

see drawing number 065/95
for existing plans / survey

PROJECT
UNITS MSU6 AND SU24
MERIDIAN CENTRE HAVANT HANTS
REVISED DETAIL PROPOSALS

CLIENT
HAVANT COMMUNITY CHURCH

David F. Young m.b.i.a.t., a.c.i.o.b.
Architectural Technologist and Building Consultant
19, The Causeway, Down End,
Fareham, Hants. PO16 8RN.
Tel/Fax: (01329) 232097

DATE Jan 1996	SCALE 1:50
DRAWN D.F. Young	DRG. NO. 003/96

WD REPROPOINT 2833