


**CONVERSION OF EXISTING GARAGE TO PROVIDE HABITABLE ACCOMMODATION.
16, FISHERY LANE, HAYLING ISLAND, HANTS.
FOR P. ADDY & D. ARCHER.**



STORE WINDOW TO BE INWARD OPENING AND FULLY OPENABLE FOR ESCAPE PURPOSES AND MAXIMUM 1 METRE SQUARE IN AREA.
BEDROOM WINDOW TO HAVE AN OPENING LIGHT MINIMUM 850X500MM IN SIZE FOR ESCAPE PURPOSES.

INSERT NEW PURPOSE MADE DOORS INTO EXISTING GARAGE DOOR OPENING MAINTAIN A CAVITY WALL BELOW WITH MINIMUM CAVITY 150MM TO DPC/FLOOR LEVEL TO BE AGREED WITH LA ON SITE.

date july 2012
scale 1:50

SINGLE STACK PLUMBING TO BS 5572 USE 75MM DEEP SEAL TRAPS SVP TO TERMINATE A MINIMUM OF 900MM ABOVE THE NEAREST OPENING WINDOW. PROVIDE RODDING ACCESS AT BASE OF STACK.

PROPOSED LAYOUT

PETER J. WALKER MRICS
CHARTERED SURVEYOR
182 SEAFRONT, HAYLING ISLAND, HANTS
PO11 9 AN

TEL: 02392 467571