KEY PROPOSALS

- Site Boundary
- Existing Trees
- A1 — Aquatic Planting to Existing Pond
- S2 — Shrub areas
- Grass
- W1 — Wildflower Meadow
- Proposed Tree Planting
- Proposed Slope
- S1 — Proposed Woodland Matrix (shrub and whip tree planting mix)
- MC — Proposed Memorial Copse (Trees to be planted by others)
- H2 — Proposed 1.8m h hedge
- H1 — Proposed 1.2m h hedge
- R1 — Proposed Sedum Planting to Roof
- Proposed 2m h Mound
- Proposed Swale

3no Fe
4No Cs
4No Cs
S1
S1
S1
17No Sc
17No Sc
Existing Hedge Retained
20lin m H1
20lin m H1
Existing Hedge Retained

DETAIL A

A1
MC
MC
12No Pa
7No Pn
8No Pn
S1
W1
MC
MC
S1
S1
2no Pn
1no Pn
45m2 S2
A1
21lin m Tb2
35lin m Tb1
2no Qr
27m2 S2
A1
1no Pn
1no Fe
H2
R1
H2
39m2 S2
52m2 S2
17m2 S2
15m2 S2
11No Pa
37m2 S2
H1
20lin m Tb2
2no Bp
15No Ac
H1
50lin m Tb2
10lin m Tb2
43lin m Tb2
3no Bp
2no Bp
2no Qr
3no Bp
1no Pn
1no Bp
W1
W1
W1
1no Pn
5no Fe
1no Qr
1no Qr
2no Fe
3no Pn
3no Fe
4No Cs
4No Cs
S1
S1

REFER TO DETAIL A

NOTES:

Read in conjunction with:
HED.923.201 Illustrative Masterplan
HED.923.202 Surfaces & Furniture Plan
HED.923.205 & 206 Fencing Plans
HED.923.207 & 208 Lighting Plans

All materials proposed or similar approved

PLANTING SCHEDULE

Tree Planting

Semi Mature Tree Planting

Cs 42No Castanea sativa
20-25cm girth, RB

Pa 19No Prunus avium 'Plena'
18-20cm girth, RB

Ac 15No Acer campestre
20-25cm girth, RB

Pn 24No Populus nigra
20-25cm girth, RB

Fe 10No Fraxinus excelsior
20-25cm girth, RB

Qr 6No Quercus robur
20-25cm girth, RB

Bp 11No Betua pendula (ms)
18-20cm girth, RB

Whip Tree & Shrub Planting Mix (S1)

Tree species

Single species planted in groups of 3 or 5 @ 5m centres as shown. All whips protected with plant guards.

Ac 28No Acer campestre (Field maple) 90-120cm h
Fe 28No Fraxinus excelsior (Ash) 90-120cm h
Qr 28No Quercus robur (English oak) 90-120cm h

Whip Tree & Shrub Planting Mix (S1)

(Approx 2300m2)

Shrub species

Shrubs planted randomly @ 1 per 1.5m2 in groups of 15-20. All shrubs protected with plant guards.

Cornus sanguinea (Dogwood) 45-60cm h (10%)
Corylus avellana (Hazel) 60-90cm h (15%)
Crataegus monogyna (Hawthorn) 60-90cm h (10%)
Euonymus europea (Spindle tree) 45-60cm h (10%)
Ilex aquifolium (Holly) 45-60cm h (5%)
Ligustrum vulgare (Wild Privet) 45-60cm h (5%)
Malus sylvestris (Crab Apple) 45-60cm h (10%)
Prunus padus (Bird Cherry) 45-60cm h (5%)
Salix caprea (Goat Willow) 45-60cm h (5%)
Sambucus nigra (Elder) 45-60cm h (15%)
Viburnum lantana (Wayfaring Tree) 45-60cm h (5%)
Viburnum opulus (Guelder Rose) 45-60cm h (5%)

Shrub Planting (S2) (Approx 72m2)

EVERGREEN/SEMI EVERGREEN

Buxus sempervirens (Common Box)
3L c/g 25-30cmh 10 per m2 UH: 50cm
Heuchera micrantha var. diversifolia 'Bressingham Bronze (Coral Flower) 2L c/g UH: 30cm
Lavendula angustifolia 'hidcote' (English Lavender) 3L c/g 25-30cmh 5 per m2 UH: 60cm
Rosemarinus officinalis (Rosemary) 3L c/g 25-30cmh 5 perm2 UH:150cm
Santolina incana (Cotton Lavender) 3L c/g 5per m2 UH: 60cm
Ajuga reptans 'Caitlins Giant' (Bugle) 2L c/g 9per m2 UH: 15cm
Hebe pinguifolia 'Pagei' (Hebe) 3L c/g 5per m2 UH: 70cm
Pinus mugo (dwwarf pine) 3L c/g 4per m2 UH: 50cm
Choisya ternata 'Sundance' (Mexican Orange Blossom) 3L c/g 5per m2 UH: 1m
Euonymus fortunei 'Silver Queen' (Spindle) 3L c/g 5per m2UH: 2m
Phormium tenax 'Purpureum' (New Zealand Flax) 10L c/g UH: 2m

HERBACEOUS PERENNIAL
Iris sibirica 'Snow Queen' (White Iris), 2L c/g 5 per m2 UH: 90cmh
Rudbeckia fulgida var. sullvantii 'Goldsturm' (Coneflower) 2L c/g UH: 60cm
Stipa tennuissima (Feather Grass) 3L c/g UH:60cm
Rosa 'Schneewittchen' (Perpetual flowering shrub-rose) 3L c/g 5 perm2 UH:1m
Miscanthus sinensis 'Zebrinus' (zebra grass) 3L c/g 5per m2 UH: 150cm
Verbena bonariensis (Verbena) 2L c/g 5 perm2 UH: 1m
Sedum telephium 'Autumn Joy' 3L c/g 5 perm2 UH:50cm

Aquatic Planting (A1)

Single species planted in groups of 3 or 5 at 4/sqm .

Nuphar albamesh pots, 2L
Nuphar lutea mesh pots, 2L
Juncus effusus c/g,1L
Iris pseudacorus c/g,1L

Bulb Planting

Planted in groups of 50-100

Galanthus nivalis (snowdrops)
Narcissus pseudonarcissus (daffodils)
Hyacinthoides non-script (bluebells)

Hedge Planting

All shrubs protected with plant guards.

Tb1 147No Taxus bacata (Common Yew)
Preformed hedging 1.8m h planted as a double staggered row @ 3 per lin m
Tb2 984No Taxus bacata (Common Yew)
900-1.2mh planted as a double staggered row @ 4 per lin m

Native Hedge Mix Planting (H1)

Planted randomly @ 4 per lin m in groups of 15-20 in a double staggered row. All shrubs protected with plant guards.

Acer campestre (Common Field Maple) 60-80cm h (30%)
Ulex europaeus (Common Gorse) 60-80cm h (15%)
Fagus sylvatica (Common Hazel) 60-80cm h, (20%)
Ilex Aquifolium (Common Holly) 60-80cm h, (15%)
Prunus spinosa (Common Blackthorn) 60-80cm ht (20%)

Wildflower Mix (W1)

British Seed House WFG 7 Free Draining Sandy Soil Mix
4g per m2. 4000m2 in total

Grass Seed Mix (G1)

Grass Seed for General Grass Area
British Seed House A9 General Outfield Mix
25g per m2

Green Roof (R1) (251m2)

Sedum

CONSULTANTS

H E D
Hyland Edgar Driver

Landscape Architects and Urban Designers

One Wessex Way Colden Common Winchester Hampshire SO21 1WG
Telephone 01962 711600 Facsimile 01962 713945

LAND AT BARTON'S ROAD

FOR PLANNING

DRAWING TITLE
PLANTING PLAN

REVISION
-

DRAWING NUMBER
HED.923.203

REV
-

SCALE
1: 500 @ A1

DRAWN
JW

DATE
MAY 11

CHECKED
-

DATE
-

APPROVED
-

© Copyright Reserved