Existing Hedging
to remain

Existing post and
rail fence

Reinstated
to a grass
Paddock

Drainage trench
to be filled in with
soil to existing
levels

Gate

A1

Paddocks

RPA Radius
10.2m to
BS5837:2005

Existing post and
rail fence

RPA to be protected
with Cellweb

Gate

Crushed tarmac
driveway over laid
with gravel laid to
existing levels

Hollybank
Cottage

T1

A2

A3

Grass

Permitted new
stables

Grass

RPA Radius
6.0m to
BS5837:2005

T7

T6

Grass

Grass

Grass

Five-bar wooden
gate

T3

T4

T5

T2

RPA Radius
3.0m to
BS5837:2005

Native Planting

Post and
rail fence

RPA Radius
3.0m to
BS5837:2005

Native Planting
Crateagus monogyna (Hawthorn) 75%
Prunus spinosa (Blackthorn) 10%
Corylus avellana (Hazel) 5%
Ilex aquifolium (Holly) 2%
Acer campestre (Field maple) 2%
Rosa canina (Dog Rose) 2%
Euonymus europeus (Spindle) 2%
Viburnum opulus (Guilder rose) 2%
Vibutnum lantana (Wayfaring tree) 2%
Planted at 45cm spacings

Surface water
cut off channel

Tarmacdry porous ashphalt
on granular sub base to form
a non-migratory finish. Overall
depth 320mm from finish to
subgrade

RPA Radius
3.0m to
BS5837:2005

Post and
rail fence

RPA Radius
3.0m to
BS5837:2005

RPA Radius
6.0m to
BS5837:2005

Long Copse Lane

Long Copse Lane

Scale 1-200

0 1 2 3 4 5 6

Note
This drawing may be scaled for planning purposes only. For all other purposes dimensions must be checked on site and not scaled from the drawing

A1 Existing crushed tarmac
to be removed and reinstated
as grass to existing levels.
A2 Piles of crushed tarmac
to be spread out to construct
driveway to existing levels
A3 Piles of rubble and crushed
tarmac to be used to construct
driveway to existing levels
All material to be used on site.

Site Address Long Copse Lane Emsworth	
Title: Landscape Plan	
Date : 24.08.11	Client : Madgwick
Scale : 1-200 @ A2	Drawing No 0134-11

Ordance Survey (c) Crown Copyright 2011. All rights reserved Licence number 100020449