

A) All plant stock to be in accordance with relevant British Standard 3936 part 2.
B) Handling and planting: Plant material shall be handled, supplied and planted in accordance with the Committee on Plant Supply and Establishment's publications. In all cases plant material should comply with the relevant British Standards.
C) Species, plants to be supplied to be exactly true to name.
D) Delivery of plants. Ensure that adequate protection is given to all plants and their root systems to preclude failure due to lack of moisture or exposure during transportation to the site, and between delivery and planting.

Cultivate by hand or mechanical means in order to create a workable tilth ready for planting. During the above operation Enmag granular fertiliser will be incorporated into the topsoil.

- 1) Tree Pits: Excavate in positions marked on the drawing a circular planting pit measuring 900mm diam x 600mm deep. The base of the pit should be broken up to a depth of 150mm.
- 2) Backfill: Should comprise of excavated material and 20L Tree and Shrub Planting Compost evenly, well firmed around the root and finished soil level should correspond with water mark of tree. Any surplus material to be removed from area.
- 3) Staking: Each tree to be supported by a straight, round, treated stake well driven and cleanly cut off below the crown of the tree. Secure with rubber ties and spacer blocks at the top and bottom of the stake.
- 4) Pruning: Following planting, the crown of each tree is to be lightly pruned to remove any damaged twigs or buds to promote even vigorous growth.

- 1) Set out: Evenly within the planted areas in accordance with the drawing and schedule giving due consideration to future growth.
- 2) Planting: Should be in a pit that comfortably accommodates the root or container. Each plant to be placed in an upright, well balanced stance and return backfill. Well heel-in to ensure that no air pockets are left and leave plants firm.
- 3) Pruning: Deciduous material to be cut back by 30% to encourage rapid, bushy establishment.
- 4) Completion: Beds should be edged neatly, kerbs and adjacent areas forked over and left neat and tidy.

Place a 50mm layer of bark mulch over all planted areas. Fork over and leave neat and tidy.

a1 scale 1:100	a3 scale 1:200	27863 PD126	rev A
-------------------	-------------------	-------------	----------

Proposed Site Layout