Mr.Kim.Gifford
Gifford Tree Service
07831 488 456

Tree Survey Schedule

14 Laburnum Grove
Hayling Island

Ref/Tag No.	Species	Hgt (m)	SD (mm)	N-E-S-W (m)	Crown Clearance	Age Class	P.Cond	S.Cond	ERC	Category grading	Recommendations	Radius	RPA	Sq. Sides
T1	Chamecyparis	7	300	2,2,2,2	2	M	Good	multi stemmed	20	C	will require pruning in the future	3.6	40.7	6.4
T2	Cupressocyparis	12	500	4,4,4,4	3	M	Good	No external defects	41+	C	will require pruning in the future	6.0	113.1	10.6
T3	Macrocarpa	12	600	5,5,5,5	3	M	Good	No external defects	42+	C	will require pruning in the future	7.2	162.9	12.8
T4	Malus	10	400	5,5,5,5	3	M	Good	No external defects	10-20	C	will require pruning in the future	4.8	72.4	8.5