Amended Plan

A. Trees:

Species	Typical Specification
Prunus avium 'Plena'	16-18cm girth
Prunus serrula	Multistem 2-2.5m

B. Shrubs and Ground Cover:

Species	Height/Spread cm	Min Break	Min Pot size	Plant M^{-2}
Cistus 'Silver Pink'	30-40	4/Bushy	3L	4
Cotoneaster microphyllus	30-40	3/Bushy	3L	4
Hebe albicans 'Red Edge'	40-60	9/Bushy	10L	1
Lavandula angustifolia 'Hidcote'	30-40	7/ Bushy	5L	2
Perovskia 'Blue Spire'	30-40	3/ Bushy	3L	3

C. Specimen shrubs:

Phormium 'Bronze Baby'	40-60	C 5/Branched	10L	1

D. Herbaceous:

Geranium macrorrhizum 'Bevan Variety'	Clump	3L	4
Heuchera 'Palace Purple'	Clump	3L	6
Pennisetum alopecuroides 'Hameln'	Clump	3L	6
Stachys byzantica 'Silver Carpet'	Clump	3L	6
Verbena bonariensis	Clump	3L	6

E. Hedge planting:

Escallonia rubra 'Crimson Spire'	60-80cm high	C 4/Bushy	0.5m centres

AMENDED/ADDITIONAL PLAN
RECEIVED
0 9 JUL 2010
DIRECTOR OF ENVIRONMENT
HAMPSHIRE COUNTY COUNCIL

PERMIT

MILL HILL CHILDRENS CENTRE

PLAYGROUND

CAR PARK

MILL ROAD

Existing grass to be made good as necessary

Pennisetum alopecuroides 'Hameln'

Geranium macrorrhizum 'Bevan Variety'

1 Nr Prunus avium 'Plena' 16-18cm girth

Cistus 'Silver Pink'

Phormium 'Bronze Baby'

Pennisetum alopecuroides 'Hameln'

Geranium macrorrhizum 'Bevan Variety'

Hebe albicans 'Red Edge'

Pennisetum alopecuroides 'Hameln'

Lavandula 'Hidcote'

Escallonia 'Crimson Spire'- 0.5m centres

1 Nr Prunus serulla 2-2.5m high -multistem

LP

Hebe albicans 'Red Edge'

Verbena bonariensis + Stachys byzantica 'Silver Carpet'

Cistus 'Silver Pink'

Heuchera 'Palace Purple'

Perovskia 'Blue Spire'

Cistus 'Silver Pink'

Geranium macrorrhizum 'Bevan Variety'

Perovskia 'Blue Spire'

Cotoneaster microphyllus

Heuchera 'Palace Purple'

Hebe albicans 'Red Edge'

3 Nr Prunus avium 'Plena' 16-18cm girth

Existing hedgerow to be retained

Existing grass to be made good as necessary

LEGEND
EXISTING
Existing vegetation to be retained
PROPOSED
Buildings to HCC architects details
Multistem tree planting secured with double timber staking and cross bar as specified Q31
Hedge planting as specified Q31
Shrub divisions as specified Q31
Amenity grass turf as specified Q30
Seed mixture as specified Q30

NORTH

Rev:	Date:	Amendment	Name:	Checked:
A	08.07.10	Add trees to boundary	DR	NJ

Drawing Based Upon: HCC Topo survey

Status: For Planning

Notes: Contractors are not to scale from this drawing. All dimensions to be checked on site and any discrepancies, ambiguities and/or omissions between this drawing and information given elsewhere must be reported to this office. If in doubt, ask.

RPS

Client: Hampshire County Council

Project: Mill Hill Childrens Centre
Landscape Improvements

Title: Planting Plan

Date: 05/10 Scale: 1:100 Paper Size: A1

Drawn: DR Checked: NJ Job Ref: JSL1759

Drawing Number: 500 Rev: A

www.rpsgroup.com