KEY:

Proposed new lighting columns to be provided.

Existing lighting columns to be re-headed.

NOTES:

For further lighting information and specification refer to Abacus drawing, design ref LS19189__1

Existing Store Parking:	
Standard bays	488
Disabled bays	20
Parent & Child bays	14
Trolley bays	10
Total	532
Community Centre Parking:	
Standard bays	26

Proposed Store Parking:	
Standard bays	487
Disabled bays	20
Parent & Child bays	14
Trolley bays	10
Total	531
Community Centre Parking:	
Standard bays	26

Rev	Date	Amendment		
A	12.4.11	Walkway extended to new crossing by others	PF	TT

Allotment Gard

EVERGREEN CLOSE

FOREST END

FIRE STATION

Existing banner display board to be relocated as shown to suit new proposed walkway

New proposed walkway to link with a new proposed crossing by others (The new crossing will form part of an application for an adjacent project).

Remove existing trolley bay and replace with new to accommodate new walkway.

New RC slab for recycling area to be provided.

MAUREPAS WAY

Existing island to be narrowed to allow widening of existing road.

Recycling

SUB STATION

NO ENTRY

EXIT

Service Yard

Existing walkway to be made flush. Bollards installed as required.

ONE WAY

5No. NEW CONDENSER UNITS.

4800

3500

SMOKING SHELTER

TB

LONDON ROAD

CHAPEL LANE

SWISS ROAD

Section of existing island to be removed to allow for re-allignment of pedestrian walkway

ASDA SUPERSTORE

COMMUNITY CENTRE

Public Toilets

Community Centre Parking

Golden Court

PORTLAND ROAD

CLOCK HOUSE

St George's Walk

MAUREPAS WAY

Project No	Dwg No	Rev
0338	SP01	A

Dwg Title: Site Plan

Date	Scale
Jan 2011	1:500@A1
LC	TT

Project: Asda Waterlooville

Client: Asda Stores Ltd

Gleneagles Project Services
Suite 11
1A Woodsome Park
Fenay Bridge
Huddersfield
HD8 0JW
Tel: 01484 606949 Fax: 01484 609533
E-mail: val.hudson@gps-ltd.co.uk

DO NOT SCALE FROM THIS DRAWING, IF IN DOUBT ASK
© THIS DRAWING MAY NOT BE COPIED WITHOUT PRIOR WRITTEN PERMISSION