PERMIT

DO NOT SCALE FROM THIS DRAWING
ALL DIMENSIONS TO BE VERIFIED BY THE CONTRACTOR ON SITE

N

Key

Boundary Treatment	
	1.8m high close-boarded stained timber fence with 0.3m high concrete gravel boards and concrete post.
	1.2m high Plastic coated chain link fence and concrete post.
	1.8m high close-boarded stained timber fence with 0.15 high concrete gravel boards and concrete post.
	0.9m High Dwarf wall and render panel see dwg 520

Gate

Water Butt
1-2 Bedroom home with private garden am minimum 150Litres
3+ Bedroom home with private garden am minimum 200Litres

Compost Bin
1 - 4 Person Dwelling with private garden a minimum 220Litres
5+ Person Dwelling with private garden a minimum 330Litres

Rotary Dryer (Provided)

Refuse Store / Bins with suitable hardstanding under.

Paving Slabs 450 x 450mm colour, grey

Garden shed see drawing 9-01

03
Type A

04
Type C

05
Type C

07
Type A

06
Type A

Driveway surface and construction to engineers drawing and specification

New Footpath surface and construction to engineers drawing and specification

Existing extent of ranelagh road

Existing driveways and footpath to be maintained

New footpath to be into existing footpath

RANELAGH ROAD

BROCKHAMPTON ROAD

WSV

HAVANT BOROUGH COUNCIL
09 MAR 2011
RECEIVED

REV	DESCRIPTION	DATE	INT	CHD
C2	Regar garden fences changed to 1.8m close boarded	08.03.11	KJW	KW
C1	Garden & floor plans updated	22.11.10	KJW	KW
T1	Tender Issue	14.07.10	PG	
STATUS	CONSTRUCTION			

calfordseaden
construction & property consultants

Client
Leadbitter

Project
Ranelagh Road, Havant
Hampshire

Title
Site layout 2 of 5
Plots 4 - 7

Scale	Date	Drawn	Checked
1:100 @A1	14.07.10	PG	KR

Project No:	Drawing No.	Revision
S100044	102	C2

Calford House, Wessex Business Park, Wessex Way
Colden Common, Winchester, Hampshire SO21 1WP
T 01962 718300 F 01962 718350
E winchester@calfordseaden.co.uk W www.calfordseaden.co.uk